



**REGULAR MEETING OF COUNCIL
Tuesday, February 23, 2021 @ 3:30 PM
George Fraser Room, Ucluelet Community Centre,
500 Matterson Drive, Ucluelet**

AGENDA

| | Page |
|---|--------|
| 1. CALL TO ORDER | |
| 2. ACKNOWLEDGEMENT OF FIRST NATIONS TERRITORY | |
| Council would like to acknowledge the Yuułu?iŋ?ath First Nation, on whose traditional territories the District of Ucluelet operates. | |
| 3. NOTICE OF VIDEO RECORDING | |
| Audience members and delegates are advised that this proceeding is being broadcast on YouTube and Zoom, which may store data on foreign servers. | |
| 4. LATE ITEMS | |
| 5. APPROVAL OF AGENDA | |
| 6. UNFINISHED BUSINESS | |
| 7. MAYOR'S ANNOUNCEMENTS | |
| 8. PUBLIC INPUT & DELEGATIONS | |
| 8.1 Public Input | |
| • Public input via Zoom. | |
| • Public input via communityinput@ucluelet.ca . | |
| 8.2 Delegations | |
| • Ursula Banke, Island Work Transitions Inc. Re: WC Senior Services - Better at Home Program (UWLM) D - WC Senior Service Network | 3 - 6 |
| • Ursula Banke, Island Work Transitions Inc. WC Local Labour Market Information Project D - WC Business and Workforce Strategy | 7 - 10 |
| 9. CORRESPONDENCE | |
| 10. INFORMATION ITEMS | |
| 10.1 CBT 2021 Grant Opportunities <i>Rebecca Hurwitz, Executive Director, Clayoquot Biosphere Trust</i> | 11 |

[2021-02-05 CBT granting update](#)

11. COUNCIL COMMITTEE REPORTS
 - 11.1 Councillor Marilyn McEwen
Deputy Mayor January - March 2021
 - 11.2 Councillor Lara Kemps
Deputy Mayor April - June 2021
 - 11.3 Councillor Jennifer Hoar
Deputy Mayor July - September 2021
 - 11.4 Councillor Rachelle Cole
Deputy Mayor October - December 2021
 - 11.5 Mayor Mayco Noël
12. REPORTS
 - 12.1 CBC License Agreement Renewal 13 - 23
Joseph Rotenberg, Manager of Corporate Services
[R - CBC Lease](#)
 - 12.2 Ucluelet and Area Childcare Society Letter of Support for Co-op Community 25 - 29
Space Grant
Abby Fortune, Manager of Recreation & Tourism
[R - Daycare Letter of Support](#)
13. LEGISLATION
 - 13.1 Ucluelet Official Community Plan Bylaw 31 - 190
Bruce Greig, Manager of Community Planning
[L - OCP Bylaw](#)
14. OTHER BUSINESS
15. QUESTION PERIOD
 - 15.1 Questions via Zoom.
 - 15.2 Questions via communityinput@ucluelet.ca.
16. CLOSED SESSION
 - 16.1 Procedural Motion to Move In-Camera
THAT the meeting be closed to the public in order to address agenda items under Section 90(1) (g) of the Community Charter related to litigation or potential litigation affecting the municipality.
17. ADJOURNMENT



DISTRICT OF UCLUELET

Request to Appear as a Delegation

All delegations requesting permission to appear before Council are required to submit a written request or complete this form and submit all information or documentation by 11:00 a.m. the Wednesday preceding the subsequent Council meeting. Applicants should include the topic of discussion and outline the action they wish Council to undertake.

All correspondence submitted to the District of Ucluelet in response to this notice will form part of the public record and will be published in a meeting agenda. Delegations shall limit their presentation to ten minutes, except by prior arrangement or resolution of Council.

Please arrive 10 minutes early and be prepared for the Council meeting. The Mayor (or Acting Mayor) is the chairperson and all comments are to be directed to the chairperson. It is important to address the chairperson as Your Worship or Mayor Noël.

The District Office will advise you of which Council meeting you will be scheduled for if you cannot be accommodated on your requested date. For more information contact the District Office at 250-726-7744 or email info@ucluelet.ca.

Requested Council Meeting Date: Feb 23, 2021

Organization Name: WC Senior Services Network

Name of person(s) to make presentation: Ursula Banke

Topic: WC Senior Services - Better at Home Program (UWLM)

Purpose of Presentation:

Information only

Requesting a letter of support

Other (provide details below)

Please describe:

Contact person (if different from above): Ursula Banke

Telephone Number and Email: ubanke@avemployment.ca (250-725-8805)

Will you be providing supporting documentation? Yes No

If yes, what are you providing?

Handout(s)

PowerPoint Presentation

Note: Any presentations requiring a computer and projector/screen must be provided prior to your appearance date. The District cannot accommodate personal laptops.

WC Senior Services Network (Better at Home)

TO: Mayor & Council, District of Ucluelet

FROM: Ursula Banke, Community Liaison, Island Work Transitions Inc.,

EMAIL: ubanke@avemployment.ca

DATE: Jan 29, 2021

SUBJECT: West Coast Senior Services Network (Better at Home Program)
Presentation & Request for a Letter of Support (Feb 23, 2021)

Dear Mayor and Council

As Community Liaison for Island Work Transitions Inc., I have been working with community organizations, facilitating the building of networks within our region; creating strategies and developing projects that will stabilize and diversify the regional economy here on the west coast. Ultimately, our goal is to align workforce supply and demand with our region's sustainable development goals for the long term.

In 2019, I was appointed to the Council of Advisors to the Office of the BC Seniors' Advocate. I became a member of their Rural & Remote Committee and continue to lobby on behalf of our Rural & Remote communities on the west coast.

I am here today, to present on behalf of the WC Senior Services Network (WCSSN).

In spring of 2020, the WCSSN organized into a coalition of senior service providers. Taking a collaborative approach, we have developed a strategy to bring the Better at Home Program to the west coast region.

The Better at Home Program is a province-wide program funded by the Government of BC and managed by the United Way of the Lower Mainland (UWLM) to help seniors remain independent at home and stay connected with their community.

The Better at Home Program supports seniors who wish to age in place with dignity, stay socially connected and prevents social isolation, especially among older adults who are most vulnerable. The Better at Home program provides a range of non-medical home support services such as housekeeping, grocery shopping, home repair, friendly visiting, yard work and transportation to appointments. Services are delivered through local non-profit organizations by volunteers and paid workers.

Community-based services vary from community to community and are designed to complement existing services. Volunteers, contractors and paid staff from local non-profit organizations are trained to provide Better at Home services.

Ursula Banke, Community Liaison & Project Facilitator
ubanke@avemployment.ca

Page 1 of 3

WC Senior Services Network (Better at Home)

What are the common standards to all Better at Home programs?

Although there are many differences among Better at Home programs, there are also commonalities:

- service fees are established on an income-based sliding scale which ensures that services are free for low income seniors, and market rate for seniors with an income above the BC average.
- all volunteers providing services directly to seniors must have a criminal record check.
- programs have a local Advisory Committee for guidance, advocacy, and to help support the integration of the program into community and be responsive to seniors' needs.
- programs submit progress reports to the provincial office to monitor performance.
- program coordinators engage in a Community of Practice which includes sharing learning activities, discussing best practices on an online portal, and meeting annually for training opportunities and participation in collective dialogue. These activities help develop capacity of each local program to best serve and support the older adults in BC.

Who pays for Better at Home?

The Government of BC, through the Ministry of Health, provides funding to the United Way of the Lower Mainland to manage the Better at Home program across BC. Individual community organizations will also accept donations, raise funds, and encourage volunteer participation. Older adults who receive Better at Home services may pay a fee based on their income. Some services may be free. These fees-for-service are fed back into the local program in order to serve more seniors.

Funding is reserved for each local program based on the demographics of the community, such as the number of seniors residing in that community, income of seniors, etc. The funding allocation will be different in each community because of their distinct community characteristics.

Next Steps

The United Way Lower Mainland is aware of our interest in bringing the Better at Home program to the west coast. We are organized, agreed on a strategy and we are 'ready' for when UWLM opens their next call for Better at Home Program applications; scheduled to come out in the late spring.

What do we need?

On behalf of the WC Senior Services Network, I am asking Mayor and Council for a 'Letter of Support' in our efforts to bring the Better at Home Program to the west coast region.

Thank you for your time and consideration to support this regional initiative.

Ursula Banke

Ursula Banke, Community Liaison & Project Facilitator
ubanke@avemployment.ca

Page 2 of 3

WC Senior Services Network (Better at Home)

Better at Home Program – ACTION PLAN 2021 - Revised Nov 26/20

- a) **Project Lead #1** - Coastal Family Resources Coalition (registered CBT non-profit status)
Project Alternate #1 - Pacific Rim Hospice Society (registered non-profit status)
Project Alternate #2 - WC Community Resources Society (registered non-profit status)
 (These 3 organizations have proven successful delivery of projects and programs within the region)
- b) **Advisory Group:** * new
- Tarni Jacobsen – Pacific Rim Hospice Society
 - Barb Gudbranson – District of Ucluelet – Parks & Rec
 - Lisa Morgan – Toquaht Nation - Director of Community Services
 - Rachelle Cole – BC Emergency Services
 - Faye Missar – Coastal Family Resources Coalition
 - Jane Osborne – BC Community Response Network
 - Janine Croxall – Pacific Rim Hospice Society
 - Margaret Morrison – WC Community Resources Society
 - Marcie DeWitt – Alberni Clayoquot Health Network
 - Ursula Banke – Island Work Transitions Inc., (WCSS Network Facilitator)
 - *Hilary O'Reilly – District of Tofino - Recreation (replacement for Pam Zwicker)
- c) **A Regional Model** (8 communities, social enterprise, volunteers) CFRC and WCCRS deliver programs & services through a regional model
- d) **Youth** (intergenerational model) Better with a Buddy, NCN Warriors (boys), Grade 12 Tech class
- e) **Geographic scope** - Same as CBT region – include all communities (From Hot Springs to Macoah)
- f) **Demographics** Program Beneficiaries - All persons, aged 55 and over, living in this region
- g) **Needs Assessment** – Supply/Demand Senior Services - Gap Analysis (WIP - PRHS)
 Research to include senior services supply/demand within all communities
- h) **Letters of Support** (Div of Family Practices, FNHA) and from various stakeholder communities and/or organizations

IMPORTANT MESSAGES (Better at Home - United Way Lower Mainland)

Nov. 27, 2020

Email message from Cathy Holmes (UWLM Better@Home)

“If funding is coming your way, it won't be until sometime after the new fiscal in April. My suspicion is that sometime in the middle of 2021 you potentially could be up for expansion... no guarantees merely hopes and I have fervently expressed the need in your two communities ...”

Ursula Banke, Community Liaison & Project Facilitator
 ubanke@avemployment.ca

Page 3 of 3



DISTRICT OF UCLUELET

Request to Appear as a Delegation

All delegations requesting permission to appear before Council are required to submit a written request or complete this form and submit all information or documentation by 11:00 a.m. the Wednesday preceding the subsequent Council meeting. Applicants should include the topic of discussion and outline the action they wish Council to undertake.

All correspondence submitted to the District of Ucluelet in response to this notice will form part of the public record and will be published in a meeting agenda. Delegations shall limit their presentation to ten minutes, except by prior arrangement or resolution of Council.

Please arrive 10 minutes early and be prepared for the Council meeting. The Mayor (or Acting Mayor) is the chairperson and all comments are to be directed to the chairperson. It is important to address the chairperson as Your Worship or Mayor Noël.

The District Office will advise you of which Council meeting you will be scheduled for if you cannot be accommodated on your requested date. For more information contact the District Office at 250-726-7744 or email info@ucluelet.ca.

Requested Council Meeting Date: February 23, 2021

Organization Name: Island Work Transitions Inc.

Name of person(s) to make presentation: Ursula Banke (Project Facilitator)

Topic: WC Local Labour Market Information Project

Purpose of Presentation: Information only
 Requesting a letter of support
 Other (provide details below)

Please describe:

Contact person (if different from above): _____

Telephone Number and Email: _____

Will you be providing supporting documentation? Yes No

If yes, what are you providing?

Handout(s)

PowerPoint Presentation

Note: Any presentations requiring a computer and projector/screen must be provided prior to your appearance date. The District cannot accommodate personal laptops.

TO: Mayor & Council, District of Ucluelet
FROM: Ursula Banke (Project Facilitator)
 Island Work Transitions Inc.
DATE: Feb 17, 2021
SUBJECT: Presentation 2 - WC Business & Workforce Strategy – Post Pandemic Recovery Plan

Dear Mayor and Council:

1. **WC Business & Workforce Strategy & Post Pandemic Recovery Plan** (Region as a Whole)

It was in November 2020 that Mayor and Council sent a letter of support for the project “WC Local Labour Market Information Project”. The WCLLMI Project was developed in 2 phases. Island Work Transitions Inc., (IWT) was identified by the Stakeholders’s Advisory Group to be the ‘lead’ to the WC LLMI Project.

Phase 1 (short term pilot) West Coast Local Labour Market Information Project
 Strategy – Dist of Ucluelet submit application to

Clayoquot Biosphere Trust – Community Development Grant (\$5000)

Phase 2 (long term – whole region) West Coast Business & Workforce Strategy – Post
 Pandemic Recovery Plan

Strategy – Dist of Ucluelet be identified as a partner to the project; furthering the goals
 & objectives of the Ucluelet’s Economic Development Strategy.

Two grant opportunities have recently evolved.

a) Clayoquot Biosphere Trust Community Development Grant (\$5000 max)

Issue – CBT does not grant to For Profit even if the project is non-profit

The project needs a qualifying partner such as District of Ucluelet, as lead applicant. IWT
 staff would assist District of Ucluelet staff in preparation of the application and
 District staff would submit the application as partner to the project.

b) Employment & Social Development Canada - Sectoral Initiatives Program

\$2.5 M per year for 3 years (application deadline March 4, 2021)

Request to Mayor & Council

To write a letter that outlines the benefits that a project partnership would bring to social
 & economic development recovery in Ucluelet; outline contribution of cash and/or
 inkind to be determined as budget allows; agrees to participate & support the goals,
 objectives & activities as outlined in the project “West Coast Regional Business &
 Workforce Strategy - Post Pandemic Recovery Plan (see following pages for Project
 outline) Important Note - Project applicant’s partnership letters must accompany
 application – application deadline March 4/21.

Kind regards,

Ursula Banke, WC LLMI Project Facilitator,

Community Liaison / Employment Centre Coordinator

Island Work Transitions Inc., (dba Alberni Valley Employment Centre)

381 Main Street , P.O Box 1050, Tofino, BC V0R 2Z0

Ph: 250-725-8805 - Fax 250-725-2845

Email: ubanke@avemployment.ca

**West Coast Regional Business & Workforce Strategy - Post Pandemic Recovery Plan
Presentation to Funding & Non-funding Partners - Project Outline**

PROJECT GOALS (coordinate 4 Pillars into Regional Workforce Recovery Strategy Goals)

1. **WORKFORCE** - Meet specific 'needs of workforce to support economic recovery of all sectors within each community in our region of Canada' (SIP 1)
2. **EMPLOYERS** – facilitate the development of 'sectoral solutions that meet the local & regional workforce challenges while meeting the needs of employers' (SIP 2) and includes 'solutions for Employers to address & respond to emerging challenges as well as opportunities in the business community' (SIP 3)
3. **EDUCATION & SKILLS TRAINING/UPGRADING** – Develop & implement 'sectoral solutions to address gaps/needs in education and skills training/certification' (SIP 3)
4. **REGIONAL ALIGNMENT WITH NATIONAL STRATEGY** – build capacity to align region with Canada's 2030 Agenda National Strategy - Goal 8: Promote sustained, inclusive and sustainable economic growth, full and productive employment and decent work for all

PROJECT OBJECTIVES

1. **OBJECTIVE (Goal 1)** - Develop a sectoral labour market information database (LMI tool) to measure, monitor & report status of the local & regional Workforce, identify gaps and address supply & demand issue.
 - ACTIVITY – 1**
 - a) Work with stakeholders to establish a set of sectoral indicators to include, but not limited to, measuring individual communities
 - unemployment rate, average hourly wage, gaps between groups,
 - proportion of youth (aged 18-24) not in education, employment or training
 - proportion of older adults (aged 55+) needing/wanting to work but unable to keep up with physical demands
 - GDP per capita - regional
 - b) Develop a database (LMI tool) for individual communities and the region as a whole
 - c) Collect & input data, measure, monitor & report regional statistical information
2. **OBJECTIVE – (Goal & 2)** Sectoral solutions for Employers & Workforce (demand & supply)
 - ACTIVITY - 2**
 - a) Work with local business organizations to implement Business Retention & Expansion (BRE) program and incorporate individual post pandemic recovery strategies
 - b) Create BRE database to coordinate, track changes, provide information that supports informed-decision making, develop and test mitigation strategies, revise solutions

3. **OBJECTIVE (Goal 3)** - Develop solutions for education & skills training for worker transition
ACTIVITIES – 3 sectoral needs/issues & response strategies –
Partner - North Island College

4. **OBJECTIVE – (Goal 4)** to align with Canada’s 2030 Agenda National Strategy - Goal 8: Promote sustained, inclusive and sustainable economic growth, full and productive employment and decent work for all.
ACTIVITY - 4
 - a) Establish a **Regional Workforce Planning Board** with a mandate to align with the goals of Canada, Employment and Social Development Canada and its Sectoral Initiatives Program and continue the regional work to:
 - i. Address specific needs of the workforce and support economic recovery of all sectors within the region
 - ii. Develop & implement sectoral solutions to meet the workforce challenges and needs of employers
 - iii. Develop & implement sectoral solutions to address gaps/needs in education and skills training/certification
 - b) Project Continuity – continue with project activities including data/gap analysis and needs assessments

STAKEHOLDER PARTNERSHIPS (needed to support the project goals)

1. Workforce – IWT, NETP
2. Business – Chambers of Commerce, NEDC, CFAC
3. Education & Skills Training – NIC
4. Government - municipal, regional, provincial, federal

PROJECT BENEFITS:

- **A Transferrable Model** - A regional & collaborative approach to coordinate post pandemic workforce recovery and workforce alignment strategies
- **Organization, Coordination & Alignment** of post pandemic recovery strategies – measure, monitor, evaluate fluctuations, identify gaps, develop alignment strategies that address business & workforce supply & demand issues.
- Coordination of regional strategies, collaboration and future partnership opportunities



February 5, 2021

Dear Mayor and Council,

I am writing on behalf of the CBT Board of Directors to ensure that the District of Ucluelet Council is aware of CBT's 2021 grant opportunities. Between now and March 22nd, we are supporting communities and organizations to access funding from the following grant areas:

- Youth & Education (up to \$5K)
- Community Development (up to \$5K)
- Research & Environment (up to \$5K)
- Arts & Culture (up to \$5K)
- Biosphere Research (up to \$20K)
- Vital Grants (up to \$20K)
- Neighbourhood Small Grants (note: applications are from March 1st – April 15th)

We've been listening to the communities we serve and we are reflecting on CBT's granting practices, re-envisioning our approach with the values of equity. Given the pandemic context, we are committed in the immediate term (i.e. this year) to being flexible and adaptive in our granting practices to ensure that funds are accessible where they're most needed in the region. Looking ahead, we are excited to work with our board, volunteers and the communities we serve to make CBT granting more equitable in the long term. We are committed to ensuring CBT grants reduce inequities in the region not only through the projects they fund, but by the grant-making policies and processes themselves.

CBT's Neighbourhood Small Grants are a small but powerful example of an alternative grant-making process that reduces the administrative barriers to funding access. Any individual community member (as opposed to a CRA qualified donee) can apply for up to \$500 for projects through a quick and accessible application. CBT staff are happy to receive these applications over the phone. Neighbourhood Small Grants applications will be open for applications from March 1st until April 15th.

Over the coming weeks, our grants team will be hosting grant information sessions via Zoom. I will also be asking your staff for guidance on how to share this information best with your community as part of our goal to support projects and initiatives where they're most needed in our region this year. Our website includes a full list of CBT grant opportunities as well as links to the online application. Please reach out to me directly at 725-2219 or via email at rebecca@clayoquotbiosphere.org if you have ideas to share and would like to discuss this further.

Respectfully,

Rebecca Hurwitz
Executive Director

PO Box 67, 316 Main Street, Tofino BC Canada V0R 2Z0
T 250.725.2219 F 250.725.2384

clayoquotbiosphere.org



STAFF REPORT TO COUNCIL

Council Meeting: February 23, 2021
500 Matterson Drive, Ucluelet, BC V0R 3A0

FROM: JOSEPH ROTENBERG, MANAGER OF CORPORATE SERVICES

FILE NO: 2380-20

SUBJECT: CBC LICENSING AGREEMENT RENEWAL

REPORT NO: 21-17

ATTACHMENTS: APPENDIX A – CBC LICENSING AGREEMENT

RECOMMENDATION(S):

1. **THAT** Council authorize the District of Ucluelet's authorized signatories to enter into the CBC Licensing Agreement dated for reference February 23, 2021.

PURPOSE:

To obtain Council's approval to enter into a Licensing Agreement with the CBC for their radio tower which is located on the Matterson Reservoir.

BACKGROUND:

The District of Ucluelet entered a license agreement with CBC dated for reference the 16th day of July 2015 for their radio antenna to be located on the Matterson Reservoir. This antenna provides for CBC Radio coverage in and around Ucluelet. That agreement has expired.

Staff and representatives from CBC negotiated the draft CBC Licensing Agreement which has a five-year term. The new agreement is substantially similar to the agreement that has expired but it features a modest increase in the annual license fee, a one year termination clause rather than a 90 day termination clause, an overholding clause and an option for CBC to extend the agreement for two additional five year terms.

TIME REQUIREMENTS – STAFF & ELECTED OFFICIALS:

Nominal staff time will be required to coordinate execution of the Agreement.

FINANCIAL IMPLICATIONS:

The annual license fee of \$510.00 per year will be collected from CBC for the term of this agreement. If CBC exercises their option to extend the agreement, the licensing fee will be subject to renegotiated.

OPTIONS REVIEW:

1. **THAT** Council authorize the District of Ucluelet's authorized signatories to enter into the CBC Licensing Agreement dated for reference February 23, 2021. **(Recommended)**
2. **THAT** Council provide alternative direction to Staff.

Respectfully submitted: Joseph Rotenberg, Manager of Corporate Services

Appendix A

LICENCE AGREEMENT

THIS AGREEMENT made in duplicate this 23rd day of February, 2021.

BETWEEN:

DISTRICT OF UCLUELET, a municipality having its offices at 200 Main Street, Ucluelet, British Columbia, V0R 3A0 (hereinafter referred to as the “**Licensor**”)

AND:

CANADIAN BROADCASTING CORPORATION, a Crown corporation established under the *Broadcasting Act S.C. 38-39 Elizabeth II c.11*, having its had office at 181 Queen Street, Ottawa, Ontario, K1P 1K9 and a place of business at 250 Front Street West, Toronto, Ontario, M5V 1E6; (hereinafter referred to as the “**Licensee**”)

WHEREAS by a License dated the Sixteenth (16th) day of July 2015 (hereinafter referred to as the “Original License”) the Licensor granted to the Licensee a license to install, maintain and/or occupy facilities on the Lands, more particularly described in the Original License, for a term of five (5) Years, that commenced on the First (1st) day of September 2015 and terminated on the Thirty-first (31st) day of August 2020;

AND WHEREAS the Licensee gave notice of its intention to enter into a new license agreement and the Licensor has agreed;

As per the terms and conditions hereinafter contained, the Licensor and Licensee covenant and agree as follows:

Section 1: Licensed Area

- (a) The Licensor is the lawful owner of a certain parcel of land at Ucluelet, BC, District Lot 281, Clayoquot Land District, PT OF THE REM OF DL 281 THAT PORTION LOCATED AT THE END OF SHORT RD (SEE 00114.900 OTHER PORTION OF DL 281)(hereinafter referred to as the “Lands”)
- (b) The Licensor hereby grants to the Licensee a non-exclusive licence (the “Licence”) to utilize a portion of the Licensor’s Lands (the “Licence Area”) for the installation and operation of an FM Radio Transmitter Site, as set out in Appendix “A”, with such facilities including any and all equipment and property either owned or leased by the Licensee and hereinafter referred to as the “Works.”
- (c) The exercise by the Licensee of the rights herein granted and all Works effected by the Licensee shall be at the sole and exclusive risk of the Licensee. The Licensor shall not be liable to the Licensee for any loss,

damages, costs and/or disbursements relating to property or trade of the Licensee, save in the event that such loss, damage, cost and/or disbursement is directly caused by the negligence of the Licensor, their employees, agents and/or contractors.

Section 2: Term

- (a) This Agreement is for a term of five (5) years commencing on the First (1st) day of September 2020 (hereinafter referred to as the “Commencement Date”) and terminating on the Thirty-first (31st) day of August 2025 at 11:59 p.m., or the date of any earlier termination as provided in this Agreement (hereinafter referred to as the “Termination Date”)(“hereinafter referred to as the “Initial Term”).
- (b) Provided that the Licensee is not in default at the time it exercises its option(s), the Licensor hereby grants to the Licensee the option to renew this Agreement for two (2) additional term(s) of Five (5) Years each upon the same terms and conditions as herein contained save and except for the yearly License Fee, which shall be negotiated in good faith between the parties at least ninety (90) days before the end of any of the Initial Term or any Renewal Term (hereinafter referred to as a “Renewal Term(s)"). In order to exercise any of these option(s) herein granted, the Licensee shall give to the Licensor not less than six (6) months prior written notice of its intention to exercise the aforesaid option.

Together, the Initial Term and any and all Renewal Term(s), once duly exercised, shall be referred to as “Term”.

- (c) If the Licensee remains in possession of the Licensed Area after the expiration or other termination of the Term or any Renewal Terms thereof, the Licensee shall occupy the Licensed Area on a month-to-month basis, upon the same terms and conditions, and at a license fee equal to the then current license fee as adjusted and payable on a monthly basis.

Section 3: Licence Fee

- (a) In consideration of the licence herein granted, and without prior demand, the Licensee will pay to the Licensor annual licence fees in the sum of Five Hundred and Ten Dollars (\$510.00) plus applicable Sales Taxes, if any (the “**Licence Fee**”). The License Fee is payable annually, in advance on the Commencement Date and on each and every anniversary of the Commencement Date throughout the Term, without set-off or abatement. Payment shall be made to the Licensor at the address set forth in section 6(g) below.
- (b) If for any reason, it becomes necessary to calculate Licence Fees, or any other charges or fees payable by the Licensee pursuant to this Licence, for irregular periods, an appropriate pro rata adjustment will be made on a daily basis.

- (c) Any increase in property taxes or any other levy assessed against the Licensor occurring after the date on which the Licensee first took possession of the Licence Area, which is directly attributable to the Licensee's Works (as defined below), including any increase in a grant paid or payable in lieu of taxes, shall be paid directly by the Licensee to the Licensor or reimbursed by the Licensee on demand if such increase is paid by the Licensor.

Section 4: Licensee's Covenants

THE LICENSEE COVENANTS WITH THE LICENSOR:

- (a) that it will bear all direct and indirect costs related to its installation and use of the Lands;
- (b) that it will pay for any and all electrical connections, electricity charges, electrical Equipment and/or services as maybe attributable to the Licensee's operations at the Land and/or operations of its Works.
- (c) that it will not, during the Term, transfer, assign or sublicense this Licence and will not permit or suffer any other person to occupy the whole or any part of the Licence Area and will not otherwise encumber the Licence Area, without the prior written consent of the Licensor, which consent will not be unreasonably withheld;
- (d) that it will, as required, submit all plans and specifications for the installation or modification of the Works on the Lands for pre-approval by the Licensor. All Work installations, maintenance, modification and repair work performed on the Lands shall be in accordance with Good Engineering Practices (hereinafter referred to as "GEP");
- (e) that the Licensee shall maintain all of its Works in a good and safe state of repair and in a clean and orderly condition, including keeping all areas in and around the Works neat, clean and tidy and free and clear of all debris, materials and tools, all in accordance with the Standards, GEP;
- (f) that the Licensee will not bring any Contaminants (as defined herein) onto, into or under the Licence Area or the Lands. For the purposes of this section 5(h) the term "contaminants" means any substance, including without limitation, urea formaldehyde, hydrocarbons, lead, pollutants, polychlorinated byphenyls ("PCBs"), contaminants, deleterious substances, dangerous substances or goods, hazardous, corrosive, or toxic substances, special waste, waste, pesticides, defoliants, and any material, including without limitation radioactive materials, asbestos-containing materials, PCB-containing equipment or materials, and any other solid, liquid, gas, vapour, odour, radiation, or combination of any of them, the storage, manufacture, handling, disposal, treatment, generation, use, transport, remediation or release into the environment of which is now or hereinafter prohibited, controlled, or regulated under any applicable law;

- (g) that no vehicles or equipment of any type belonging to or in the possession of the Licensee or its employees, servants, contractors, consultants or agents shall be allowed to interfere with the Licensor's use of the adjacent public road or driveway (hereinafter referred to as the "Road");
- (h) to use the Road only for the purpose of gaining access to and egress from the Licensee's Works, provided that the Licensee's use of the Road shall be at the Licensee's sole risk and the Licensor shall bear no responsibility or liability for loss or damage to persons or property of the Licensee relating to the use of the Road or the condition thereof;
- (i) that the Licensee shall comply with all applicable rules, regulations and bylaws of the District of Ucluelet and other governing bodies, in any manner affecting the Works or the Lands or the Licence Area;
- (j) that the Licensee shall not do, or permit to be done, anything that may damage or injure the Licence Area or the Lands and the Licensee shall, at the Licensee's expense, maintain and repair any damage done to the Licence Area or the Lands (excluding ordinary wear and tear) as a result of the Licensee's exercise of its rights hereunder, all to the satisfaction of the Licensor;
- (k) the Licensee will not suffer or permit any liens under the *Builders Lien Act* to be registered against title to the Lands by reason of labour, services, or materials supplied to the Licensee. In the event that any lien is so filed, the Licensee will take immediate action to cause same to be removed;
- (l) that the Licensee will indemnify and save harmless the Licensor, its officers, employees, contractors, subcontractors, agents, invitees and assigns against any and all liabilities, claims, demands, actions, causes of action, losses, damages and costs, including fees of solicitors and other professional advisors, which the Licensor may incur or be put to in connection with any breach, violation or non-performance of the Licensee's obligations under this Licence, any loss or damage to property, or any personal injury or bodily injury of any person arising out of in connection with the use and occupation of the Licence Area by the Licensee, its invitees or those for whom it is in law responsible, during the Term. This indemnity will survive the expiration or earlier termination of this Licence;
- (m) that notwithstanding the preceding, Licensee shall not be responsible for any indirect or consequential damages suffered by Licensor and for damages caused by gross negligence or wilful misconduct of the Licensor; and
- (n) the Licensee shall obtain and maintain during the Term, at the Licensee's expense, the following insurance coverage with insurance companies satisfactory to the Licensor, acting reasonably, and in a form satisfactory to the Licensor, acting reasonably:
 - a. "All Risks" coverage for property of every kind owned or leased by the Licensee and/or which the Licensee is responsible for and has been

installed by, or on behalf of the Licensee in the Licence Area, in an amount not less than the full replacement cost thereof; and

- b. "Commercial General Liability" insurance including, but not limited to, bodily injury, including death, property damage, including loss of use thereof, tenants legal liability, personal injury liability, contractual liability, non-owned automobile liability and contractor's protective insurance coverage, on an occurrence basis with limits of not less than Three Million Dollars (\$3,000,000) per occurrence, or an amount which the Licensor may from time to time specify, and showing the Licensor as an additional insured and such policy will include severability of interest and cross liability clauses.

All such insurance shall:

- a. be non-contributing with, and will apply only as primary and not as excess to, any other insurance available to the Licensor; and
- b. include a waiver of any subrogation rights which the Licensee's insurers may have against the Licensor.

The Licensee shall furnish to the Licensor certificates, or other evidence acceptable to the Licensor, as to the insurance, from time to time effected by the Licensee, and its renewal or continuation in force.

Section 5: Licensor's Covenants

THE LICENSOR COVENANTS WITH THE LICENSEE:

- (a) that access to the Licence Area will be permitted to the Licensee and its employees, contractors and agents at all reasonable times for the purposes of this Licence; and
- (b) that it will not relocate the licensed Area and/or the Licensee's equipment in whole or in part at anytime during the Term or any Renewal terms thereof.

Section 6: Mutual Covenants

IT IS FURTHER MUTUALLY AGREED BETWEEN THE PARTIES HERETO:

- (a) that the use and occupancy of the Licence Area by the Licensee during the Term will, under all circumstances, be viewed as a licence only and will not create or be deemed to create any legal or equitable interest in land in the Licence Area in the Licensee's favour;
- (b) that nothing contained herein shall be deemed or construed by the parties as creating a trust or the relationship of principal and agent, lessor and lessee, or of partnership or of joint venture between the parties, it being understood and agreed that none of the provisions contained herein, nor

any act of the parties shall create any relationship between the parties other than that of Licensor and Licensee;

- (c) that this Licence may be terminated by either party forthwith on twelve-months prior written notice, as outlined in section 6(g) below;
- (d) if and whenever the Licensee defaults in observing or performing any of the terms and conditions set forth herein and such breach or failure is not remedied to the satisfaction of the Licensor, acting reasonably, within 14 days after delivery of written notice from the Licensor to the Licensee specifying the breach or failure, then the Licensor may:
 - a. terminate this Licence without further notice or legal process; and/or
 - b. perform, or cause to be performed, any such covenants and/or obligations, or any part thereof to be performed, at the Licensee's expense, the amount of which expense shall be deemed to be the cost incurred by the Licensor;
- (e) in the event that during the Term of this Licence, the Licensee ceases to hold the required approval from Industry Canada and/or the Canadian Radio-Television Telecommunications Commission to operate on the Licence Area, the Licensee shall cease transmitting forthwith and shall remove the Works from the Licence Area, in accordance with the terms of this Licence, and this Licence shall be terminated as of the later of the date of such cessation and the date that is ninety (90) days after the Licensor or the Licensee was given notice;
- (f) that upon the expiration or earlier termination of this Licence, the Licensee shall, at its expense, remove the Works from the Licence Area. The Licensee shall conduct such removal without damaging the Licence Area or the Lands and shall, at its expense, restore the Licence Area and the Lands to their original condition, to the satisfaction of the Licensor. Any property of the Licensee, including the Works, remaining on the Licence Area or the Lands ninety (90) days after the expiry or earlier termination of this Licence shall be deemed to have been abandoned by the Licensee and shall become the property of the Licensor or, at the Licensor's discretion, shall be removed from the Licence Area or the Lands at the Licensee's expense;
- (g) any notice which is required to be given under this Licence may be effectively given by one party to the other if hand-delivered or mailed by prepaid registered mail or sent by facsimile and directed as follows:

to the Licensor at:

DISTRICT OF UCLUELET

200 Main Street
PO Box 999
Ucluelet, BC V0R 3A0

Attention: Corporate Officer
Fax: (250) 726-7335
Email: Info@ucluelet.ca

to the Licensee at:

CANADIAN BROADCASTING CORPORATION

250 Front Street West
P.O. Box 500, Station "A"
Toronto, Ontario
M5W 1E6

Attention: CBC/Radio-Canada Transmission
Fax: (416) 205-2420
Email: cbc.transmission@cbc.ca

A notice will be deemed to be received on the day it is delivered, if delivered personally, on the date and at the time it is received by the recipient's facsimile, if delivered by facsimile, or seventy-two (72) hours after the time and date of mailing, if delivered by mail;

- (h) time will be of the essence of this Licence;
- (i) this Licence will be construed in accordance with and governed by the laws applicable in the Province of British Columbia;
- (j) this Licence constitutes the entire agreement between the parties and no understanding or agreement, oral or otherwise, exists between the parties with respect to the subject matter of this Licence, except as expressly set out in this Licence;
- (k) no provision of this Licence will be considered to have been waived unless the waiver is in writing and a waiver of the Licensor of any breach of a term, covenant or condition of this Licence will not be considered to be a waiver of any subsequent breach of the term, covenant or condition or other term, covenant or condition;
- (l) this Licence may be executed in counterpart and delivered by email or facsimile transmission and such copies, together, will be deemed as effective as if a single Licence had been executed by the parties.

- (m) that the headings throughout this agreement form no part of the agreement itself, and are wholly without legal significance; and
- (n) that subject to the provisions of the *Access to Information Act* (Canada, R. S. 1985, c. A-1) both parties shall ensure that non-public information owned by the other party and disclosed to a party, in any manner, in the course of negotiation of the agreement or contained within such agreement shall remain confidential and not be disclosed to any third party excepting its solicitors, advisors or agents or others required for the purpose of interpreting or carrying out obligations under this agreement or assessing the value and the meaning of this agreement, unless required by law the party to which such information is disclosed must undertake to acknowledge that such divulcation is made subject to the provisions herein and the party who discloses the information shall remain responsible for any breach to this confidentiality provision by such third party. This provision shall remain in force and effect for five (5) years from the expiration of the contract.

Section 7: Access to information

- (a) The Licensee is subject to the *Access to Information Act* (Canada, R. S. 1985, c. A-1), as amended from time to time. As a consequence, records under the control of the Licensee may be subject to a request for access and be disclosed if no exclusion or exemption provided in the Act applies. This paragraph will not be interpreted as a waiver of the confidentiality obligations of this agreement.

IN WITNESS WHEREOF the parties hereto have executed this agreement as of the date first written above.

DISTRICT OF UCLUELET

Per: _____
Name:
Title:

Per: _____
Name:
Title:

CANADIAN BROADCASTING CORPORATION

Per: _____
Name: **Martin Marcotte**
Title: Executive Director, Real Estate Solutions

Per: _____
Name:
Title: Finance and Administration

APPENDIX "A"

Facilities made available under the Agreement are as follows:

SERVICE: for CBC/Radio-Canada FM Radio Transmitter Site

LAND USE:

Use of mutually defined area on the Licensor's property at Ucluelet, BC, for installation of:

One (1) 2-bay PSI TX Antenna model: PSIFML-2A-90WS-HR attached to a 10m (75mm' OD) mast mounted on top of the water reservoir building

One (1) Kathrein RX Antenna model: YA7-FCM/HCM attached to a 4.5m (60mm OD) mast mounted on top of the water reservoir building

BUILDING (SHARED):

Spaced for one (1) equipment rack in pump control shack located next to the reservoir

FREQUENCY:

92.7MHz

POWER:

Connected to Licensor's power (breaker Panel) with 120VAC 15A breakers



STAFF REPORT TO COUNCIL

Council Meeting: FEBRUARY 23, 2021
500 Matterson Drive, Ucluelet, BC V0R 3A0

FROM: ABBY FORTUNE, MANAGER OF RECREATION & TOURISM

FILE NO: 1855-05 COOP

SUBJECT: UCLUELET AND AREA CHILDCARE SOCIETY
LETTER OF SUPPORT FOR CO-OP COMMUNITY SPACES GRANT

REPORT NO: 21-22

ATTACHMENT(S): APPENDIX A - HEROLD ENGINEERING

RECOMMENDATION(S):

1. **THAT** Council write a letter of support for the Ucluelet & Area Child Care Society (UACCS) to partner with the District of Ucluelet through the Co-op Community Spaces Grant to:
 - a. Build an awning addition of the end of the building at the Daycare at the UCC for covered outdoor space;
 - b. Remove the pea gravel and install rubber matting for a playground surface; and
 - c. To accept funding and issue receipts on the UACCS behalf.

2. **THAT** Council approve the construction of an awning addition to the Ucluelet Community Centre (UCC) if the grant is successful.

PURPOSE:

To request a letter of support from Council for the Ucluelet Daycare & Area Child Care Society's grant application to the Co-op Community Spaces Grant in partnership with the District of Ucluelet.

To approve an addition to a District asset of an awning to the daycare portion of the UCC.

BACKGROUND:

The Co-op Community Spaces Program was established to improve community health and well-being by building places for Western Canadians to come together, build social connections and enable community development. The maximum amount eligible for this grant is \$150,000 and the deadline for submission is March 1, 2021.

An eligibility requirement of this grant is that non-profit organizations partner with their municipal government who will accept funding and issue receipts on their behalf. If the UACCS was successful with the Co-op Community Spaces Grant a Memorandum of Understanding ("MOU") will be drafted between UCCAS and DOU outlining responsibilities and expectations regarding the project and the funding.

UACCS will be responsible for any cost overruns on the project above the maximum eligible grant amount of \$150,000.

This expansion of the facility would become a District asset that would be maintained by the District of Ucluelet. There is no expectation on compensation for the UACCS if they do receive this grant.

The expansion plans for the building has been reviewed by Herold Engineering. A final sign-off will be required to move forward on the awning. Jeff Duncan, of Herold Engineering, will simply seal the sketch mark-ups, provide additional renderings required (Schedule B) in order to move forward on the project. Quotes for the construction have been received for this project from ICON Development Ltd. and Out of Our Tree.

TIME REQUIREMENTS – STAFF & ELECTED OFFICIALS:

Staff time would be required for the drafting of the MOU, support with the oversight of the project and the issuance of the receipts on behalf of the Society.

FINANCIAL IMPACTS:

The UACCS is currently finalizing costs for the project. The maximum allowable for this grant is \$150,000.

There would be no direct financial implications to the District of Ucluelet for this project.


POLICY OR LEGISLATIVE IMPACTS:

A MOU will be required if the Ucluelet and Area Child Care Society is successful in obtaining funding of the proposed project through the grant.

OPTIONS REVIEW:

1. **THAT** Council write a letter of support for the Ucluelet & Area Child Care Society (UACCS) to partner with the District of Ucluelet through the Co-op Community Spaces Grant to:
 - a. Build an awning addition of the end of the building at the Daycare at the UCC for covered outdoor space;
 - b. Remove the pea gravel and install rubber matting for a playground surface; and
 - c. To accept funding and issue receipts on the UACCS behalf. **(Recommended)**
2. **THAT** Council approve the construction of an awning addition to the Ucluelet Community Centre (UCC) if the grant is successful. **(Recommended)**
3. **THAT** Council provide alternative direction to Staff.

Respectfully submitted: Abby Fortune, Manager of Recreation & Tourism



J.C.C. CHILDREN'S CENTRE - COVERED OUTDOOR PLAY AWNING
 1/2" = 1'-0"
 JULY '20


calculate areas. Do not scale this drawing. All dimensions to be checked on site by the Contractor and such dimensions to be their responsibility. All work must comply with the relevant Building Code or Building Bylaw and related documents. Drawing errors and omissions must be immediately reported to the Architect.

Issues

D.C.C. Chippen's Centre - Covered Outdoor Play Space Awwing.
 3/32" = 1'-0"



- 18 Jun 08 Issued for Coordination
- 4 Jul 08 Issued for Coordination
- 29 Jul 08 Issued for Class B Cost Estimate
- 3 Sep 08 Issued for Coordination
- 8 Oct 08 Issued for Coordination
- 28 Oct 08 Issued for BP / Foundation
- 13 Nov 08 Issued for Coordination
- 27 Nov 08 Issued for Tender

Revisions



| | | | | |
|--|----------------|--|-----------------|----------|
| Project #: 1040-011 | Client: D.O.U. | Discipline: | Date: AUG. 5/20 | SKETCH # |
| Project Title: CHILDRENS CENTRE AWNING | | <input checked="" type="checkbox"/> Structural - Buildings | Drawn: JDD | SK1 |
| Subject: FOOTING / PIER DETAILS. | | <input type="checkbox"/> Structural - Bridges | Design: JDD | SHEET |
| | | <input type="checkbox"/> Civil - Municipal | Check: | 1 of 1 |
| | | <input type="checkbox"/> Industrial - Marine | | |
| | | <input type="checkbox"/> Building Envelope | | |

Metric Grid





STAFF REPORT TO COUNCIL

Special Council Meeting: FEBRUARY 23, 2021
500 Matterson Drive, Ucluelet, BC V0R 3A0

FROM: BRUCE GREIG, MANAGER OF COMMUNITY PLANNING

FILE NO: 6480-20-OC

SUBJECT: UCLUELET OFFICIAL COMMUNITY PLAN BYLAW

REPORT NO: 21-23

ATTACHMENTS: APPENDIX A – REVISED OCP BYLAW No. 1236, 2020
APPENDIX B – REVISED SCHEDULE 1 TO OCP BYLAW No. 1236, 2020
(INCLUDING REVISED SCHEDULES AND MAPS)

RECOMMENDATIONS:

THAT Council, with regard to the Official Community Plan (OCP) bylaw update:

1. consider District of Ucluelet Official Community Plan Bylaw No. 1236, 2020, in conjunction with the District of Ucluelet Financial Plan;
2. consider District of Ucluelet Official Community Plan Bylaw No. 1236, 2020, in conjunction with the municipal Waste Management Plans;
3. give second reading to District of Ucluelet Official Community Plan Bylaw No. 1236, 2020, as amended;
4. refer the OCP Bylaw to the following agencies for a period of 60 days to invite their formal comment:
 - Ucluelet First Nation;
 - Toquaht Nation;
 - Alberni Clayoquot Regional District;
 - District of Tofino;
 - School District 70;
 - Island Health;
 - Ministry of Transportation and Infrastructure;
 - Pacific Rim National Park Reserve;
 - Clayoquot Biosphere Trust;
 - Westcoast Community Resources Society;
 - Alberni Clayoquot Health Network;
 - Wild Pacific Trail Society;
 - Tourism Ucluelet;
 - Ucluelet Chamber of Commerce; and,
5. refer District of Ucluelet Official Community Plan Bylaw No. 1236, 2020, to a public hearing.

PURPOSE:

The purpose of this report is to provide a brief background and explore next steps for the update of the Ucluelet Official Community Plan (OCP) bylaw.

BACKGROUND:

The following summary and background to the Ucluelet Official Community Plan (OCP) bylaw is included in the appendices to the draft OCP:

“The Village of Ucluelet was incorporated in 1952 and became as District Municipality in 1997. The community adopted its first Official Community Plan (OCP) bylaw in 1971. The history of OCP’s in Ucluelet is as follows:

- *OCP Bylaw No. 235 (1971)*
- *OCP Bylaw No. 407 (1981)*
- *OCP Bylaw No. 498 (1988)*
- *OCP Bylaw No. 772 (1998)*
- *OCP Bylaw No. 900 (2004)*
- *OCP Bylaw No. 1140 (2011)*

A review of the Ucluelet OCP bylaw was initiated by Council in 2016.

From 2016 through 2018 the District, along with students and faculty from Vancouver Island University’s (VIU) Master of Community Planning program, collected community opinions on the OCP and the broad range of issues of interest to the community. A series of public engagement activities and events were held during this time, including “planning on the streets” events, pop-up planning workshops, stakeholder workshops with community groups and classes from the local schools. A three-day public consultation blitz in the spring of 2018, culminating in a large public open house, connected with 256 local residents.

Council initially received the draft OCP bylaw in September of 2018, at which point the bylaw received first reading. The 2018 municipal election, focus on pressing affordable housing issues and a robust community debate on new non-medical cannabis retail regulations – and then the onset of a global pandemic – all contributed to stretch out the timeline for the work to update the OCP. Concurrently, work on flood risk mapping, Indigenous relations and policies, housing and land use demand resulted in reports to Council for direction on specific policy areas. These were incorporated into this revised OCP document presented to Council for consideration of second reading as amended and formal referral to external agencies ahead of a public hearing on the bylaw.”

OVERVIEW:

The draft 2020 OCP presented with Bylaw No. 1236 represents a major overhaul of the 2011 Plan. In particular, proposed changes to the OCP include:

1. a new structure organized around the broad themes of Place, People and Systems;
- 2 |

2. writing which attempts to be more inclusive of Indigenous perspectives (see Part 1);
3. expanded policies on affordable housing (see Part 3);
4. an updated section on economic development (see Part 4);
5. an updated Long-Range Land Use Plan (see Schedule 'A') reflecting the current zoning (and sub-zones) but also showing the expected evolution of land uses toward the year 2050, particularly in the former Forest Reserve land areas;
6. addition of a Parks and Trails Network map (see Schedule C) showing the location of existing and proposed new parks, trail connections and open space;
7. new mapping and clarification of Development Permit areas for protection of the environment and avoiding natural hazards (see Schedules 'E' and 'G', and DP guidelines in Part 6);
8. updated policies responding to climate change, energy use and sea level rise (see Parts 2 and 6);
9. clarification of Development Permit areas for form and character (see Schedules 'F', and DP guidelines in Part 6); and,
10. an updated section on implementation, including enforcement (see Part 6).

The document has benefitted from the enthusiastic input of Ucluelet residents as well as insights provided by all municipal departments. Staff have attempted to draft a plan which captures the character of Ucluelet and charts the direction where the community is headed over the coming years. The aim has been to create a document which will prove useful:

- to residents and property owners, as they look to understand what their friends and neighbours envision, and where they fit within the community;
- to businesses and investors, as they seek a clear understanding of the framework they are working in and the available opportunities;
- to other agencies, as they look for the direction Ucluelet is taking to see where our interests align;
- to staff, as they work to continually improve municipal operations and deliver services on behalf of the community; and,
- to Councils, as they discuss community issues, set priorities and deliberate on where to focus finite resources.

FINANCIAL IMPACTS:

Adoption of an OCP does not commit Council or the community to complete any tasks or projects by a certain time, or commit to funding future projects; those future decisions remain at the discretion of Council. The OCP as drafted does note a number of follow-up actions which would build on the Plan and help clarify future decisions facing the community and its elected Council. A number of projects are also identified as priorities (particularly trails, sidewalks and other public-realm improvements). These items will all be brought forward for consideration by Council as part of its strategic planning and budgeting process, with the associated costs to be detailed at that time. The OCP works in concert with the Strategic Plan and budgets adopted by Council to set both the long-term goals and specific immediate and near-term priorities within that overall direction.

POLICY OR LEGISLATIVE IMPACTS:

There are a number of legislated requirements under the *Local Government Act* for adopting an OCP bylaw: both necessary content and steps in the process. These are discussed in Part 7 of the OCP document (see p.123 in **Appendix “B”**).

Note that after first reading, a legislated requirement (under section 477 of the *Local Government Act*) is for Council to consider the OCP in conjunction with its financial plan and any waste management plan. If proceeding past first reading, Council should turn its mind to these areas and consider the motions presented above.

The requirements for adopting an Official Community Plan bylaw include Council consideration of opportunities for consultation with persons, organizations and authorities as part of the process. The early notification to the agencies listed, in the fall of 2018, provided an opportunity for input to inform the draft bylaw. Comments received have shaped edits to the draft OCP document, as presented to Council on January 12, 2021. After second reading, formal referral back to these agencies is an appropriate next step. Allowing a generous amount of time to enable agency comment is typical, and staff suggest that 60 days would be appropriate. This would result in a public hearing being scheduled around the last week of April or first week of May.

Once an Official Community Plan is adopted, the subsequent decisions of Council and actions of the municipality must be consistent with the objectives and policies set out in the plan.

OPTIONS:

The draft OCP has been revised as previously directed, and Council consideration of the recommended motions at the outset of this report would move the bylaw forward to a public hearing to formally gather community input on the Plan. If there are edits which Council wishes to see made to the OCP, direction on those changes could also be given prior to second reading of the bylaw.

Alternatively, Council could provide direction to staff on whether additional review and input from the public, specific agencies or entities is desired before further consideration of the bylaw.

Respectfully submitted: Bruce Greig, Manager of Community Planning
John Towgood, Planner
Donna Monteith, Acting Chief Administrative Officer

DISTRICT OF UCLUELET**Bylaw No. 1236, 2020**

A bylaw to adopt "District of Ucluelet Official Community Plan 2020"

WHEREAS Section 472 of the *Local Government Act* provides that the Council of a local government may, by bylaw, adopt an Official Community Plan;

AND WHEREAS Council has caused an Official Community Plan to be prepared for all areas of the District in accordance with the provisions of Sections 473 and 474 of the *Local Government Act* and other relevant sections as referenced in the Plan;

AND WHEREAS Council has consulted with the board of education and considered and consulted with other persons, organizations and authorities it considers will be affected, including how many and whether appropriate opportunities for consultation should be early and ongoing, all in accordance with Sections 475 and 476 of the *Local Government Act*;

NOW THEREFORE the council of the District of Ucluelet, in open meeting assembled, enacts as follows;

1. The document entitled "District of Ucluelet Official Community Plan 2020" and its associated appendices, maps, schedules, tables and figures, all attached as Schedule 1 to this bylaw and made a part of this bylaw, is hereby designated as the Official Community Plan for the entirety of the area within the District of Ucluelet, as depicted on Schedule A of the Official Community Plan.
2. The "District of Ucluelet Official Community Plan Bylaw No. 1140, 2011", and all its schedules and amendments are repealed.
3. This bylaw may be cited for all purposes as the "District of Ucluelet Official Community Plan Bylaw No. 1236, 2020".

READ A FIRST TIME this **18th** day of **September**, 2018.

Considered in conjunction with the District of Ucluelet Financial Plan and the Waste Management Plan under Section 477 of the *Local Government Act*, this ____ day of _____, 2021.

READ A SECOND TIME this ____ day of _____, 2021.

PUBLIC HEARING HELD this ____ day of _____, 2021

READ A THIRD TIME this ____ day of _____, 2021.

ADOPTED this ____ day of _____, 2021.

CERTIFIED CORRECT; "District of Ucluelet Official Community Plan Bylaw No. 1236, 2020".

Mayco Noël
Mayor


Joseph Rotenberg
Corporate Officer

THE CORPORATE SEAL of the
District of Ucluelet was hereto affixed
in the presence of:


Joseph Rotenberg
Corporate Officer



Place



People



Systems

The District of Ucluelet logo, featuring a stylized wave and leaf design, is positioned on the left. To its right, the text 'DISTRICT OF UCLUELET' is displayed. On the right side of the dark blue banner, the title 'Official Community Plan 2020' is written in large white font.

This plan would not exist without the hard work and input generously provided by the following:

- Shawn Warner at CGIS for mapping;
- Nicky Ling at Ukee Infotech for proofing and editing;
- Dr. Pam Shaw and the students of the Masters of Community Planning program and Mount Arrowsmith Biosphere Region Research Institute at Vancouver Island University for assistance with community engagement;
- the staff from all departments of the District;

...and most importantly, all the community members who shared their ideas, concerns, vision and passion for the community of Ucluelet.

Cover artwork by Katsumi Kimoto and Marla Thirsk

Title: District of Ucluelet Official Community Plan
Prepared By: Department of Community Planning, District of Ucluelet
Status: Draft 7
Contact: Planning Department
District of Ucluelet
200 Main Street, Ucluelet BC V0R 3A0
 250-726-7744

[Type here]

Contents

Part One: Introduction6

What is an Official Community Plan & Why Plan7

 COMMUNITY CHARACTER AND IDENTITY7

 COMMUNITY VISION8

 CONTEXT.....9

Part Two: Place.....15

Natural Environment.....16

 ECOLOGY16

 WILDLIFE17

 ENVIRONMENTAL PROTECTION17

 CLIMATE ACTION18

 PARKS.....27

 TRAILS28

 OPEN SPACE & GREENBELTS29

Transportation and Movement.....31

 GENERAL TRANSPORTATION NETWORK.....32

 NETWORK IMPROVEMENTS - VILLAGE CENTRE33

 MARINE TRANSPORTATION.....34

 PEOPLE ON FOOT35

 PEOPLE ON BICYCLES36

 PEOPLE ON TRANSIT36

 PEOPLE IN AUTOMOBILES36

 PEOPLE MOVING FISH.....37

Part Three: People 38

Community Health, Safety and Wellbeing 39

 FIRE AND EMERGENCY SERVICES 39

 COMMUNITY SAFETY..... 41

 HEALTH AND WELLBEING..... 42

 RECREATION..... 43

 FOOD SECURITY..... 44

 HERITAGE AND CULTURE 45

Land Use, Housing and Managed Growth 47

 LAND USE CATEGORIES 47

 VILLAGE SQUARE 51

 COMMERCIAL 54

 INDUSTRIAL 57

 INSTITUTIONAL 60

 MARINE 62

 RESIDENTIAL..... 66

 FUTURE COMPREHENSIVE PLANNING AREAS 72

Part Four: Systems 77

 Servicing and Infrastructure 78

 Municipal Finance, Governance and Operations..... 83

 Economic Development 85

Part Five: Schedules & Maps 88

 SCHEDULE A: LONG-RANGE LAND USE PLAN..... 89

 SCHEDULE B: TRANSPORTATION NETWORK 89

[Type here]

| | | | |
|---|-----|--|-----|
| SCHEDULE C: PARKS & TRAILS NETWORK | 89 | DEVELOPMENT PERMIT AREA IV (MULTI-FAMILY, COMMERCIAL, AND MIXED-USE) | 106 |
| SCHEDULE D: WATER & SEWER INFRASTRUCTURE | 89 | Environmental Development Permit Areas | 110 |
| SCHEDULE E: DEVELOPMENT PERMIT AREAS – ENVIRONMENTAL PROTECTION | 89 | DPA V – TERRESTRIAL ECOSYSTEMS (MATURE FOREST)..... | 112 |
| SCHEDULE F: DEVELOPMENT PERMIT AREAS – FORM & CHARACTER | 89 | DPA VI - STREAM AND RIPARIAN AREAS PROTECTION | 113 |
| SCHEDULE G: DEVELOPMENT PERMIT AREAS – STEEP SLOPES.... | 89 | DPA VII – MARINE SHORELINE | 115 |
| MAP 1: REGIONAL CONTEXT | 89 | DPA VIII– NATURAL HAZARD AREAS PROTECTION (STEEP SLOPES) | 117 |
| MAP 2: REGIONAL INFRASTRUCTURE | 89 | ENFORCEMENT | 121 |
| MAP 3: ARCHAEOLOGICAL POTENTIAL | 89 | Part Seven: Appendices | 122 |
| MAP 4: COASTAL STORM – FLOOD CONSTRUCTION LEVELS | 89 | BOILERPLATE (REQUIRED CONTENT, LEGISLATION) | 123 |
| MAP 5: TSUNAMI FLOOD VULNERABILITY..... | 89 | PLANNING PROCESS (PAST OCP’S, PUBLIC CONSULTATION, REFERRALS)..... | 124 |
| MAP 6: TSUNAMI FLOOD PLANNING | 89 | COMMUNITY PROFILE (DEMOGRAPHICS AND PROJECTIONS) | 125 |
| MAP 7: CURRENT LAND USE | 89 | DEFINITIONS | 127 |
| MAP 8: ENVIRONMENTAL BASE INFORMATION | 89 | REFERENCES & CREDITS | 128 |
| Part Six: Implementation | 90 | | |
| Implementation | 91 | | |
| Monitoring | 92 | | |
| Relationship to Other Plans | 92 | | |
| Regional Context..... | 93 | | |
| Development Permit (DP) Area Designations and Guidelines...94 | | | |
| Form and Character Development Permit Areas | 95 | | |
| DEVELOPMENT PERMIT AREA I (VILLAGE SQUARE)..... | 99 | | |
| DEVELOPMENT PERMIT AREA II (PENINSULA ROAD) | 102 | | |

[Type here]

The District of Ucluelet acknowledges that we are located on the traditional territory (ḥaaḥuuli) of the Yuuḷuḡiḡath (Ucluelet First Nation). We are neighbouring communities who share interests in the Ucluth Peninsula and surrounding area. Our long-standing relationship is built upon mutual respect and many individual, personal ties.

The District aims to broaden and strengthen this relationship to better the lives of all community members. Discussion of the municipality's relationship with indigenous people and communities follows in Part One of this plan.

[Type here]

Part One: Introduction

What is an Official Community Plan & Why Plan

An Official Community Plan, or “OCP”, is a statement of objectives and policies adopted by a local government to guide decisions on land use planning, land use management and municipal operations within the area covered by the plan. The OCP sets out a road map for the community, to let everyone know where we’re headed in the long term. The scope of this OCP looks 30 years down the road. It is a living document and should be changed from time to time as the community evolves, as new issues come up or as new opportunities arise. The OCP is adopted by bylaw, by the elected Council of the District of Ucluelet; once the OCP is adopted any subsequent bylaws enacted or works undertaken by Council must be consistent with the plan.

For details on the legislative context, community profile, public consultation and process which went into developing this OCP, please refer to the appendices in Part 7.

Following this introductory foundation chapter, the bulk of the plan is organised under three broad headings of Place, People and Systems – followed by a chapter on Implementation and appendices.

Ucluelet is:

COMMUNITY CHARACTER AND IDENTITY

Ucluelet is a diverse, active and welcoming community which has been shaped over time by the energy of the place and the people drawn here to the natural setting of the rugged outer west coast of Vancouver Island.

Located on the narrow Ucluth Peninsula between Barkley Sound and the exposed Pacific Ocean, Ucluelet’s name (“safe harbour” in the Nuu-chah-nulth language) points to the key position of the town in this spectacular landscape. Poised on the edge of the Pacific, the community draws its energy from the interplay of the contrasting and complementary qualities of the landscape and the people. A short stroll takes you from Big Beach and the surge of the wild Pacific to the Whiskey Dock in the centre of the village and the calm waters of the harbour. Layered through the community are pairs of influences which add to its richness: land / sea; indigenous / settler; ancient / modern; resident / visitor; small town / world class; energizing / restoring; raw / refined – the interplay of these forces makes for a community which is complex, balanced and dynamic.

The people who make up the town of Ucluelet are known for being a friendly, hardworking, resourceful and welcoming group of citizens who are fiercely protective of the land and sea, and the resources which have sustained the community for generations. Ucluelet has been recognised as a town committed to carefully managing its growth to ensure that, as it changes over time, the natural environment is protected, the social fabric of the community is strengthened, and the local economy becomes more diverse and vibrant. This plan builds on the careful work of the past, and has been shaped by input from the engaged and passionate citizens of Ucluelet.

COMMUNITY VISION

Vision

Ucluelet's built and natural environment reflects, above all, the value we place on the outstanding beauty and diverse natural habitat of this place, which support the well-being of all members of the community. Ucluelet residents and visitors enjoy a high quality of life built upon a sustainable, diverse and vibrant local economy.

Guiding Principles

The policy directions contained within the OCP aim to realise this vision of Ucluelet as a vibrant, natural and active community. The following guiding principles reflect components of the vision and will be used to guide decision making.

1. Protect natural areas and ecological function
2. Maintain and enhance Ucluelet's unique character and preserve its heritage
3. Foster a welcoming and complete community
4. Build a diverse and dynamic local economy
5. Create a compact and vibrant Village Square
6. Develop and maintain top quality parks, trails, recreation and community services for residents and visitors
7. Broaden the spectrum of housing options to improve the availability of appropriate, affordable housing for all
8. Increase transportation choice and reduce automobile trips
9. Manage growth in balance with jobs, infrastructure investments, and the provision of services
10. Embrace the challenge of addressing the causes and impacts of climate change

The Visitor Experience

The tourism sector is a strong and growing part of its economy yet Ucluelet remains a working town first, and a resort second.

Importantly this is one of the town's strengths as a visitor destination. Ucluelet is the kind of town where not only does your yoga instructor live next door to a forklift operator, but there's a good chance that she *is* a forklift operator.

Interactions with the creative and colourful locals are an essential part of how our community leaves an impression on the visitor. By continuing to strengthen and grow as a diverse working town, by fostering small businesses and local innovators, and by improving the town facilities, programs and infrastructure to benefit all community members, we will also expand and improve the visitor experience.

Remaining genuinely Ukee in the face of growth and change will be key to maximising the quality of life for both residents and visitors.

CONTEXT

Region and Neighbours

The District of Ucluelet is located on the Ucluth Peninsula, at the entrance to Barkley Sound on the west coast of Vancouver Island. The town is situated just south of the Long Beach unit of the Pacific Rim National Park Reserve. The municipality is located within the Alberni Clayoquot Regional District (ACRD); other nearby west coast communities are the town of Tofino at the northern end of Long Beach, and the unincorporated community of Bamfield on the opposite side of Barkley Sound.

Ucluelet is situated in the traditional territory of the Yuułuꞵiꞵꞵath (Ucluelet First Nation), whose community is based immediately across the harbour at Hitacu. The Yuułuꞵiꞵꞵath are one of the five Maa-Nuulth Treaty First Nations along with the nearby 'tuk^waaꞵath (Toquaht Nation). The administrative office of the Toquaht Nation is located on Peninsula Road in the town of Ucluelet. The Toquaht Nation and the District of Ucluelet are partners in the Barkley Community Forest.

The economies of the Yuułuꞵiꞵꞵath First Nation, the Toquaht Nation and the District of Ucluelet are inexorably linked and all share a close tie to the area forests, fisheries and visitor economy. Citizens of all three communities regularly intermingle in town where many live, work, go to school, shop and access services.

Nearby residents of the Millstream and Port Albion unincorporated areas of the ACRD Area C are also an integral part of the fabric of the Ucluelet community.

The District provides drinking water to the Yuułuꞵiꞵꞵath First Nation at Hitacu, and back-up water supply and fire protection to Millstream. Ucluelet and its neighbours benefit from a history of mutual respect and assistance.



YFN: Relationship and Reconciliation

“The Yuułuᑲiᑲaᑲ First Nation asserts that we have occupied, benefited from and governed our traditional territory, lands, waters and resources since time immemorial.

The traditional territory of the Yuułuᑲiᑲaᑲ First Nation has in the past provided the resources necessary to sustain the Yuułuᑲiᑲaᑲ First Nation and we honour its connection to the lands, waters and resources of its traditional territory which provide for our physical and spiritual needs.

Through our inherent right to self-government, the Yuułuᑲiᑲaᑲ First Nation has preserved and protected our traditional territory and we accept the obligations and responsibilities inherent in governing Yuułuᑲiᑲaᑲ lands and pledge to protect Yuułuᑲiᑲaᑲ lands for future generations of our citizens.

We promote a healthy and prosperous future that ensures the continued existence of the Yuułuᑲiᑲaᑲ First Nation as a strong political, social and cultural community that aspires to grow as an organized, determined, successful and self-reliant people.

The Yuułuᑲiᑲaᑲ First Nation values the need to respect, protect and promote our heritage, culture and traditions which form the basis of our success and destiny while understanding that these practices may change and require contemporary expression.

It is the desire of the Yuułuᑲiᑲaᑲ First Nation that our Yuułuᑲiᑲaᑲ lands continue to provide the resources necessary to sustain us, preserve our traditional ways and culture, encourage self-sufficiency and security through economic development and growth and to provide a home for the Yuułuᑲiᑲaᑲ people forever.

It is also the desire of the Yuułuᑲiᑲaᑲ First Nation that economic development and growth on our Yuułuᑲiᑲaᑲ lands will be conducted in a way that is transparent and accountable and that will foster a safer, stronger, healthier, more financially secure and more sustainable community. To this end, the Yuułuᑲiᑲaᑲ First Nation encourages our citizens to participate in the planning process for development and growth in order to create the type of community we want to live in and be a part of and that meets our needs.

Economic development and growth on Yuułuᑲiᑲaᑲ lands will be carried out in a way that ensures our economic development and growth is socially, economically and environmentally sustainable.”

(Source: YFN Planning & Land Use Management Act 2011)

The District of Ucluelet and the Yuułuʔiłʔatḥ Government have adopted a protocol agreement, most recently updated in 2014, as a framework within which to advance our working relationship. The vision put forward in the protocol agreement is as follows:

Protocol Context

Our community vision is:

- A healthy community where the citizens of our population are united and share a sense of civic pride.
- A year round, diversified and healthy economy that yields growth which doesn't compromise the environment or what makes our communities unique.

Our collaborative organizational vision is:

- Effective governments, working towards common issues, as partners.

Shared Values

Our common values will serve as a foundation for our conduct and decision-making, and will guide us when prioritizing our interests, and determining the methods used to advance those interests. These values include:

Relationships

- trust
- integrity
- authentic communication
- cooperation
- transparency
- respect
- honesty

- mutual benefit
- patience
- fairness

Culture

- appreciation and celebration of different cultures
- traditions
- history

Social

- sense of community
- family
- reciprocity and giving back
- life long learning

Environment

- sustainability
- do no harm
- interconnectedness
- renewable energy

Objective 1A To recognise the interests and heritage of local indigenous people and communities.

Objective 1B To build and strengthen the relationship between the municipality and indigenous communities with a spirit of neighbourliness and mutual support, in this time of reconciliation.

The United Nations Declaration on the Rights of Indigenous Peoples (UNDRIP) was adopted by the UN General Assembly in 2007. In 2015 the Truth and Reconciliation Commission listed as the first principle for reconciliation that the UNDRIP, “Is the framework for reconciliation at all levels and across all sectors of Canadian Society.” The UNDRIP was officially adopted by the Government of Canada in 2016. In November of 2019 the Government of British Columbia passed the *Declaration on the Rights of Indigenous Peoples Act*; BC is the first Canadian province to start bringing its legislation in alignment with the UNDRIP.

Note that the District of Ucluelet is not a “State” and does not carry the legal weight of “the Crown”; the responsibilities of the Crown can not be delegated downward to local government by the Province. At the same time, as noted in the Truth and Reconciliation Commission *Calls to Action*, all levels of government - including local municipalities - have a role to play in healing relationships, building community and addressing the ongoing legacies of colonialism to create a more equitable and inclusive society.

Policy 1.1 The District of Ucluelet adopts the *United Nations Declaration on the Rights of Indigenous Peoples* as the framework for reconciliation (see Appendices).

Policy 1.2 Make every effort to build on the history of respect and mutual assistance which characterises the relationship between the municipality and the Yuułuᑭifᑦath and ‘tukʷaaᑦath Nations.

Policy 1.3 Endeavour to ensure that municipal facilities, functions and programs are welcoming and accessible to Indigenous members of the community.

Policy 1.4 Seek opportunities for mutual benefit when exploring topics of housing, economic development, transportation, utilities, tourism, emergency services and other matters which affect the wellbeing of our communities.

Policy 1.5 Use the protocol agreement between the District of Ucluelet and Yuułuᑭifᑦath Government as an avenue for dialogue and action on matters of mutual interest, where we come to the table as equal parties.

What is a ‘policy’?

Policy statements say what the District means to do. The policies in this plan should be read as if preceded by the words “The District of Ucluelet will...”

Point in Time & History; View to 2050

This OCP takes a 30-year view, looking ahead to how the community of Ucluelet will evolve to the year 2050 and beyond.

Written in 2020, this plan is a complete policy document to guide the community at this point in time, but also acknowledges specific areas where further work is necessary in the short term to adjust or more clearly define the community direction and priorities.

The following work, some of which is already underway (or budgeted and scheduled), will allow the District to update this plan in the near future to provide a true long-term vision:

- continued conversations with local indigenous communities
- priority housing actions including a community housing needs assessment
- completion of the long-term land use demand study, currently underway
- review and refinement of environmental development permit areas
- storm surge and tsunami modeling and refinement of flood construction levels, currently underway
- completion of the sewer master plan
- completion of an integrated stormwater management plan
- implementation of the Community Climate Change Adaptation Plan

An OCP attempts to take the long view, projecting a vision for how the community might evolve over the next decades. Written in 2020, in the midst of the COVID-19 pandemic, the long-range view is even less clear than it might have been – unprecedented and unforeseen change has challenged local priorities and upended global economies.

Some things have become clearer:

- The importance of community.
- The resiliency and adaptability of local businesses and workers.
- The fragility of supply chains and the benefit of diverse local economies.
- The restorative value of fresh air, open spaces and wild places.
- Ucluelet is a desirable place to live, visit, work and play – and will only become more so as time goes on. The pressures which come with increased visitation and migration can be balanced if Ucluelet maintains a clear view of those things that define, support and benefit the community.

Part Two: Place

Natural Environment

Ucluelet is characterised by the beauty of its landscapes and unique natural features including rocky beaches, old growth forests and a rich diversity of wildlife. This magnificent setting positioned on the edge of the Pacific Ocean greatly enhances the quality of life in Ucluelet by providing recreation areas, beautiful scenery and a healthy habitat for fish, wildlife and humans.

ECOLOGY

Ucluelet is home to rich plant and animal habitat due to the peninsula's interface between the terrestrial and marine environments. The ecosystems here are a complex and fragile array of diverse flora and fauna which depend on the health and resources of the ocean and temperate rainforest.

Terrestrial ecosystems provide a home to many large mammals such as bears, cougars and wolves. Bald eagles can be seen regularly soaring the air currents in skies above town.

The marine ecosystem surrounding the peninsula includes salmon, sea lions, otters, migratory and resident grey, humpback and orca whales, seabirds, and an additional 240 species of birds.

The backshore, intertidal zones and network of streams support an incredible diversity of life, providing habitat and spawning conditions which support both terrestrial and marine food chains.

The rich forests include coniferous species of Sitka Spruce, Balsam, Cedar, Western Hemlock, Douglas Fir and deciduous trees including Red Alder. Forest health and age is a critical component of the natural life and biodiversity of the area.

The moderate climatic conditions provide significant moisture, sufficient sunlight and mild winters resulting in abundant vegetative growth year-round.



WILDLIFE

Ucluelet and the surrounding region share the natural environment with an array of wildlife, including bears, cougars and wolves. The frequency of human contact with these large mammals increases as new lands are developed. As human development spreads out and encroaches upon wildlife habitat, the wildlife and human interaction increases.

As the foraging areas, migration paths and game trails for wildlife are overlain with human development and contact increases, normally submissive species such as bears, cougars and wolves can begin to become habituated to human activities. They may become accustomed to odours and noises and less afraid of cars, bicyclists and runners.

Game trails and migration pathways in the area that have existed for hundreds or even thousands of years are encroached upon by development causing animals to learn, evolve and cope with human activity. Within town limits bears are particularly drawn to berry patches and trash which is not bear-proofed.

Development in Ucluelet's future raises the potential for increased wildlife and human contact. Ucluelet promotes prevention measures to reduce wildlife impacts through a wildlife smart program.

Prevention methods include keeping garbage inside until the day of pick up, bear proof dumpsters, properly functioning compost and networks of communication between friends and neighbours about sightings. Prevention is a win-win situation because both people and wildlife benefit. It will be beneficial to the District of Ucluelet to continue working with the National Park Reserve on wildlife programs.

The District participated in a 'Human-Bear Conflict Management Plan' in 2005/2006. The priority actions identified in this plan are to bear-proof garbage and food attractants, and to identify and set aside habitat and corridors for wildlife as lands are developed within the District.

ENVIRONMENTAL PROTECTION

The District of Ucluelet is committed to the responsible stewardship of its natural resources and preservation of the local environment for future generations.

Respect for the natural environment is a key feature of Ucluelet's Official Community Plan vision. It provides the guiding framework upon which the following policies have been developed to further enhance and protect Ucluelet's diverse natural habitat.

Objective 2A To develop carefully and use land wisely to ensure that the most sensitive and valuable environmental features are protected, and ecological functions are not irreparably disturbed.

Objective 2B To manage municipal infrastructure and operations in ways that responsibly minimise impacts on the natural environment.

Objective 2C To encourage conservation of District and Regional resources.

Objective 2D To work with and support other agencies and groups who share the community's goal of protecting our environment.

New Development Permit Areas for the protection of the environment have been established by this OCP (see Schedule E and Section 6).

Policy 2.1 Use the regulatory tools available to local governments to ensure new development responds to the community's goal of maintaining a healthy, diverse natural environment.

Policy 2.2 Maintain significant areas of natural green space and forest cover. Large scale clearing to accommodate development is not supported.

Policy 2.3 Convene a community mapping workshop to capture local knowledge of locations and routes which are particularly important for local wildlife.

Policy 2.4 Identify natural corridors for public and wildlife use or as natural landscapes.

Policy 2.5 Foster and support local environmental stewardship and heritage protection groups.

Policy 2.6 Collaborate with non-profits, provincial and federal agencies on research, education and enforcement efforts aimed at protecting the environment.

Policy 2.7 Support efforts to establish an Indigenous-led landscape-scale West Coast Stewardship Corridor extending from the Southern to Northern regions of Vancouver Island.

Policy 2.8 Promote solid waste management practices - such as WildSafe BC bin closure protocols - to discourage attraction of wildlife.

Policy 2.9 Explore bylaw amendments and education for options to allow backyard husbandry of poultry while avoiding attracting wildlife by using appropriate electric fencing.

Policy 2.10 Explore, with public input, the merits of defining and initiating a system of municipal permitting prior to removal of the most significant, mature trees in the community.

Policy 2.11 Given that all land in the community is proximate to watercourses and the ocean, and given the significant rainfall experienced in Ucluelet, discourage the cosmetic use of pesticides anywhere in the District.

Policy 2.12 Lobby the provincial government to institute a province-wide system of regulating the cosmetic use and sale of pesticides.



CLIMATE ACTION

Mitigating greenhouse gas emissions and adapting to the impacts of climate change is viewed as one of the greatest challenges of our time. At the same time as communities throughout the world are struggling to prepare for a future without abundant, low-cost fossil fuels, the Greenhouse Gases (GHG) created by the world's current dependence on fossil fuels are creating devastating impacts on global ecosystems that are expected to last for many generations.

For our community the potential for sea-level rise, impacts to our water system increasing intensity of storm events, and impacts to fish stocks have a direct influence on our residents and businesses.

To address this challenge, provincial legislation requires that an Official Community Plan include targets for the reduction of greenhouse gas emissions and transition to renewable energy, and policies and actions the local government has proposed with respect to achieving those targets.

In establishing these targets, policies, and actions, it is important to understand the role and ability of local government to effect GHG reductions.

In 2018, Council committed to the Federation of Canadian Municipalities (FCM) Partners for Climate Protection (PCP) milestones program. The municipality achieved Milestone 2 for District emissions and Milestone 4 for community emissions in 2019 and is committed to achieving Milestone 5 for both categories by 2022.

The District will support emissions reductions through policies and programs in the following areas:

- Land Use and Development
- Transportation
- Renewable Energy
- Solid Waste and Waste Management
- Awareness, Education, and Outreach
- buildings
- public infrastructure and facilities
- community energy systems

Our Goals:

- Ucluelet residents are resilient to climate change and energy scarcity and costs.
- Transportation options reduce greenhouse gas emissions, fossil fuel dependence and the creation of air contaminants.
- New and existing buildings are energy efficient and use 100% renewable energy.
- The waste stream to the regional landfill is reduced to a minimum, with recovery, re-use, recycling and composting of resources undertaken as standard practice.
- Ucluelet relies on clean, renewable, and efficient energy sources.

The following are goals (objectives) identified in the recently adopted Ucluelet mitigation and adaptation plans.

Transportation

Objective 2E – Ucluelet attracts businesses so residents can access key services close to home.

Objective 2F – Ucluelet residents can safely move around town by foot, bike, scooter, or other low-carbon transportation modes.

Objective 2G – Ucluelet is connected to the region by reliable transit and an extended EV charging network.

Objective 2H – Ucluelet residents and visitors can charge electric vehicles at home, work, and popular destinations.

Buildings

Objective 2I – Ucluelet is connected to the region by reliable transit and an extended EV charging network.

Objective 2J – Existing residential and commercial buildings become energy efficient, comfortable, durable, and cheaper to operate through whole-building energy retrofits.

Objective 2K – Ucluelet transitions away from heating oil by 2030 in favour of renewable sources of heat such as heat pumps.

Waste

Objective 2L – Organic waste is diverted from the landfill due to a curbside collection program and on-site composting

Objective 2M – Single-use plastics are eliminated in favour of reusable and biodegradable alternatives.

Leadership

Objective 2N – The District integrates climate action into all municipal processes.

Objective 2O – The District leads by example by ensuring all buildings are energy efficient, by transitioning to a low-carbon fleet, and establishing zero-waste policies for operations and events.

Objective 2P - The District meets the community's 80% GHG reduction and 100% renewable energy targets for its municipal operations.

Adaptation

Objective 2Q – Strengthen infrastructure resilience and reduce risk to buildings and property.

Objective 2R – Enhance resilience of ecosystems and protect natural areas.

Objective 2S – Improve public safety and preparedness to climate-related events.

Greenhouse Gas Targets

Policy 2.13 The District will align its community targets with those established by the Province of BC in 2018. Using a 2007 baseline, those targets are:

40% GHG reduction by 2030

60% GHG reduction by 2040

80% GHG reduction with 100% renewable energy by 2050

Policies to positively influence the community's energy use and GHG emissions are found throughout the OCP, where the plan covers areas of land use, transportation, infrastructure and operations.

Part 6 of this plan also discusses GHG reductions and climate change adaptation policy in detail.

GHG Policies - Land Use and Development

Policy 2.14 Support the walkability and bike-ability of the community.

Policy 2.15 Require development planning for new areas to include infrastructure to support electric vehicle charging in residential, commercial and public places.

Policy 2.16 Support infill development near the Village Square to create a complete and compact core that is walkable, vibrant and attractive as a place to live, work and play without the need for a car.

Policy 2.17 Focus municipal and other government facilities within this compact core.

Policy 2.18 Support re-development to enhance Peninsula Road as the District's primary corridor, to promote the introduction of

local transit service (and higher transit frequencies than is possible with lower density development), including a potential transit connection between Tofino and Ucluelet, as well as Port Alberni.



GHG Policies - Transportation

Policy 2.19 Encourage pedestrian and bicycle facilities as part of all new development projects.

Policy 2.20 Expand infrastructure to support vehicle and cycling electrification in public places, businesses and residences.

Policy 2.21 Encourage and support regional organizations to convert their fleets to Zero Emission Vehicles.

Policy 2.22 Convert all light-duty vehicles to zero-emission vehicles in municipal operations including the integration of e-bikes where possible.

Policy 2.23 Expand the Wild Pacific Trail network as opportunities arise.

Policy 2.24 Work with other local communities to establish more frequent regional transit connections, including to Tofino, First Nations communities, the Tofino airport, and Port Alberni.

Policy 2.25 Encourage BC Transit to create local transit routes to serve most destinations within the community with a high level of service, and focus development along this transit corridor.

Policy 2.26 Work towards a future multi-modal transportation centre near the Village Square area to better link the District with air, water, and transit service providers with local transit, taxi, walking, and cycling facilities.

Policy 2.27 Provide weather protection at stops for future local and regional transit buses.

Policy 2.28 Support car-sharing and carpooling within the community, such as the creation of priority parking stalls for pool vehicles and/or facilitating a community carpooling database.

Policy 2.29 Support bike-sharing within the community, such as locating bike share racks within the Village Square area and at resort locations.

Policy 2.30 Encourage adequate, secure bicycle parking facilities at major destinations within the District.

Policy 2.31 Pursue opportunities to create bike lanes and multi-use paths within existing road allowances.

GHG Policies - Buildings

Policy 2.32 Require high-efficiency buildings in new developments and major renovations of existing buildings, with an aim to implement the provincial Step Code to raise the bar on energy efficiency.

Policy 2.33 Promote multi-unit, mixed-use buildings with shared walls that reduce energy losses.

Policy 2.34 Establish and undertake the work, as necessary, to refine Flood Construction Levels to ensure new development and infrastructure avoids the impact of rising sea levels.

Policy 2.35 Support the transition from heating oil to lower-carbon building heating systems.

GHG Policies - Public Infrastructure and Facilities

Policy 2.36 Review municipal infrastructure and assets for vulnerability to rising sea levels and increased storm events.

Policy 2.37 Establish policies that focus light energy only onto areas where illumination is required and restrict the spillover of light to the night sky and intrusion into adjacent properties.

Policy 2.38 Implement external lighting technologies that reduce energy consumption including a shift to LED lighting for all District and BC Hydro streetlighting

Policy 2.39 Where feasible, strive to design new public facilities with leading edge energy technologies that demonstrate leadership and provide local examples that can be applied to private sector buildings and facilities.



GHG Policies - Renewable Energy

Policy 2.40 Support the development of 100% renewable energy systems including a variety of energy sources, including biomass, solar voltaic, solar hot water, geothermal and sewer and wastewater heat recovery sources.

Policy 2.41 Maximise energy efficiency through district energy and heat recovery from industrial or commercial sources.

Policy 2.42 Explore the feasibility of renewable District Energy systems including potential pilot projects demonstrating technologies such as geothermal, tidal and wave energy.

GHG Policies - Solid Waste and Waste Management

Policy 2.43 To reduce energy and emissions associated with waste management, the District will consider enhancing programs to reduce waste, recycle and reuse waste where possible aiming for a goal of zero waste.

Policy 2.44 Work with the regional district to explore opportunities to promote individual or collective composting systems to reduce methane emissions from organic waste.

Policy 2.45 – Implement a single-use plastics bylaw in favour of reusable and biodegradable alternatives.

GHG Policies - Awareness, Education and Outreach

Policy 2.46 Distribute information on measures and incentives that individuals and businesses can take to reduce GHGs on the District's web site and public mailings, tax notices, etc.

Policy 2.47 Regularly communicate information on the issue of climate change and GHG reduction measures at public facilities, meetings and through electronic sources.

Policy 2.48 Support the sustainability goals of Tourism Ucluelet including their adopted 2020 strategy statement: *“By 2023 Tourism Ucluelet will lead Ucluelet's vibrant and sustainable tourism industry through industry collaboration, responsible and authentic promotion, visitor and community education, support for community priorities and accountability in our operations.”*

Climate Adaptation - Policies

Policy 2.49 Address vulnerabilities to electrical distribution infrastructure.

Policy 2.50 Conduct flood risk mapping for sea level rise and use results to communicate and manage risks.

Policy 2.51 Assess vulnerabilities of the Highway 4 transportation link.

Policy 2.52 Study current water systems and explore resiliency measures to make the existing water system more resilient.

Policy 2.53 Create an Invasive Species Action Plan.

Policy 2.54 Support local activities to maintain wild fish stocks and habitat.

Policy 2.55 Develop a Biodiversity Network Plan to ensure priority ecosystems are protected in municipal land-use planning bylaws.

Policy 2.56 Through the Integrated Stormwater Management Plan, create bylaws, policies or plans to protect habitats.

Policy 2.57 Complete Emergency Operations Centre (EOC) training and update EOC to continue to be prepared for extreme events.

Policy 2.58 Participate in a region-wide climate change dialogue and planning process with municipalities, First Nations, Parks Canada and BC Parks to expand and integrate the Ucluelet Climate Change Adaptation Plan into future projects.

Actions Plans – Mitigation and Adaptation Plans

Policy 2.59 Implement the *Clean Energy for the Safe Harbour District of Ucluelet 100% Renewable Energy Plan* (2019).

Policy 2.60 Implement the Ucluelet Climate Change Adaptation Plan.

Policy 2.61 Report to Council annually on the progress of mitigation and adaptation efforts in the Annual Report.

Policy 2.62 By 2022, achieve Milestone 5 for Community and Corporate emissions in the Federation of Canadian Municipalities (FCM) Partners for Climate Protection (PCP) milestones program.

Parks, Trails and Open Space

Our Goals:

A connected and legible parks and trails network which supports:

- active, healthy and connected ways of living
- an unparalleled experience of the natural and cultural landscapes of the Ucluth Peninsula
- the further development and diversification of the town's economy

The parks, trails and open spaces within the District of Ucluelet contribute to the unique character and sense of place which defines our community. The parks network includes nature parks, community parks, neighbourhood parks, trails, beach accesses, greenbelts and road edges.

Key parks, trails and open spaces in Ucluelet are identified on Schedule C: Parks and Trails Network.

Objective 2T Recognize, enhance and protect key areas for biodiversity and sensitive marine, terrestrial, and riparian ecosystems within the parks and trails network.

Objective 2U Build on the success of the Wild Pacific Trail and expand the experience of this unique ribbon of the coastal landscape, ultimately connecting beyond the municipal border to Pacific Rim National Park Reserve.

Objective 2V Anticipate growth in the community and tourism sector, and respond by expanding the parks and trails network to meet the needs and demands of residents and visitors.

Objective 2W Provide a diverse, inclusive range of activities and experiences among the parks and trails network, accessed and enjoyed by people of all ages and abilities.

Objective 2X Develop a municipal network of parks, trails and open spaces designed, constructed and maintained to strike a balance between:

- maximum experience for citizens and visitors
- infrastructure affordable to our small-town tax base
- appropriate “Ukee” character which reflects our west coast setting

PARKS

The 2013 Parks and Recreation Master Plan (PRMP) identifies a number of strategies to guide the future of the municipal parks and recreation functions. The following policies incorporate the recommendations of the PRMP:

Policy 2.63 Park land dedication and acquisition is a key strategy in conserving the District’s natural areas and ecosystems.

Policy 2.64 Existing parks and trails are to be maintained and protected for public use and environmental preservation.

Policy 2.65 When acquiring new park land, facilities, or trails include the operational and maintenance costs in long-term financial planning and budgeting.

Policy 2.66 Budget for the continued maintenance and replacement of parks equipment and assets.

Policy 2.67 Review and set standards for signage, access and site furnishings at trailheads, trail connections and beach accesses.

Policy 2.68 Develop an integrated plan for improving and connecting public open spaces and pathways.



Policy 2.69 The priorities for new parks & trails projects are:

- improve sidewalks, pathways and connected public realm areas in the vicinity of the Village Square
- extend the Wild Pacific Trail as shown on Schedule C
- create and extend the Safe Harbour Trail as shown on Schedule C
- create a connected pedestrian route along the Small Craft Harbour connecting to the Village Square
- improve the Coast to Coast Connection between the Village Square and Big Beach
- improve accessible, safe viewing opportunities and re-purpose the Lightkeeper’s House at Amphitrite Point
- improve signage and wayfinding to identify pathways, key locations and public facilities

Future parks & trails projects could include:

- new parks in the former Forest Reserve areas
- improved public access to harbor via end-of-road parks
- hard sports surface / fieldhouse / concession / foodbank / emergency staging area at Tugwell Field
- a new park and perimeter trail on Hyphocus Island
- a Japanese Memorial Garden
- a new park near the terminus of Peninsula Road
- additional active recreation facilities (e.g., frisbee golf course, fitness trail, etc.)
- a community boathouse supporting opportunities for kayak / canoe / row / sail programs
- explore feasibility of alternative energy (geothermal / tidal / wave) outdoor pool and/or hot pool

TRAILS

Visitors and residents alike experience Ucluelet by moving through the landscape of the peninsula on a network of world-class trails. This expanding network is the result of the vision, commitment and hard work of the community. The trails serve as a public amenity and also as an economic driver – bringing visitors to the community and enticing them to return. Continued expansion and improvement of the trail network will be key to achieving the goals of this plan.

Wild Pacific Trail

Objective 2Y A continuous Wild Pacific Trail following the exposed outer shore along the length of the peninsula.

Policy 2.70 As development extends into former Forest Reserve lands, it is the District’s aim to see the Wild Pacific Trail extend along the entire shoreline of the municipality.

Policy 2.71 Explore with property owners, the Alberni Clayoquot Regional District and the Yuułu?if?ath First Nation the opportunity to extend the Wild Pacific Trail northward beyond the municipal boundary to connect with the Pacific Rim National Park Reserve.

Policy 2.72 Trails created in new development areas should be located in a network of dedicated public land (highway or park dedication) of sufficient width to maintain the character and experience of the landscape for both trail users and neighbours. Creating public access through statutory rights-of-way over private land should be seen as a next-best solution to be used only in extenuating circumstances.

Safe Harbour Trail

Objective 2Z A continuous Safe Harbour Trail following the shore of the Ucluelet Inlet wherever possible and, where interrupted by

existing residential or marine commercial activities, connecting seamlessly with town pathways.

Policy 2.73 Use existing and new rights-of-way to create new sections of trail along the shoreline of Spring Cove, Hyphocus Island, the Inner Boat Basin and Olsen Bay.

Policy 2.74 As development extends northward along the inlet, create a connected Safe Harbour Trail along the shoreline wherever possible.


Policy 2.75 Make pedestrian pathway connections and improvements a priority in the vicinity of the Village Square and extending outward along Peninsula Road and Matterson Drive. Once sections of sufficiently safe and connected pathways are linked, identify and promote these sections to form a walking tour connecting the Village Square to the Inner Boat Basin, Imperial Lane, Big Beach and other parts of town.

Regional Trails

Objective 2AA A connected network of trails linking Ucluelet with the broader regional landscape.

Policy 2.76 Support the Alberni Clayoquot Regional District area 'C' OCP policy of developing the West Coast Telegraph Trail connecting Ucluelet to Toquart Bay.

Policy 2.77 Support regional efforts to create a seamless Multi-Use Pathway traversing the west coast, and continue to maintain (through updated servicing agreement) the section of pathway between the Ucluelet municipal boundary and the Pacific Rim National Park Reserve.



OPEN SPACE & GREENBELTS

Significant areas of public land are found on the edges of roads (legally termed areas of “highway” dedication). Some are maintained as more manicured boulevards while many are less formal, containing ditches, natural vegetation and sometimes trails. These spaces provide green space and also important habitat and movement corridors for birds, insects and other wildlife.

Policy 2.78 Minimise driveway cuts and pavement within public highways to the areas necessary for safe pedestrian and vehicle movements and parking.

Policy 2.79 Develop a program for planting street trees in the vicinity of the village centre, with Peninsula Road being a priority.

Policy 2.80 Develop a program and budget for gradually upgrading public access to the ocean (physical or visual) wherever possible, including the undeveloped road ends of Matterson Drive, Alder Street and Norah Street.

Transportation and Movement

By land, Provincial highway #4 connects Ucluelet and the Ucluth Peninsula to the eastern side of Vancouver Island. The Tofino-Ucluelet Airport, located approximately 24km to the northeast within the Pacific Rim National Park Reserve, serves people traveling by private and commercial airplanes.

The Francis Barkley provides marine passenger and cargo ferry service from Port Alberni to Ucluelet Harbour. Canada Customs Service provides customs clearance in the harbour for marine visitors.

People travel to and within Ucluelet predominantly by car. Transportation is a key factor of how residents and visitors experience community life and the landscape.

Transportation is a key policy area from a broader community planning perspective, as the greatest component of the District's greenhouse gas emissions with the best potential for GHG reductions.

The 2011 Transportation Plan concludes that additional vehicle capacity is not required on District roads for the foreseeable future, recommending that capital projects be focused on safety upgrades and strategic improvements to pedestrian and cycling infrastructure.

The eventual extension of Marine Drive to create a parallel collector route will be pursued as development occurs on the former Forest Reserve lands.

Ucluelet's long narrow peninsula has contributed to an accessible walking environment as one can walk to most places in the community in approximately 15 minutes. The relatively

short distances between the Village Square, most retail services, the Community Centre and beaches (within one kilometre of most homes) fosters walking and cycling throughout the community.

Given the unique outdoor setting of this area, walking and cycling will continue to be encouraged and supported, and will be a significant component of future transportation improvements within the District.

Recognising that Ucluelet is a small town with limited financial capacity for capital improvements, construction of new sidewalks and extension of the multi-use pathway will be prioritised with a focus on key functional requirements, such as circulation within the Village Square, and access to schools and the Community Centre with their associated recreation, culture and sports activities.

Our Goals:

- People rely less on fossil-fueled private automobiles
- People enjoy more and safer walking and cycling on an expanded network of active transportation pathways and facilities
- Harbour facilities protect the marine environment while providing even better access and support for both commercial and recreational boat traffic

Objective 2BB Develop a transportation network which enables people to move throughout the community safely, conveniently and beautifully.

Objective 2CC Prioritise transportation infrastructure needs and capital spending to maximise value for local residents, businesses and visitors.

Objective 2DD In order to reduce GHG emissions, encourage active and electric forms of transportation as a viable and routine alternative to the private automobile.

Objective 2EE Develop a network of safe bicycle and pedestrian routes throughout the District;

Objective 2FF Integrate transportation and land use management to help sustain a compact and walkable community.

Objective 2GG Create a safe and efficient transportation system for the movement of people and goods within the District.

GENERAL TRANSPORTATION NETWORK

Policy 2.81 Given that road capacities are sufficient for the foreseeable future, shift attention from roads and road capacity to prioritise pedestrians and cycling.

Policy 2.82 Promote mobility opportunities which minimise greenhouse gas emissions.

Policy 2.83 Within the 5-year Financial Plan, prioritise transportation needs while recognising funding constraints and managing expectations.

Policy 2.84 Incorporate low impact design principles and minimise paved cross-sections in an updated Subdivision and Development Servicing Standards bylaw.

Policy 2.85 When reviewing development applications consider low-impact street standards, which could include narrower travel lanes, parking bays/pull-outs, low design speeds (tighter radii, steeper curves and some sight line restrictions) and heavily landscaped boulevards.

Policy 2.86 Initiate a 30 km/hour speed limit on Peninsula Road and Matterson Drive.

Policy 2.87 Ensure new development improves connections to Peninsula Road and the Pacific Rim Highway as the District's primary corridor, to promote improved local and regional transit service.

Policy 2.88 As the former Forestry Reserve lands develop, extend Marine Drive to the northwest to provide a secondary parallel route along the length of the Peninsula. A connected network and enhanced access for emergency services is a community priority.

Policy 2.89 Acquiring the ability to extend Marine Drive, by dedication of sufficient public highway, is a community priority and may be pursued ahead of the construction or development of adjacent public lands.



NETWORK IMPROVEMENTS - VILLAGE CENTRE

Policy 2.90 Ensure that safe, barrier-free access for all is provided in the design and modification of new streets, sidewalks, and pathways.

Policy 2.91 Partnering with the Ministry of Transportation and Infrastructure where possible, complete a detailed roadway and intersection design for streets in the village core to develop “shovel ready” streetscape segments in preparation for future capital budgeting and grant opportunities.

Policy 2.92 As identified in the Parks and Recreation Master Plan, complete a detailed review and prioritised plan for improvements to the parks, pedestrian walkways and open spaces in the vicinity of the Village Square for consideration in the 5-year financial plan.

Policy 2.93 Include landscaped boulevards, traffic calming measures and continuous pedestrian pathways on Peninsula Road and Main Street.

Policy 2.94 Pursue streetscape improvements on Main Street down to the Government Wharf, i.e. move parked cars away from the existing sidewalk and formalise parking through line painting and signage;

Policy 2.95 Upgrade Peninsula Road in phases in the following sequence:

- Main Street to Bay Street
- Bay Street to Lyche Road
- Lyche Road to Seaplane Base Road
- Seaplane Base Road to Forbes Road
- Main Street to Marine Drive

Policy 2.96 Improve the efficiency, safety and on-street parking opportunities of Peninsula Road in the long term by:

- reducing the number of access points by sharing between adjoining property owners wherever possible
- reducing the width of access points to 6 metres
- removing as many driveway access points to Peninsula Road as practical

Policy 2.97 As development occurs, connect Cedar Road to Lyche Road.

Policy 2.98 Maximise on-street parking through street improvements on Cedar Road, Helen Road and Larch Street.

Policy 2.99 Explore phase 2 improvements to the newly acquired Cedar Road visitor hub to link air, water, and transit services with local transit, taxi, walking, and cycling facilities.



MARINE TRANSPORTATION

Policy 2.100 Support the Harbour Authority in providing improved public access for commercial and recreational use of the Ucluelet Harbour and surrounding marine areas.

Policy 2.101 Encourage the Harbour Authority to continually improve the environmental performance of its operations, and to encourage mariners to respect and protect the marine environment.

Policy 2.102 Improve options for boat trailer parking near the ramp at Seaplane Base Road.

Policy 2.103 Recognise the need for safe and environmentally responsible marine fueling services which support the local economy. Ensure existing marine fuel services are zoned appropriately.

Policy 2.104 Recognise the contribution marine services industries make to the local economy and ensure existing marine service businesses are zoned appropriately.

Policy 2.105 Explore the feasibility of establishing a regular water taxi service between key points on both sides of the Ucluelet Inlet.

Policy 2.106 Explore opportunities to improve public access to the ocean via District-owned lands.

PEOPLE ON FOOT

Our Goals:

The District endorses the following pedestrian charter:

- Ucluelet recognises that walking is a key indicator of a healthy, efficient, socially inclusive and sustainable community
- Ucluelet acknowledges universal rights of people to be able to walk safely and to enjoy high quality public spaces at any time
- Ucluelet strongly supports community design and the provision of adequate infrastructure and facilities that foster safe, convenient, direct and comfortable pedestrian travel
- Ucluelet is committed to reducing physical, social, safety and institutional barriers that limit walking activity

Policy 2.107 Prioritise pedestrian improvements which provide safe routes to the schools and the Ucluelet Community Centre.

Policy 2.108 Update the subdivision and development standards to require construction of appropriate vehicle, pedestrian and bicycle facilities as part of all new development projects.

Policy 2.109 Focus pedestrian and cycling improvements along Peninsula Road, Matterson Drive and Marine Drive, as shown on Schedule B: Transportation Network.

Policy 2.110 Develop a prioritised plan for pedestrian improvements in the Village Square area and links to other parts of the community to maximise the comfort and safety of residents, and so that a safe and legible Walking Tour can be offered to visitors.

PEOPLE ON BICYCLES

Policy 2.111 Work to implement the bicycle route network as shown on Schedule B: Transportation Network

Policy 2.112 Support the development of recreational walkways and/or multi-use trails throughout the municipality, providing links between major park and open space areas. These walkways may be off-road or adjacent to roadways, and generally follow the alignment of the trail system shown on Schedule C.

Policy 2.113 Ensure adequate, secure bicycle parking facilities at major destinations within the District.

Policy 2.114 Support extension of the paved multi-use trail to Tofino, in partnership with the District of Tofino, Parks Canada, the Alberni Clayoquot Regional District, local First Nations and other agencies.

Policy 2.115 Encourage local efforts to expand mountain biking trails, access and mapping in the vicinity of Ucluelet, including lands in the Barkley Community Forest.

PEOPLE ON TRANSIT

Policy 2.116 Identify priority locations for improved bus stop facilities including weather protection.

Policy 2.117 Advocate with BC Transit for service connecting the entire community, spanning the length of the peninsula to the Amphitrite Point lighthouse.

Policy 2.118 Work with other local communities, BC Transit and Tofino Bus Services to establish higher frequency regional transit services including Tofino, the airport, and Port Alberni.

PEOPLE IN AUTOMOBILES


Policy 2.119 Include electric vehicle charging facilities at municipal parking lots, where feasible.

Policy 2.120 Support car-sharing and carpooling within the community, such as the creation of priority parking stalls for pool vehicles and/or facilitating a community carpooling database.

Policy 2.121 Explore overnight visitor parking solutions for people using Ucluelet as a launching point for marine tours.

Policy 2.122 Identify and provide directional signage to appropriate seasonal RV parking locations in the vicinity of the Village Square.

Policy 2.123 Discuss with the School District options for permitting time-limited RV parking at the Elementary and High Schools during the summer months.



PEOPLE MOVING FISH

Policy 2.124 Recognising the value provided by truck delivery and hauling services, aim to ensure safe use of District roads by all road users while enabling appropriate truck access.

Policy 2.125 Explore alternatives to improve truck movements and pedestrian safety in the vicinity of the Village Square.

Policy 2.126 While recognising the need for short-term truck staging on Alder Street to access the active marine industries on Eber Road, work to improve road surface and pedestrian safety in this area.

Policy 2.127 Encourage truck staging and storage on appropriately zoned light industrial lands.



Part Three: People

Community Health, Safety and Wellbeing

Our Goals:

- a thriving community of healthy, active, engaged citizens of all ages
- a resilient and prepared community of neighbours who help one another
- a vibrant cultural scene – inclusive of all cultures and walks of life
- equitable access to a variety of recreation and lifelong learning opportunities

FIRE AND EMERGENCY SERVICES

Fire and Emergency Services supports and maintains a community emergency management system through mitigation, preparedness, response and recovery initiatives for emergencies and disasters.

The Ucluelet Volunteer Fire Brigade has been providing fire protection services for the community for over 70 years. Each year the UVFB responds to an average of 110 callouts for fire, motor vehicle accidents and medical first responder calls.

The Emergency Support Services team is responsible for coordinating efforts to provide shelter, food, clothing, transportation, medical services and reunification services to victims of emergencies and disasters.

Ucluelet and the entire west coast of Vancouver Island are isolated. Road access is via Highway # 4, a difficult road to travel under normal conditions. As a result, the District will consider local responses to emergency situations and not rely on Highway # 4 or Peninsula Road to evacuate the community elsewhere.

A tsunami triggered by a local earthquake could reach Ucluelet within 10 – 15 minutes; therefore emergency personnel will not have sufficient time to warn residents of the impending danger. The District will work to raise awareness of immediate evacuation plans, which should consider evacuation routes to areas of high ground.

The Ucluelet Emergency Network (UEN) utilises a “four pillar” approach of mitigation, preparedness, response and recovery.

The UEN is a multi-jurisdictional committee that consists of representatives from:

BC Ambulance Service
 Canadian Rangers
 District of Ucluelet
 Emergency Support Services
 Pacific Rim National Park
 Royal Canadian Mounted Police
 Royal Canadian Marine Search and Rescue
 School District 70
 ‘tukwaa?ath (Toquaht Nation)
 Ucluelet Volunteer Fire Brigade
 West Coast Inland Search and Rescue
 Yuułu?if?ath (Ucluelet First Nation)

The areas identified as high ground in Ucluelet are:

- High School and associated fields;
- Tugwell fields;
- Top of Hyphocus island;
- Upper parts of Millstream; and
- High points on Reef Point and Coast Guard Roads.

Objective 3A Support, recognise and celebrate the contributions made by the members of the Ucluelet Volunteer Fire Brigade and other community organizations.

Objective 3B Increase community capacity to respond to emergencies.

Policy 3.1 Complete a community risk assessment and identify current and future needs for emergency services.

Policy 3.2 Analyse future growth potential and infrastructure needs to ensure the community can sustain and afford the necessary emergency and infrastructure services.

Policy 3.3 Provide emergency services facilities, equipment and resources that are adequate and affordable for the size of the local and visitor populations.

Policy 3.4 Identify and prioritise any infrastructure gaps which could affect the ability to respond to emergencies.

Policy 3.5 Explore opportunities for efficiency and funding of a combined new community safety facility (i.e., serving fire, ambulance, police).

Policy 3.6 Work with neighbouring communities to maximise efficiency and capacity for providing appropriate regional

emergency services, by exploring opportunities for shared services and/or servicing agreements.

Policy 3.7 Support the Ucluelet Emergency Network’s efforts to continuously improve community training, awareness and preparedness for emergency events.

Policy 3.8 Support regular practice including evacuation drills utilizing the existing road network and facilities within the community.

Policy 3.9 Improve tsunami evacuation route signage for prone areas, directing people to the closest high ground area.

COMMUNITY SAFETY

The municipal Building Inspection, Bylaw Enforcement and Business Licencing functions ensure that land uses, building construction and activities in the community are conducted in ways which are safe, equitable and respectful of potential impacts on neighbours.

These functions, in coordination with the level of service provided by local Fire and Emergency Services, also affect land values and insurance rates within the community.

Objective 3C Ensure all buildings within the municipality meet the minimum health and safety standards set by the BC Building Code to ensure they are safe for their intended use.

Objective 3D Ensure the use of land and buildings within the municipality complies with provincial and municipal standards, in order to lower risks to the community, protect the environment and ensure the safety of first responders.

Objective 3E Ensure land uses and business activities protect the environment, respect neighbours and foster a positive welcoming impression among residents and visitors.

Policy 3.10 Implement a system of appropriate regular fire inspections tailored to building uses, community capacity and level of risk.

Policy 3.11 Provide a thorough and efficient system of building permitting and inspections.

Policy 3.12 Provide an efficient and equitable system of business licensing, and explore opportunities to promote licensed businesses through a local business registry.

Policy 3.13 Foster increased awareness and local knowledge of building and fire safety codes, standards and bylaws through such means as providing permit checklists, application guides and educational opportunities.

Policy 3.14 Develop a municipal bylaw enforcement policy to clearly communicate expectations and priorities for the monitoring and enforcement of bylaws to ensure community health, safety, wellbeing and positive visitor experience.

Policy 3.15 Regularly review municipal policies and bylaws with an aim to minimise regulation to only that which is necessary to achieve community objectives of maintaining health, safety, wellbeing, protection of the environment and reducing situations of conflict and nuisance.



HEALTH AND WELLBEING

Ucluelet residents are served locally by the Tofino General Hospital and the Ucluelet Medical Clinic.

More comprehensive, extended medical care is available in Port Alberni and Nanaimo. A range of massage, chiropractic, physiotherapy and other health-related services are also available in Ucluelet and Tofino.

Health and fitness classes are provided by local private providers and at the Ucluelet Community Centre – all supporting active lifestyles and community health.

Objective 3F Foster improved local health resources serving all citizens, including vulnerable populations.

Objective 3G Provide inclusive and equitable municipal services and recreation programs.

Objective 3H Pursue the five goals from the “pathways to wellbeing” by the Canada Parks and Recreation Association to foster:

- active living
- inclusion and access
- connecting people and nature
- supportive environments
- recreation capacity

Objective 3I provide the best in recreation, tourism and parks services to positively affect the overall health and well-being of the community.

Objective 3J Provide inclusive opportunities for quality recreational services, community events, conferences,

workshops, and gatherings through outstanding programs, facilities and customer service.

Objective 3K Work to make District programs, services and events more accessible, following the recommendations of the Age-Friendly Action Plan.

Policy 3.16 Support efforts to retain and improve local medical facilities, specialist options and improve transportation options to out-of-town medical services.

Policy 3.17 Support the expansion of convenient and affordable transportation options to access medical and other essential services for people of all ages and abilities.

Policy 3.18 Design and improve public facilities and spaces to be inclusive. Make accessible design a priority for major facilities within the walkable core of town (i.e., between the community centre and the Village Square).

Policy 3.19 Continuously look for opportunities to improve access to community buildings and programs.

Policy 3.20 Look for opportunities to improve access to public washroom facilities in strategic locations.

Policy 3.21 Improve the pedestrian environment with a priority emphasis on sidewalks, crosswalks, seating, lighting and visibility in the vicinity of the Village Square and UCC.

Policy 3.22 Develop and maintain all-ages accessible facilities, trails and/or viewpoints in appropriate key locations within the parks and trails network.

Policy 3.23 Explore avenues to better communicate opportunities for all members of the public to participate in civic events, programs, services and discussions.

RECREATION

The District operates the Ucluelet Community Centre (UCC) as the hub of recreation programs, civic engagement, cultural and special events. This gathering place has been developed with the goal of offering something of value to everyone in the community.

The Ucluelet Parks and Recreation Master Plan and Age Friendly Action Plan guide the continual re-evaluation of District facilities and programs, to provide program excellence and high participation by community members and visitors.

Objective 3L Continually evaluate and adjust to meet the needs of the community through recreation programs, Arts and Culture initiatives and event support.

Objective 3M Continue to invest in and present the District's diverse arts and heritage mosaic.

Objective 3N Continue to evaluate trends in facility use, community needs and resources necessary to serve the interests of a diverse population.

Objective 3O Deliver and support excellent services in partnership with aligned organizations, including the School District, non-profit organizations and the private sector.

Objective 3P Ensure that recreation programs, cultural activities and special events remain relevant and responsive to the needs and interest of Ucluelet area residents.

Policy 3.24 Continue to undertake a comprehensive assessment of recreation and cultural programs and special events.

Policy 3.25 Support and celebrate the strong local spirit of volunteerism by fostering connections to volunteer opportunities, and by celebrating and recognizing volunteer contributions.

Policy 3.26 Review the grant-in-aid policy to provide an appropriate level of support to organizations providing services to the community.

Policy 3.27 Continue to use the UCC as the inclusive focal point for delivering universal programs for people of all ages and abilities.

Policy 3.28 Provide space and support for programs provided by other community agencies including:

- West Coast Community Resources Society
- Ucluelet Children's Daycare Centre
- Vancouver Island Regional Library



FOOD SECURITY

Objective 3Q Residents have access to healthy food and opportunities to grow, harvest and buy local food.

Policy 3.29 Encourage and support opportunities for direct seafood sales at appropriate facilities in the Harbour.

Policy 3.30 Support community gardens on appropriate public lands.

Policy 3.31 Encourage opportunities for food production and gathering on appropriate lands in the Barkley Community Forest.

Policy 3.32 Support appropriate wildlife-smart organic waste composting.

Policy 3.33 Support the implementation of the Coastal Addendum to the Alberni Agriculture Plan.

Policy 3.34 Identify, build and maintain food storage and processing facilities which can serve to provide duplicate capacity in case of community emergencies (e.g., food bank, UCC kitchen, schools, etc.).

Policy 3.35 Explore the feasibility of a combined fieldhouse, emergency muster station and foodbank at Tugwell Field.

Policy 3.36 Explore opportunities for teaching food growing, preparation and preserving within educational and recreation programs, including after-school kids' programs.

HERITAGE AND CULTURE

Heritage and Cultural Conservation

The Ucluth Peninsula has been inhabited for thousands of years by the Yuułuᑭᑦᑭᑦᑭᑦ (Ucluelet First Nation). Many ancient sites and artefacts are scattered throughout the District.

There is a legal and moral obligation to conserve these sites and materials. Archaeological sites are managed under the provincial *Heritage Conservation Act*. This Act provides for the protection and conservation of British Columbia’s archaeological resources. Under the legislation, archaeological sites are protected whether their location is documented or not.

Cultural heritage resources are different than archaeological sites, and are also of significant value. These sites will often lack the physical evidence of human-made artefacts or structures, but will retain cultural significance to one or more living groups of people.

Examples include such things as ritual bathing pools and resource gathering sites. Effective implementation will require a positive working relationship between the Yuułuᑭᑦᑭᑦᑭᑦ and the District.

The Yuułuᑭᑦᑭᑦᑭᑦ Government has provided archaeological and cultural potential mapping which highlights areas considered to be of very high archaeological potential (see Map 3); this includes the marine foreshore and all areas 150m inland around the shore of the Ucluth Peninsula, plus old-growth forest ecosystems.

Known affectionately by locals as “Ukee,” Ucluelet’s rich history is commemorated today in place names, local events and built environments. A number of sites are recognised as having heritage value, including:

- St. Aidan on the Hill church site at Main Street and Peninsula Road
- Plank roads and boardwalks that once connected parts of the community (and recalled in signage installed by the Ucluelet and Area Historical Society along portions of the Wild Pacific Trail)
- Japanese community post-war settlement at Spring Cove and other locations
- Seaplane Base Road and Recreation Hall area
- George Fraser property, gardens and farm south of Peninsula Road
- Imperial Lane and the Whiskey Dock

Ucluelet boasts a vibrant artistic community, being home to many artists and cultural events. In addition to showcasing the area’s culture, history and natural wonders, these events provide important social gatherings for residents and draw large numbers of visitors.

Heritage and culture together form a strong part of Ucluelet’s identity and also generate tourism and other economic development opportunities.

Objective 3R To preserve archaeological, historical and cultural features.

Objective 3S To identify areas of the Ucluth Peninsula with major potential for archaeological and cultural sites.

Objective 3T To celebrate the local culture of the Ucluelet community.

Policy 3.37 Develop, in partnership with the Yuułuʔiłʔatḥ Government, a protocol for referral and input on development proposals within the areas of high archaeological and cultural potential identified on Map 4.

Policy 3.38 Develop, in partnership with the Yuułuʔiłʔatḥ Government, a joint Heritage Alteration Permit and protocol / servicing agreement for archaeological and cultural guidance on municipal works and operations within the areas of high archaeological and cultural potential identified on Map 4.

Policy 3.39 Work with the Yuułuʔiłʔatḥ First Nation, the Heritage Conservation Branch and local historians to identify archaeological and cultural sites, features and place names.

Policy 3.40 Work with local historians and the Heritage Conservation Branch to locate, identify and record all significant heritage and cultural features and sites.

Policy 3.41 Development proposals will be reviewed in relation to existing and possible archaeological sites, and where sites are apparent, the owner will be notified of their responsibility for complying with the requirements of the provincial Heritage Conservation Branch.

Policy 3.42 Support the documentation and build awareness of heritage places (natural or cultural), buildings, artefacts and landscapes in the community.

Policy 3.43 Seek First Nations' input on District heritage and cultural matters and events.

Policy 3.44 Invite input from the Yuułuʔiłʔatḥ on the use of traditional names in areas of significance to the indigenous community, and to find opportunities to highlight the Nuu-chah-nulth language where appropriate.

Policy 3.45 Roughly half of the existing street names in Ucluelet are nouns; invite input from the Yuułuʔiłʔatḥ on Nuu-chah-nulth translations of these names, and explore opportunities for a bilingual street sign program.

Policy 3.46 Work with property owners through the Development Permit process to encourage building and site design that reflects Ucluelet's west coast and fishing village heritage.

Policy 3.47 Facilitate the provision of gathering spaces throughout the community, with particular emphasis on the Village Square and the Community Centre.

Policy 3.48 Support the Ucluelet and Area Historical Society in planning for a future museum and/or venues for historical cultural displays and archives.

Policy 3.49 Support heritage preservation and stewardship of District-owned heritage resources.

Policy 3.50 Encourage the preservation of privately-owned heritage properties and consider incentives for heritage conservation, by means such as zoning bonuses through Heritage Revitalisation Agreement.

Policy 3.51 Identify and connect places of historical significance as part of the future Ucluelet walking tour;

Policy 3.52 Support community cultural events that celebrate and build cultural experiences for residents and visitors and foster further understanding and connection to this place.

Policy 3.53 Surfing is good.



Policy 3.54 Artwork illustrating this document was generously provided by local artists Katsumi Kimoto and Marla Thirsk. To seek illustrations for future updates to this plan, the District will issue a broad call for submissions by local citizens and artists to “draw your community”.

Land Use, Housing and Managed Growth

LAND USE CATEGORIES

To put the guiding principles of this OCP into effect, the long-range land use for all areas of the municipality have been designated as shown on Schedule A, “Long-Range Land Use Plan”. Descriptions of each land use designation are summarised below. Note that current land uses and zoning may differ from the long-range designation for any given property. Over time, as properties redevelop the zoning and use of the land should align with the designated uses noted in this plan.

Also note the District may consider requests to down-zone properties to recognize existing non-conforming land uses (brought about by past blanket rezonings), without triggering an amendment of this OCP even if the existing / interim use does not match the long-range uses anticipated on Schedule A.

Commercial

Village Square Commercial

This designation applies to the village square and includes a broad range of mixed uses.


These may include retail uses, offices, restaurants, tourist accommodation, financial, cultural and community services, and

multi-family residential (e.g. apartments and residential units above retail stores).

Compact, high density, mixed-use buildings which respect the existing character of the neighbourhood are encouraged

Service Commercial

This designation generally applies to portions of Peninsula Road between Forbes Road and Bay Street. It includes uses such as motels, restaurants, personal and retail services, service stations and automobile repair.



Tourist Commercial

This designation includes visitor accommodation (e.g. hotels, motels, hostels, guesthouses), marinas and other supporting uses such as kayak and bike rentals.

Long-term residential uses in the vicinity of the centre of town is supported, therefore a mix of residential uses, including

employee housing, may also be included in the zoning of areas designated Tourist Commercial in this location.

Neighbourhood Commercial

This designation applies to individual lots or small commercial nodes providing small-scale commercial services compatible with surrounding land uses and primarily serving lands within convenient walking distance.

Parks and Open Space

This land use designation applies to the District's parks, playgrounds, trail network and green spaces. This includes nature parks, community parks, neighbourhood parks, trails and greenbelts. Lands with this designation may also include a variety of public institutional uses such as the Coast Guard facilities at Amphitrite Point, water towers, the Ucluelet Community Centre, etc., which are compatible with the surrounding public park context.

Note that the Schedule 'A Longe-Range Land Use Plan may indicate Parks and Open Space designation across areas of private land; these generally indicate areas with high habitat values, flood potential and/or potential for pathway connections. This may indicate where there are existing rights-of-way, or where desired open space areas should be considered and could be determined in detail at the time of future development approvals.

Single-Family Residential

This designation includes detached single-family homes and duplexes. Single-family properties may include secondary suites, accessory dwelling units, home occupations and guest accommodation.

Some small-scale multi-family land uses exist within single-family neighbourhoods. Further small-scale development of multi-family uses - which demonstrate how they fit within the neighbourhood context specific to their location - may also be approved within these areas without amendment of this OCP

Multi-Family Residential

This designation includes multi-family residential housing of medium to high-density. This includes row houses, cluster housing, townhouses and apartment buildings.

This designation may also include small-lot single-family subdivision or cluster developments which achieve similar densities.



Industrial

Light Industrial

This designation provides for a variety of light and medium industrial uses, such as food processing and wood-based manufacturing industries, including service commercial and light industrial uses. This designation applies to lands along Forbes Road.

Marine Industrial

This designation applies to the upland side of commercial marine properties and provides for a variety of water-dependent and supportive light and medium industrial uses, such as fish processing and unloading, ice plants, marine repair and manufacturing industries, marine fuel services and other marine light industrial uses.

This designation generally applies to lands with existing marine infrastructure fronting the harbour.

Public Institutional

This designation includes community and institutional uses, such as schools, libraries, recreation areas, health facilities, supportive housing, policing and emergency services, municipal buildings and facilities (e.g. the sewage lagoon on Hyphocus Island) and religious institutions. This category also includes lands supporting public utilities such as electrical and data transmission networks.

Water Areas

Water Lots

This designation applies to all areas of current and anticipated foreshore leases as designated in Schedule A.

Uses are subject to future review but may include docks, moorage of fishing vessels, loading/unloading of marine vessels, fish processing and support industry, tourist and recreation facilities including marinas and boat launches, marine residential, environmental protection, utilities and log storage.

Small Craft Harbour

These foreshore leases are held by the Department of Fisheries and Oceans and are managed by the District. A range of activities are permitted, including private boat moorage and other recreational pursuits, commercial fishing and guiding enterprises.

Marine Conservation

This designation applies to marine areas intended for conservation and transient recreational uses only; expansion of foreshore tenures and long-term vessel moorage are not supported within the Marine Conservation areas.

Village Square and Commercial Core

Village Square

The Ucluelet Village Square area is the heart of the community and Ucluelet's main gathering and shopping destination. It is a compact area comprised of those lands within an approximate five-minute walk (500 metre radius) of Main Street and Peninsula Road.

The Village Square area is oriented toward the waterfront acknowledging the critical role the harbour continues to play in the community's identity and prosperity. Access and views to the water are a community priority.

As the main commercial and mixed-use area of Ucluelet, the Village Square area is a welcoming place for community members and visitors alike.

Other designations also located within the core area of Ucluelet include Institutional, Multi-Family Residential, Residential and Parks and Open Space.

The Village Square designation contains the broadest range of services and land uses in the District. This includes retail, professional offices, health care, administrative, financial, tourist accommodation and supporting uses, cultural and community services and residential.

Marine Industrial uses that require access to the harbour are also permitted in key locations, including the UHS fish plant.

Service commercial uses (e.g. gas stations and other similar uses oriented toward the automobile) are located outside of the Village Square in order to maintain its strong pedestrian focus.

The Village Square provides for multi-family residential options in and around the core. This housing is located in mixed-use buildings and expands the community's affordable housing choices.

The Village Square has the community's highest densities and building forms, yet is designed to respect views and existing character. It is appealing and safe for pedestrians of all ages.

The architectural style and urban design of the Village Square reflects Ucluelet's unique history and coastal context. High quality urban design enhances the public realm and the pedestrian environment. Village Square uses are designed to transition sensitively to adjoining areas.



Village Square Policies:

Policy 3.55 The area bounded by the Harbour, Bay Street, Larch Road and Otter Street is to be designated as the Village Square. This area is also designated as the Village Square Development Permit Area for form and character (see Schedule ‘F’ for form and character DP mapping and Section 6 Implementation for details of the DP designation, applicability and guidelines.)

Policy 3.56 New retail, service and office development shall be concentrated in the Village Square designation to maximise pedestrian access for employees and customers and maintain the vitality of the village core.

Policy 3.57 Tourist accommodation (e.g. boutique hotels) and supporting uses are encouraged (e.g. eating and drinking establishments) to locate in the Village Square designation.

Policy 3.58 The District of Ucluelet continues to recognise the importance of the harbour to the District’s economy by designating employment uses that require access to the water (e.g. fish plant, boat repair) to locate within the Village Square area. Such uses shall be sensitively integrated into the community.

Policy 3.59 Encourage residential growth within the Village Square designation in the form of apartments and residential over commercial to provide for greater housing diversity and affordability.

Policy 3.60 Properties fronting Main Street must be mixed-use, with residential above commercial uses, or standalone commercial; stand-alone multi-family may be permitted within other areas of the Village Square designation. Arrange vehicular

access in a way that gives priority to pedestrian and cyclist comfort and safety.

Policy 3.61 Cultural and institutional uses are permitted within and adjacent to the Village Square designation, to support the mixed-use, cultural heart of the community. This is the preferred location for a District Museum. The acquisition of key properties by the District, or other public agency, may be required to establish more cultural and heritage uses in the Village Square.

Policy 3.62 The District encourages Canada Post to maintain the community post office within the Village Square area.

Policy 3.63 Emphasize the Village Square as the focal point for commercial and socio-economic activity in Ucluelet.

Policy 3.64 Main Street Dock is a key public gathering place in the community. It provides public access to the waterfront that is safe and accessible.

Main Street Dock may be framed by buildings and contain uses that fit within the mixed-use vision of the Village Square (e.g. cultural, recreation, commercial) and provide interest and variety to the area.

Policy 3.65 Enhance and improve public access to the water by encouraging access or viewpoints within all new developments that are adjacent to the water, including those adjacent to water lots.

Policy 3.66 Enhance and improve the network of public open spaces and trails that connect and cross the Village Square. Specific network improvements and elements include:

- enhance existing parks including Municipal Hall Park (e.g. reducing pavement) and Waterfront Park

- retain outdoor open space along Peninsula Road (e.g. existing patio northeast of the intersection of Main Street and Peninsula Road) in order to provide overlook and views to the Harbour
- explore creation or acquisition of new public open space opportunities where feasible (e.g. including the informal green space along Cedar Road on the existing fish plant site)
- require and formalise mid-block pedestrian connections in large block areas (e.g. north side of Peninsula Road, between Bay and Main Streets)
- develop a walking tour that connects the Village Square to the Inner Boat Basin, Imperial Lane and other parts of town, to create a continuous pedestrian link with the Safe Harbour Trail (see Schedule 'C')
- encourage the provision of cycling end-of trip facilities, such as bike parking
- explore options for a connection between Lyche and Cedar Roads. This connection is desirable, and the location can be flexible to accommodate existing uses and future redevelopment of the parcel.

Policy 3.67 Support the operating fish plant and associated industry; consider opportunities such as guided tours through the fish plants, a museum to showcase the industry and sports fishing opportunities;

Policy 3.68 Village Square Pedestrian Walkway Improvements – work to improve the following sidewalk and pathway segments in the following prioritised list:

- stair / ramp at corner of Main Street and Helen Road
- pedestrian walkway on Fraser Lane
- reconstruct municipal hall parking entrance and tot lot

- pedestrian walkway on Helen Road: Main to Matterson
- pedestrian walkway on north side of Peninsula Road: Main to Bay
- pedestrian walkway on Cedar Road: Main to Bay

Commercial

Ucluelet's business community provides a range of commercial facilities and services for the convenience of residents and visitors.

Commercial uses strengthen the municipal tax base, provide employment opportunities and accommodate the twin pillars of Ucluelet's economy; fishing and tourism.

Commercial land uses are also recognised for their contribution to a complete community through the provision of services and shopping close to home.

The broadest mix of commercial uses (including offices and retail stores) is permitted in the Village Square. As the community's main gathering place and with the highest residential densities, the Village Square is the main working and shopping destination in Ucluelet.

Commercial uses are also permitted in other parts of the community. Automobile-oriented uses (e.g. service stations and building supply establishments) are permitted primarily along Peninsula Road in the Service Commercial designation.

Commercial uses oriented toward tourist accommodation are located in Tourist Commercial designations. This hierarchy of commercial designations supports a compact and vibrant Village Square, while accommodating other needed services in the community.

General Commercial Policies:

Policy 3.69 Support a hierarchy of commercial uses that supports the Village Square as the location for most commercial and retail uses, while meeting the full range of residents' and visitors' service and shopping needs.

Policy 3.70 Continue to support the work of the Ucluelet Economic Development Corporation, the Barkley Community Forest, the Ucluelet Chamber of Commerce and Tourism Ucluelet, and the formation of partnerships or joint ventures to diversify the local economy and to generate new sources of sustainable development and employment.


Policy 3.71 Promote and support locally owned small businesses, including those oriented to arts and artisans, home occupation uses, and - where appropriate - bed and breakfasts, vacation rentals and guest houses.

Policy 3.72 Review permitted uses in all commercial zones, including the merits of allowing permanent residential uses in the Tourist Commercial (CS-5) zone in the vicinity of the Village Square and residential units above service commercial uses (CS-2 zone).

Policy 3.73 Connect commercial areas to other parts of the District through multi-use pathways, sidewalks, trails and other transportation routes. Show commercial areas on the proposed walking trail tour that connects the Village Square to the Inner Boat Basin, Imperial Lane and other parts of the District.

Policy 3.74 Support climate action strategies by:

- locating commercial uses within proximity of Peninsula Road, the District’s primary corridor for development. This will promote the early introduction of local transit-service and higher transit frequencies than is possible with lower density development
- situating commercial areas within walking distance of potential future transit routes
- supporting home-based businesses that have minimal impact on neighbouring land uses
- encouraging environment-friendly commercial development, building energy and efficiency upgrades
- encouraging development in a manner that promotes energy efficiency. This may include orienting buildings for maximum solar gain, maximizing glazing, requiring overhangs that protect from summer sun and rain but allow winter sunlight in, and providing landscaping that shades in summer and allows sunlight in during the winter



Service Commercial

Lands designated for Service Commercial uses are generally located along both sides of Peninsula Road between Forbes Road and Bay Street.

Service Commercial Policies:

Policy 3.75 Designate properties along Peninsula Road for service commercial uses to accommodate existing uses as well as future uses that require automobile-oriented access and visibility.

Policy 3.76 Accommodate automobile repair uses in the Service Commercial designation. Consider amending the Zoning Bylaw to permit automobile service uses (e.g. the repair and servicing of automobiles and recreational vehicles,) in the Service Commercial zones (i.e., not within the Village Square).

Policy 3.77 Recognise the strategic location and high visibility of Peninsula Road and implement high quality urban design for service commercial uses in the area, as set out in the Peninsula Road DP Area guidelines.

Policy 3.78 Work with the Ministry of Transportation and Infrastructure to enhance landscaping along Peninsula Road through the development process, allocation of capital funds and other mechanisms (e.g. DCCs and grants).

Policy 3.79 Work with property owners to increase the supply of visitor parking in commercial areas along Peninsula Road, while minimizing the number and width of curb cuts crossing the pedestrian and bike paths.

Tourist Commercial

Ucluelet's appeal as a tourist destination for all ages is based largely on the wide range of recreation opportunities available in the community. These include hiking the Wild Pacific Trail, sea kayaking, boating, fishing, surfing and cycling.

The town serves as a gateway to Pacific Rim National Park Reserve, Clayoquot Sound, Barkley Sound and the Broken Group Islands. Visitors are able to enjoy Ucluelet's small town charm, working harbour, parks, trails and other recreational and cultural amenities.

The Tourist Commercial designation focuses primarily on providing for visitors' accommodation, together with marinas and other supporting uses, creating areas distinct from residential neighbourhoods.

Tourist Commercial Policies:

Policy 3.80 Concentrate large scale tourist commercial developments within the following general areas:

- Reef Point Area
- Inner Boat Basin
- Former Forest Reserve Lands

Policy 3.81 Encourage accommodation types that may not be provided for in other areas in order to enhance visitor options and strategically manage supply (e.g. boutique hotels are encouraged in the Village Square designation, while vacation rentals, hotel/spas are permitted in the Tourist Commercial designation.).

Policy 3.82 Allow limited and accessory commercial uses (e.g. kayak rental) within the Tourist Commercial designation in order to support a wider range of commercial uses within a compact

and complete Village Square. Limited restaurant uses are appropriate in the Inner Boat Basin area. Visitors are encouraged to access offices and retail uses in the Village Square. Transportation options to the Village Square will include pedestrian and cycling infrastructure.

Policy 3.83 Encourage the redevelopment of properties fronting onto Ucluelet Inlet ensuring:

- the provision of public access to the waterfront
- a continuous waterfront walkway connecting the Inner Boat Basin to the Village Square
- high quality architectural design reflecting the fishing village heritage of Ucluelet
- the identification, protection and enhancement of view corridors
- the inclusion of natural landscaping

Policy 3.84 Encourage development forms that maximise tree retention for undeveloped sites.

Industrial

Ucluelet has developed as a working community, supported by a strong fishing industry. Fishing and other industrial activities needing access to the waterfront continue to be important directions for the future. While forestry perhaps played a more prominent role in the past, its contribution to the local economy is ongoing and anticipated to grow with the potential for wood-based value-added enterprises.

Industrial land use, both water and land-based, provide a solid foundation for the community's economic livelihood. Industrial land use enhances the economic viability of Ucluelet through the diversification of the local economy and the provision of employment opportunities. Industrial land provides space for the supply, storage, distribution and repair functions which support other "front line" enterprises.

Local industrial land can also support the District's policies and actions to reduce greenhouse gas (GHG) emissions and respond to climate change. This is achieved through the promotion of innovative and clean industrial uses that are appropriately located and designed to maximise energy efficiency. Securing an adequate supply of local industrial land also reduces travel to access service and supply industries.

The Industrial Designation encompasses two main areas – lands at Seaplane Base Road and lands along Forbes Road. These two areas are expected to meet the industrial land needs of the District for the medium to long term. Uses within the industrial designation are designed to provide a neighbourly transition to adjoining non-industrial areas.



Industrial Policies:

Policy 3.85 Support the protection of the District's industrial land base as a vital community and economic asset that can be used to create significant local employment, property taxes and other benefits to Ucluelet.

Policy 3.86 Encourage industrial uses that will achieve higher employment and land use densities.

Policy 3.87 Guide industrial development off Peninsula Road and into the Forbes Road and Seaplane Base Road areas.

Policy 3.88 Industrial land uses must be compatible with adjoining land uses (e.g. industrial / tourist commercial / residential); use the rezoning process (e.g. siting, layout) to minimise conflicts.

Policy 3.89 Give priority to industrial uses at the Seaplane Base Road area that require water access in areas with sufficient navigational depth (e.g. north side in proximity of existing water lots).

Policy 3.90 Protect and enhance the sensitive ecosystem associated with the waters on the west side of the Seaplane Base road industrial area by maintaining a naturalised shoreline.

Given the site's unique water access, proximity to industrial and tourist commercial areas, a comprehensive plan of development will be required at the time of redevelopment. Public access to the water will be provided in a manner that is commensurate with the permitted land uses.

Policy 3.91 Create an employment-intensive area in the Forbes Road industrial area, while acknowledging the existing mixed-use nature of the area. Review the range of uses permitted in the

CD-1 ("Eco-Industrial Park") Zone. Residential uses (e.g., employee housing) should only be considered on upper storeys above appropriate light industrial space. Explore the inclusion of live/work light industrial uses within this area.

Policy 3.92 Continue to recognise the importance of the harbour to the Ucluelet's economy by allowing industrial uses that require access to the water to locate within other appropriate designations (e.g. Village Square, Water Lot and the Small Craft Harbour).

Policy 3.93 Support the creation of more detailed plan for Ucluelet's Harbour, focusing on lands in the vicinity of the Village Square, existing water lots, and appropriate locations for water-based industrial uses.

Policy 3.94 Enhance and improve public access to the water in industrial areas while recognising that the safety and operational needs of industrial businesses are not to be compromised.

Policy 3.95 Support the fish plant and supporting industry located within the Village Square designation.

Policy 3.96 Support the long-term presence of the ice plants and marine service industries located on Eber Road. Recognising the surrounding residential neighbourhood context, continue to mitigate conflicts in this area.

Policy 3.97 Support the expansion of the District's industrial land base, where appropriate, in a manner that is sensitive to adjoining land uses and helps to achieve other District objectives.

Policy 3.98 Work in partnership with the Ucluelet Economic Development Corporation (UEDC), the Barkley Community Forest and the Ucluelet Chamber of Commerce to form partnerships or joint ventures to diversify the local economy and to generate new sources of sustainable development and employment.

Policy 3.99 Continue to support the Village Square as the location for most commercial and retail uses. Review accessory retail and office use provisions in industrial zones.

Policy 3.100 Connect industrial areas to other parts of the District through multi-use pathways, sidewalks, trails and other transportation routes. Show industrial areas on the proposed walking trail tour that connects the Village Square to the Inner Boat Basin, Imperial Lane and other parts of town.

Policy 3.101 Encourage the provision of cycling end-of trip facilities, such as bike parking, in industrial areas.

Policy 3.102 Provide a safe pedestrian environment to and from industrial areas and support ability of employees to walk to work while avoiding conflicts from trucks and vehicles, for instance, by providing separated sidewalks.

Policy 3.103 Minimise detrimental effects of industrial development on the natural environment and surrounding areas. Encourage water conservation, re-use of building materials and waste products, reduced energy consumption, alternate energy sources and high air quality and water treatment standards.

Policy 3.104 Strive for a high quality of site and building design in industrial areas. This may include extensive landscaping and visual buffers between industrial and non-industrial uses. Explore

the designation of properties fronting Forbes Road as a development permit area to improve the streetscape over time.

Policy 3.105 Support climate action strategies by providing infrastructure to support electric vehicle charging and encouraging the reduction of vehicle trips.

Policy 3.106 Encourage the provision of employee amenities within industrial developments that support a healthy working environment. This may include accessory retail uses (e.g. restaurants, cafes, pharmacy), places to sit, rest or eat, exercise facilities and connections to multi-use pathways, sidewalks or trails.

Policy 3.107 Accommodate automobile repair uses in the industrial designation; consider amending the Zoning Bylaw to permit automobile service uses (e.g. the repair and servicing of automobiles and recreational vehicles,) in the light industrial zones.

Policy 3.108 There are no significant gravel deposits within the boundaries of the District of Ucluelet, and no foreseen quarry or gravel extraction operations. Significant gravel resources are available within the region, however, including in the adjacent Area C of the ACRD.

Institutional

Community and institutional uses in Ucluelet include schools, libraries, recreation areas, health facilities, policing and emergency services, municipal buildings, public utilities and religious institutions.

These places meet many needs: educational, health, spiritual, and safety. They contribute to the wellbeing of the community and to a sense of permanence and stability.

The heart of Ucluelet’s civic life is located within the Village Square. This area contains the District Hall and Waterfront Park, George Fraser Memorial Park and the Main Street Dock.

A second cluster of institutional uses is located approximately 1.5 kilometres away along Matterson Drive. This cluster includes Ucluelet Elementary and Senior Secondary Schools, the BMX Bike Track and school playgrounds, the Ucluelet Community Centre, including a branch of the Vancouver Island Regional Library and the adjoining skateboard park and basketball court.

The District recognises that providing cultural and recreation facilities within close proximity to each other is essential to creating a complete community and cultivating a dynamic relationship between the different facilities.

Connections between the two institutional nodes are facilitated by transportation and infrastructure improvements along Main Street, Peninsula Road and Matterson Drive. Walking and cycling between the two areas is encouraged.

Other institutional uses with the community include:

- Recreation Hall on Seaplane Base Road
- Sewage treatment facility on Hyphocus Island
- Forest Glen Seniors Housing (St. Jacques Boulevard)
- Ucluelet Volunteer Fire Brigade;
- Food Bank on the Edge
- Canada Post community post office
- Army Navy & Air Force Club (Peninsula Road)
- RCMP detachment
- Telus and Hydro facilities
- Water and waste water facilities (reservoirs, pump stations)
- School District 70 (Pacific Rim) facilities

At the time of writing, the Ucluelet Elementary School is receiving significant seismic upgrades and renovations - including new day care facilities - and a new Ucluelet Secondary School is under construction. The school is designed to accommodate future expansion if necessary. These new and upgraded facilities will serve the needs of the west coast for the foreseeable future.



Institutional Policies

Policy 3.109 Support improvements to the Village Square that increase its attractiveness and enhance its accessibility, usefulness, and security as a venue for public uses and events.

Improvements may include signage, planting of trees, provision of street furniture, adding pedestrian and building lighting, public art, and other aesthetic and functional items that make the Village Square more desirable to pedestrians.

Policy 3.110 Facilitate improvements, which include sidewalks and multi-use pathways to Main Street, Peninsula Road and Matterson Drive to encourage walking and cycling between key community public spaces.

Policy 3.111 Maintain a close, collaborative relationship with School District 70 to maximise the use of school facilities and services for the benefit of the community and to facilitate current and anticipated school needs.

Policy 3.112 Encourage any future rebuilding of the schools to be oriented toward Matterson Drive to emphasize the importance of this intersection, the proximity to the Village Square and the connecting function that Matterson Drive plays (e.g. connecting Village Square to key community locations (community centre, Big Beach).

Policy 3.113 Recognise and support the role of schools as neighbourhood focal points and social centres.

Policy 3.114 Encourage Canada Post to maintain a location for the community post office within the Village Square area.

Policy 3.115 a number of federally-owned employee housing lots are now designated *Institutional* on the Schedule A Long-Range

Land Use Plan. Create a new institutional Community Residential zoning designation for these properties, clarifying the community expectation for their future conversion to a possible variety of community care, shelter, supportive and/or affordable housing uses.

Marine

Small Craft Harbour/ Marine

The jurisdictional boundary for the District of Ucluelet extends approximately 200 metres (ten surveyor's chains, or 660 feet) into the Pacific Ocean surrounding the Ucluth peninsula, as shown on Schedule A. It is the intent of the District to regulate uses contained within the water areas to the full extent of its jurisdiction.

The Harbour (Ucluelet Inlet) has historically and continues to play an important role in the life and well being of residents in the District.

Currently a range of activities occur, such as fishing (commercial and sport), private boat moorage, guides and outfitters and other recreational pursuits, including launching points for excursions on the water along the West Coast, particularly the Broken Group of Islands.

A number of leases of provincial Crown foreshore have been created over the years. To date, the development of these water lots has not been regulated by the municipality through tools such as Development Permit designations.

The calm waters in this natural inlet have provided refuge for mariners for a long period of time.

The harbour has potential to maintain and promote what makes Ucluelet a great place – a place that services the fishing and sport fishing industries, the tourist industry, inspires artists and photographers and supports daily recreational enjoyment by many within the community.

The harbour is an asset worth protecting for the future economic prosperity and livability in the District.



The water areas of Ucluelet are generally designated as either:

- Small Craft Harbour (three public water lots)
- Water Lot (primarily privately-held foreshore leases)
- Marine Conservation (remaining water areas not in registered water lots)

In addition to these three designations, several water lots are designated in conjunction with the adjacent land-based designation (e.g. Village Square or Residential).

Each registered water lot is inextricably linked to various adjacent land uses; hence the relationship between land and water requires careful consideration, which could include parking needs, water and sewer servicing and visual impacts.

Following the guiding principles of this OCP, the District has designated environmentally sensitive areas and shoreline habitat as environmental Development Permit areas. See Schedule E for DP area mapping and Part 6 [Implementation](#) for DP guidelines.

General Policies:

Policy 3.116 Adopt new zoning designations for water areas to define permitted uses, servicing and parking requirements, etc.

Policy 3.117 Prohibit the following uses in the Water Lot, Small Craft Harbour and Marine Conservation designations:

- Commercial aquaculture
- Boat, vessel or aircraft storage
- Landfills

Policy 3.118 Identify environmentally sensitive areas and protect marine ecosystems by establishing marine shoreline Development Permit areas: see Development Permit Area - Schedule E.

Policy 3.119 Support marine ecology and marine education facilities within the Harbour.

Policy 3.120 Consider enhancing public access to the District-leased water lot at the foot of Alder Street, including facilities for launching canoes and kayaks.

Policy 3.121 Support transient boat moorage provided adequate sanitation facilities are located nearby.

Policy 3.122 Require all water lot uses to properly treat and dispose sanitary sewer waste and connect into the District's sewer collection system and access District potable water.

Policy 3.123 Develop guidelines for marina and marine-based commercial DP areas, including requirements for publicly-accessible vessel sewage pump-out facilities in all marina operations.

Policy 3.124 Explore new means of generating revenue to fund Harbour infrastructure.

Small Craft Harbours

The Small Craft Harbour is owned by the Department of Fisheries and Oceans, and it is managed by the District. The Small Craft Harbour manages three water lots. These are:

- Lot 2084, known as the inner harbour
- Lot 1977, known as the outer harbour
- Lot 1877, known as 52 steps

Small Craft Harbour Policies:

Policy 3.125 Ensure the continued viability of the Small Craft Harbour in Ucluelet through sound management practices;

Policy 3.126 Consider changes to the size and configuration of the Small Craft Harbour; giving priority to water lots near existing and proposed industrial areas (e.g. Lot 610 near foot of Seaplane Base Road);

Policy 3.127 Encourage water-based industrial uses to locate in the vicinity of Seaplane Base Road.

Water Lot Policies:

Policy 3.128 A comprehensive review of all existing water lots and the appropriate location of potential marine uses will be carried out by the District. Possible uses include:

- docks and moorage of fishing vessels
- loading and unloading of marine vessels
- fish processing and support industry
- tourist and recreation facilities, including marinas and boat launches
- float homes
- live-aboards and houseboats

- pier residential housing
- environmental protection
- passive recreation and opportunities to view and experience the harbour from key locations on land
- utilities
- log storage

Policy 3.129 The Main Street Dock (Lot 1689), the Whiskey Dock, is considered appropriate for specific marine uses, such as net mending, specialty catch off-loading, Francis Barkley passengers and ferrying, fish markets, and arts, entertainment and tourist functions.



Generally vessel off-loading and other heavy industrial uses are not encouraged at Main Street Dock. Other existing public and private wharfs within the harbour may be more suitable for such activities.



Marine Conservation

All water areas located between the shoreline and the District boundaries, excluding areas designated as water lots, are designated as “Marine Conservation”.

Marine Conservation Policies:

Policy 3.130 Invite regional partners to participate in developing a comprehensive “Healthy Inlet / Safe Harbour” management plan for the Ucluelet Inlet, including:

- habitat sensitivity, protection and enhancement;
- co-ordinated approach to cleanup and avoiding future contamination (sewage, plastics, derelict vessels, etc.);
- coordinated policy for liveaboard moorage and sewage disposal;
- overview of type, amount and location of landing and moorage facilities.

Residential

The Official Community Plan provides a framework to meet the diverse housing needs of residents in Ucluelet.

Residential land use is permitted in the Village Square, Multi-Family and Residential designations. Each land use designation varies in the range and density of permitted housing types.

Generally, the highest density uses (apartments and residential units above retail stores) are found in the Village Square, with medium density forms (townhouses) on the edge of the core area and single family uses located beyond a 400-metre walk of the Village Square.

The 2016 Census counted a resident population of 1,717 people in Ucluelet, and a total of 735 occupied private dwellings. This represents 1.36% annual population growth, or 23 new residents per year, over the past decade; this could be considered strong, positive growth. Over the same period, visitor growth and non-resident home ownership has also expanded considerably.

The advent of on-line advertising and bookings for short-term vacation rentals is depleting the supply of rental housing available to long-term residents in Ucluelet (and many other communities in BC). This is having a negative effect on both business viability and community well-being.

Over the past few years the District has actively monitored and enforced its bylaws on short-term vacation rentals. At the time of writing, approximately 300 vacation rental units are active in the municipality, many in existing residential neighbourhoods. A number of long-term rental units – including secondary suites –

have been converted to short-term rentals, displacing this supply of vital housing stock.

Affordable Housing is defined as:

housing costing 30% or less of annual household income suitable for households of low and moderate income, equal to 80% or less than the median household income in the District of Ucluelet, as reported by Statistics Canada and as defined by Canada Mortgage Housing Corporation, CMHC.

Affordable Housing

Ucluelet attracts a large number of visitors yearly given its spectacular scenery and opportunities for recreation, including hiking, cycling, whale watching, kayaking, winter storm watching, surfing and fishing. As a popular tourist destination, the District strives to ensure that adequate housing is available for residents, visitors, and seasonal employees alike.

Ucluelet’s challenges with a lack of affordable housing began to escalate in 2001 as tourism activity increased. The affordable housing issue in Ucluelet also has ramifications on other growing industries and the changing needs of the community.

Other industries are growing in Ucluelet and struggle to house a local work force. Youth looking to leave home are forced to leave the community because of escalating housing costs. Seniors

looking to downsize their accommodation needs are faced with a shortage of housing supply and increased prices.

Ucluelet also houses many residents who work in the neighbouring tourism destination of Tofino. This puts added strain on the existing supply of affordable housing.

Approximately 9% of Ucluelet residents identify as Indigenous (2016 census). This includes both homeowners and renters. There are a handful of housing units owned by the Yuułuʔiłʔatḥ Government in town, as well as homes owned and operated by non-profit housing providers.

A combination of strategies that includes smaller lots, secondary suites, detached accessory dwelling units (e.g. cottages), seasonal employee housing, inclusionary zoning, and residential mixed-use development can positively contribute to the broadening of housing choices and affordability within the District of Ucluelet, as well as providing for rental housing and a greater variety of options for seniors.

In April of 2018, the provincial government introduced two new pieces of legislation affecting how local governments address housing issues.

Part 14 Division 22 of the *Local Government Act* now requires local governments to commission a housing needs assessment, and update the report every 5 years. It is expected that a completed assessment report will be a pre-requisite to provincial grant funding for affordable housing projects.

Section 481.1 of the *Local Government Act* now enables local governments to designate properties in their zoning bylaws exclusively for rental housing.

In response to the current housing situation, to better understand the dynamics of the housing market and supply in Ucluelet, and to enable the municipality to be proactive on balancing the community housing needs as new development occurs, the District has adopted the following short-term housing action plan.

Policy 3.131 Short-term Housing Action Plan:

- A. continue the program to actively monitor and enforce short-term rentals
- B. commission a community Housing Needs Assessment report
- C. identify and explore the feasibility of creating temporary seasonal employee housing on at least one municipally-owned property
- D. look for opportunities to update inclusionary zoning and density bonusing, particularly on lands previously designated as Comprehensive Development under a Master Development Agreement, to ensure a mix of affordable housing types are delivered with each phase of new development in the community
- E. amend the zoning bylaw to ensure that the first rental unit on single-family residential lots is for long-term tenancy, with any additional short-term rental uses to depend on the continued existence of the long-term rental
- F. amend the zoning bylaw to remove standalone short-term rental of single-family homes from the VR-2 zoning designation (completed 2019)
- G. explore zoning opportunities for infill of compact, more affordable units in existing and new neighbourhoods (e.g., small lots, rental cottages, etc.)
- H. a number of federally-owned employee housing lots are now designated *Institutional* on the Schedule A Long-Range Land Use Plan; create a new institutional Community Residential zoning designation for these properties, clarifying the community expectation for their continued use as employee housing or future conversion to a possible variety of

community care, shelter, supportive and/or affordable housing uses;

- I. explore the use of the new rental zoning powers proposed in Bill 23
- J. explore the use of Development Cost Charges for affordable housing
- K. develop a municipal Affordable Housing Strategy – identifying the best focus of municipal resources when addressing housing issues
- L. develop a District land and development strategy and explore the options for an ongoing affordable housing program

It is expected that these actions will be revisited following completion of a community Housing Needs Assessment in 2021, which may result in amendment of this OCP.



Affordable Housing Policies:

Policy 3.132 Increase the number of affordable housing units in Ucluelet by encouraging mixed land uses in the Village Square,

seniors’ housing, small-lot single family housing, detached accessory dwelling units (cottages) and secondary suites.

Policy 3.133 Support development of multi-family housing above retail in the Village Square to encourage a mixed-use core in the District.

Policy 3.134 Ensure larger developments are required to provide affordable housing as a portion of each development phase. Completion of the Land Use Demand Study (underway) and Housing Needs Assessment (2021) should provide guidance for the District to adopt targets for percentages of affordable housing in new developments.

Policy 3.135 Permit secondary suites in single-family dwellings with sufficient off-street parking.

Policy 3.136 Encourage the retention and development of mobile/manufactured home parks with high quality site design, screening and landscaping.

Policy 3.137 Encourage alternative housing options, including small lot subdivisions.

Policy 3.138 Zone land using low to moderate densities and use density bonusing to secure affordable housing in any larger development.

Policy 3.139 Continue using inclusionary zoning regulations that require affordable housing in new multi-family developments.

Policy 3.140 Encourage land use and building design which results in liveable but smaller, more affordable housing units.

Policy 3.141 Continue to encourage developers to provide 15% to 20% staff housing for employees needed to staff new developments in tourist commercial developments.

Policy 3.142 Encourage private, non-profit and co-operatively run housing units.

Policy 3.143 Rezoning applications involving more than five dwelling units shall provide a statement describing the affordable housing components achieved by the proposal.

Policy 3.144 The District does not support strata conversion of previously-occupied rental housing units.

Policy 3.145 Include Indigenous housing needs in the development of a community Affordable Housing Needs Assessment.

Policy 3.146 Work with regional First Nations and housing providers to identify where opportunities may exist to support and/or partner on meeting all community housing needs.

Residential – Multi Family

Smaller units in higher density, multi family areas are an important component of the District’s affordable housing strategy.

Residential uses within and in close proximity to the Village Square help create a more vibrant and compact community where residents can walk to services and amenities.

Multi Family Residential Policies:

Policy 3.147 Encourage the development of multi-family residential units within an approximate five-minute walk of the Village Square;

Policy 3.148 Encourage residential development above or below the first floor in the Village Square and the Service Commercial Area;

Policy 3.149 Encourage higher density forms of multi-family development to locate along main roads, including Matterson Drive and Peninsula Road;

Policy 3.150 Explore the use of coach houses and forms of low-to medium density multi-family housing that address both street frontages in the area south of Peninsula Road, between Yew Street and Matterson Drive; and

Policy 3.151 Encourage the provision of underground or concealed parking and affordable housing units.

Residential – Single Family

The majority of housing in the District of Ucluelet is made up of detached single-family homes.

Single Family Residential Policies

Policy 3.152 Continue to acknowledge the role that single-family housing plays in terms of appeal and lifestyle choice and encourage sensitive intensification (e.g. smaller lots, secondary suites, coach houses,) where appropriate.

Policy 3.153 Retain the area along Imperial Lane as single family and encourage the character of the existing buildings to be retained during any re-development.

Policy 3.154 Designate those portions of District Lots 281 and 282 that have been developed as low density, single family as Residential, while acknowledging that the existing zoning in these areas permits a broad range of land uses.

Policy 3.155 Designate Hyphocus Island as low density rural reserve, until such time as a comprehensive proposal is received identifying cluster residential development with significant tree retention, preservation of the island in its natural state and dedication of lands for public access, including the high ground and a perimeter waterfront trail.

This area is not intended for private marina or significant commercial, tourist commercial or resort development. Some light industrial uses may be introduced as a compatible transition between the sewage lagoons and residential areas.

Policy 3.156 Encourage residential development adjacent to Spring Cove (e.g. former BC Packers site) in ways that maximise preservation of environmental and cultural values, fit with the natural setting and extend public access through the Safe Harbour Trail along the shoreline.

Residential – General

General Housing Policies

Policy 3.157 Explore early adoption of more energy-efficient building construction through the step code and seek industry input into the impact of implementing such requirements in this remote market.

Policy 3.158 Explore density bonuses for incorporating energy efficiency in existing and new buildings.

Policy 3.159 Cluster residential units to preserve natural areas where possible.

Policy 3.160 Advocate for the development of adaptable housing standards within the BC Building Code and guidelines for future development.



Future Comprehensive Planning Areas

Areas on Schedule A indicated as Future Comprehensive Planning areas applies to larger lots with development potential, where it is anticipated that future rezoning, and potentially subdivision, will occur prior to development. The land uses shown within these areas indicate the general pattern of expected land use, but final location and density of uses will be subject to the future approval processes and detailed analysis of these sites.

Former Forest Reserve Lands

The Former Forest Reserve Lands cover the largest of Ucluelet's undeveloped areas. Special conditions of this vast landscape include some of the district's richest forested habitat and the potential for spectacular residential and commercial development. Covering roughly half of Ucluelet's entire land base, the area is largely unexploited by development. Objectives of this OCP include protecting the natural qualities that make this place so special. Protecting the most sensitive and rich features of this area, and following the built form, character and material guidelines outlined in this plan, the Former Forest Reserve Lands will successfully add to the character of Ucluelet.

The coastal environment within this area is characterized by rocky bluffs and headlands along the exposed western shoreline, while a gentler rocky coast - along with sensitive marine wetlands, predominates along the protected eastern shoreline of Ucluelet inlet. This rugged and wild coast, along with the extensive forest that carpets the rolling and often steep terrain contribute immeasurably to the character of the site. There is therefore a demonstrated need to ensure that development

within this area should be protected from hazardous conditions and makes adequate provision for fitting itself harmoniously into the existing natural environment while maintaining a balance between the need for such protection and development of this land. The area contains archaeological and cultural uses and resources which must be understood and considered with any development plan. Preserving as much of the natural shoreline condition as possible, as well as the forest and its underlying shrub layer is critical in maintaining these values. All development should extend the Wild Pacific Trail and Safe Harbour Trail, and the network of connecting corridors, that make their way through the area.



In addition to development being sensitive to significant natural features worthy of protection, this area is designated for a mix of uses which will require a high standard of design cohesion to reflect the natural heritage of the area.

Master Development Agreements were established to guide the development of the former forest reserve lands. Signed in 2005

and 2006, these agreements committed the owners to additional information requirements including native vegetation management plans, full environmental impact assessments and archaeological assessments. Development subsequently stalled and in the intervening years it has become clear that a different approach may be necessary to enable development of these sites while retaining the initial vision of promoting the natural attributes and culture of the community, attracting investment, tourism and employment opportunities while demonstrating responsible stewardship of the natural environment.

Land uses on the former forest reserve lands was anticipated to include:

- single family with a range of lot sizes
- multi-family residential and commercial resort condominiums
- vacation rentals and Guest House lots
- affordable housing
- hotel/spa, motel and staff housing units
- golf course/clubhouse and marina
- limited commercial facilities restricted to servicing the tourist sector
- parks and natural space
- Wild Pacific Trail

The golf course use is no longer considered a viable component of the plan but a mix of the other uses is indicated on Schedule A.

The Wild Pacific Trail is a crucial, integral component of the former forest reserve land areas. Amendments to each Master Development Agreement may be considered without amendment of the OCP provided the Wild Pacific Trail is not compromised.

The District may also reconsider the Master Development Agreement (MDA) approach and revert zoning to a low-density Rural designation without amendment of the OCP. Future development could then proceed on application for new zoning based on the policies in this section and OCP, and the land uses generally indicated on Schedule A.

Specific policies for the lands included within the Future Comprehensive Planning areas are noted below:

Policy 3.161 Future development proposals may be considered under phased development agreements per section 516 of the *Local Government Act*.

Policy 3.162 Clear-cutting tracts of land greater than 0.5 hectare is prohibited; habitat protection and tree retention is to guide and form the character of the development.

Policy 3.163 A 30-metre wide tree buffer with no development must be provided along both sides of the Pacific Rim Highway;

Policy 3.164 The layout of the proposed extension of Marine Drive which runs parallel to the Pacific Rim Highway must respond to the natural conditions and topography of the land. Adequate vegetative buffering along the frontage of the road should also be retained to provide an attractive entrance into the community. A tree preservation plan should be a major priority to preserve this spectacular natural environment.


Policy 3.165 Low-impact design principles should prevail. This may include limited areas of impermeability, open drainage, high retention and replacement of natural vegetation, ecological landscaping, slow traffic speeds and comfortable, auto-tolerant streets, pedestrian and cyclist connectivity, end-of-trip facilities (e.g. bike lockers, showers), site and lot grading which follows existing topography, environmental protection and enhancement, wide natural buffers and retention of significant natural features.

Policy 3.166 The Wild Pacific Trail is predominantly a waterfront, natural pathway. Future subdivision must include sufficient highway dedication to allow for the continuity of the trail and vegetated buffer.

The minimum width of the Wild Pacific Trail corridor should be 10 metres, with an average width of at least 15 metres.

Access to the Wild Pacific Trail should be provided at intervals not exceeding 400 metres. Small parking areas should be provided at trail heads.

Policy 3.167 Gates, guard houses, and other means of restricting public access are not permitted.



Policy 3.168 Additional parkland, open space, trails and affordable and staff housing are some of the features and amenities that may be secured through agreement, bylaw or other mechanisms.

General Future Comprehensive Planning Area Policies

Policy 3.169 Public access to the water in all areas is supported, encouraged and intended to be secured including through agreement and dedication.


Policy 3.170 The area on Seaplane Base Road, surrounding the Recreation Hall, is designated for Future Comprehensive Planning and identified as a potential Industrial expansion area. Industrial uses that need water access will be considered for this area.

Policy 3.171 The area on Minato Road north of Peninsula Road is designated for Future Comprehensive Planning. This area is envisioned as a residential community with potential for guest accommodation, with significant tree retention. The shoreline and marine wetlands of Olsen Bay is recognised as having important ecosystem values. No development should approach within 30m of the high water mark of Olsen Bay. A greenbelt should be maintained along stream corridors and the shoreline.

Policy 3.172 All development proposals are to address and include measures that mitigate or manage the human-wildlife interface.

Policy 3.173 Developers are to retain an arborist to examine and assess the impact of development and any land clearing on tree/forest cover during subdivision development with the

intention to retain and protect as many healthy trees or pockets of forest cover as possible.



Policy 3.174 Hyphocus Island is currently zoned as Rural Reserve. The zoning of these lands should allow for limited residential development. This reflects the desired future use as primarily clustered residential pattern with substantial tree retention and significant public open space and institutional (i.e., sewage treatment) uses. This area is not intended for private marina or significant tourist commercial or resort development. Compatible light industrial uses may be considered adjacent to the sewage treatment plant. The community may consider re-designation on advancement of a comprehensive plan that addresses the policies and guidelines of this OCP. The high point of the island should be considered for its potential for emergency evacuation (e.g., in conjunction with a future park or open space at the summit of the island);

Policy 3.175 Francis Island is recognised as the symbolic entrance to the Harbour. It should not be developed, without intensive investigation of environmental, hazard and archaeological considerations. Access to the beach on the island and a trail around the edge of the Island for recreational purposes may be further explored.

The Island is zoned as Rural Reserve. Acknowledge the private ownership of Francis Island by permitting up to one single family residential dwelling, without secondary suite, B&B, vacation rental or tourist commercial uses.

Encourage and explore means of preservation, and maximum tree retention, with limited public access, including as an amenity for more intensive development of adjacent lands. Potential acquisition for designation as park land is also supported.

Policy 3.176 The area referred to as District Lot 281 has evolved into a premier location for tourist commercial development as

well as single and multi-family homes. Its prominent position next to Big Beach and its south-west orientation makes this a valuable and defining neighbourhood requiring attention in the form and character of developments. The spectacular landscape sloping gently to the ocean allows impressive vistas for visitors and home owners alike. A sensitive approach must be exercised to avoid over-cutting trees at the expense of the area's natural beauty, for enjoyment by all residents and visitors, and to protect the natural environment.

Policy 3.177 For areas of land higher than 20 to 30 metres above sea level, development, park dedication and public/open space should be coordinated with the District's Emergency Plan when considering the potential for public vistas, integrated with the multi-use pathway, trail and road network, as well as muster areas within a close walk of development areas.

Policy 3.178 All new or additional development, including campsites with no individual water supply or no individual sewage disposal facilities, must be connected to the municipal sanitary sewer system.

Part Four: Systems

Servicing and Infrastructure

The District maintains a network of municipal roads, sidewalks, water treatment and distribution, storm drainage, sewer collection and treatment infrastructure. These are monitored and maintained to meet a series of federal and provincial standards. The District plans, develops and maintains these municipal infrastructure systems to enhance the community's health, safety and overall quality of life, and to protect the local environment.

Objective 4A To protect community health and the environment by developing and maintaining efficient and highly-functioning water and sewer systems.

Objective 4B To ensure an orderly pattern of utility services and avoid premature or unnecessary public expenditures on municipal infrastructure.

Objective 4C To use water resources efficiently to ensure a safe and reliable supply over the long term.

Objective 4D To adapt municipal infrastructure systems to remain resilient to the impacts of a changing climate.

Objective 4E To reduce the use of fossil fuels and other resources in municipal operations through improved efficiency and conservation.

Objective 4F To adopt an environmentally sound, integrated stormwater management strategy.

Objective 4G To ensure that the costs of upgraded services are borne primarily by those who benefit.

Objective 4H To ensure that new development contributes toward the costs of infrastructure improvements.

Water Supply

The District of Ucluelet has two domestic water sources. The Lost Shoe Creek Aquifer supply currently consists of four wells which produce approximately 9,450 m³/day (at 90% capacity). Drier summer weather patterns potentially limit this supply, as the aquifer is drawn down to the level of the deepest well. Active water licenses also allow the District to draw up to 3,239 m³/day from Mercantile Creek; of this approximately 500 m³/day is allocated to the Ucluelet First Nations. Additional surface water cannot be taken from this source, to protect the Mercantile Creek fish habitat resource.

In the medium to long term an alternate source of water will be needed to support growth and industry within the District. Two approaches have been identified. The first would require an additional well at the Lost Shoe Creek Aquifer and/or a new well located at Mercantile Creek, expanding the current system capacity. The second approach would develop a new water supply from Kennedy Lake, identified as a source of sufficient volume to sustain the entire region. The feasibility, costs and treatment options have been analysed for the Kennedy Lake system. Ongoing discussions with regional partners will be key to determining the ultimate approach to providing a resilient, healthy source of domestic water to the community.

Water Storage

Water reservoirs are necessary to retain enough water volume and pressure for fire protection, peak hour water balancing and emergency storage purposes. The District operates two water storage reservoirs; one located along the Pacific Rim Highway

(1,400 m³ of storage) and a second reservoir located off Matterson Drive behind the schools (1,300 m³ of storage) for a total capacity of 2,700 m³.

There is a current shortfall in recommended storage volume requirements with the two existing reservoirs to meet fire flow standards, therefore the District should plan for constructing a new facility. A new reservoir could be partially funded through the Development Cost Charge bylaw.



Sanitary Sewer

The District's wastewater collection system consists of a network of gravity and forcemain sewers feeding into one of 15 municipal pump stations. All sewers are pumped through the Helen Road Pump Station before discharging to the District of Ucluelet's Wastewater Treatment facility located on Hyphocus Island.

The wastewater treatment facility is a 3-cell aerated lagoon. Each cell is lined with a high-density polyethylene membrane with a baffling curtain system which maximizes the retention time of the effluent water, allowing the system to provide a high degree of treatment. To expand lagoon capacity into the future, cell # 3 may be expanded and deepened, additional cells may be constructed if land is secured by the District, and a tertiary treatment plant may be constructed.

The District's lagoon system discharges into a marine outfall system. This outfall is located under Ucluelet Inlet to Alpha Passage near George Fraser Islands (1,480 metres in length) and accommodates the treated effluent from the District's lagoon. The outfall is sized to also handle untreated waste from up to three fish processing plants.

Pumping wastewater is expensive to maintain. However it is unavoidable, due to Ucluelet's topography. The District is pursuing strategies to reduce reliance on sewage pumping in the long term. This may include redirection and extension of specific collectors and forcemains. Additionally, the District should carefully evaluate the long-term financial operating costs before assuming responsibility for future infrastructure as a result of new development.

Heavier rainfall events in recent years have caused the maximum daily flows to exceed permit allowances approximately three to

four times a year. These extraordinary flows are attributable to high levels of inflow and infiltration (I & I), combined with more intense storm events. The District has an ongoing program to identify and address I&I incidents.

Stormwater Management

Situated in a coastal rainforest, Ucluelet is blessed with an abundance of rainfall (3,300 mm per year of precipitation). Stormwater collected in pipes and discharged directly to watercourses or the foreshore creates a potential for erosion and discharge of contaminants, which can be harmful to fish and the environment. The existing system in Ucluelet includes a mixture of pipes and open drainage ditches and swales. Several projects in Ucluelet have shown rainfall can be collected in gravel filled trenches and topsoil to dissipate stormwater run-off in a more natural way into the ground. The District will explore options to expand this approach, when updating municipal servicing standards. In addition, the District encourages developers to retain forest cover during subdivision development (i.e. only clear what is necessary to construct the infrastructure and roads) and retain pockets of forest land to the extent possible.

Solid Waste and Recycling

In 2007 the Alberni Clayoquot Regional District (ACRD) commissioned a Solid Waste Management Plan, which was endorsed by District Council. The plan's objectives are to:

Objective 4I Reduce the amount of waste requiring disposal.

Objective 4J Increase the level of recycling activity throughout the regional district.

Objective 4K Ensure that any residual waste is disposed of in a manner that protects the environment and social well-being.



In the West Coast Landfill catchment area, waste reduction targets are based on recycling rates, as the disposal rate may not be an accurate reflection of progress since it is highly affected by the annual success of the tourism industry. It is anticipated that the West Coast Landfill will be the central delivery area for recyclables collected on the west coast

Currently, there is no suitable local location to dispose of land-clearing debris and household organic waste. The District expects to continue to work with the Alberni Clayoquot Regional District on regional solutions to organic waste recycling.

The 2006 'Human-Bear Conflict Management Plan' guides consideration of development proposals and necessary actions

to reduce potential wildlife conflicts. The priority actions identified in this plan are to bear-proof garbage and food attractants and to set aside habitat and critical animal corridors as lands are developed within the District.

Servicing Policies

Policy 4.1 Require developers to pay for the full servicing costs associated with growth.

Policy 4.2 Commission, and update as necessary, infrastructure master plans for municipal water, sewer, roads, building facilities, parks, and integrated stormwater systems.

Policy 4.3 Initiate long-range financial planning to account for both the costs of replacing aging infrastructure and the expected expansion of utilities to serve a growing community.

Policy 4.4 Maintain a 5-year capital works plan for the construction and upgrading of municipal utilities, based on the infrastructure master plans and long-range financial plan.

Policy 4.5 Adopt updated Subdivision and Development Servicing Standards to require low-impact development standards, minimize long-term operational and maintenance costs, reduce the environmental impact of development, and provide the network of pedestrian, bicycle and vehicle facilities shown in this plan.

Policy 4.6 Plan for water conservation as a necessary part of future development in order to reduce peak demand requirements and meet funding criteria from Provincial and Federal governments.

Policy 4.7 Explore options for providing a second barrier water treatment system for surface water sources, as directed by the Ministry of Health, if continued use of the Mercantile Creek source is needed.

Policy 4.8 Plan for the construction of a third water reservoir, to meet future pressure and capacity needs.

Policy 4.9 Continue an active program to reduce inflow and infiltration into the sewage system.

Policy 4.10 Continue an active program for detecting leaks and unauthorized water use.

Policy 4.11 Continue the program to repair, upgrade and install SCADA on each municipal sewage pump station.

Policy 4.12 Maintain appropriate portable emergency generators to service key municipal infrastructure during power outages.

Policy 4.13 Investigate the feasibility of retrofitting existing piped systems, when replacing aging infrastructure, in favor of alternate practices for accommodating run-off.

Policy 4.14 Develop a program for reviewing the municipal systems and securing rights-of-way for all utility infrastructure where presently not secured.

Policy 4.15 Require oil and grease separators to be installed and maintained for all new or upgraded paved parking lots and service station properties.

Policy 4.16 Continue to explore the feasibility of the Kennedy Lake Regional Supply, and seek support from regional partners, as the long-term secure water source for the west coast.

Policy 4.17 Work with the Ministry of Environment to update the municipal sewage discharge permit to reflect the current level of waste water treatment.

Policy 4.18 Refer major development proposals to the Alberni Clayoquot Regional District for comments relating to solid waste and recycling.

Policy 4.19 Encourage community waste reduction and recycling.

Policy 4.20 Explore options for handling local land-clearing waste and household organic waste recycling with the ACRD.

Policy 4.21 To reduce energy and emissions associated with waste management, the District will consider enhancing programs to reduce waste, recycle and reuse waste where possible, and promote composting systems that reduce the amount of methane from organic waste.

Policy 4.22 Encourage the use of sustainable energy systems and utilities where improved energy efficiency and/or reduced GHG emissions will result.

Policy 4.23 The number of District-owned and operated sewer pump stations should be minimised.

Policy 4.24 Encourage the harvesting of waste heat from industrial, commercial or institutional sources, such as refrigeration equipment and sewer systems, where practical.

Policy 4.25 Utilize energy-efficient street lighting to reduce energy use.



Municipal Finance, Governance and Operations

A primary task of the municipal organization is to maintain the business functions which support the community's local government.

Taxation, utility billing, infrastructure financing, budgeting, contracting and seeking grants are all core functions of the District. Providing timely, accurate information and support enables good decision making by the elected Council.

Municipal staff are charged with ensuring the District functions meet legislated requirements and strive to adopt appropriate best practices to further Council's strategic directions for the community.

Clear communication with Ucluelet residents and other agencies on the ongoing operations, events and functions of the municipality ensures accountability and transparency in all of the District's practices.

Objective 4L To be a healthy, accountable, progressive organisation that is outstanding in the provision of service to the public.

Objective 4M Deliver excellent customer service.

Objective 4N Provide best value for money.

Objective 4O Provide right-sized government services and infrastructure which will be affordable to the community over the long term.

Objective 4P Strengthen relationships within the community and with neighbours.

Objective 4Q Provide streamlined services for residents, businesses and investors in the community.

Policy 4.26 Develop and institute a long-range financial planning approach which anticipates the costs of developing, operating, maintaining and replacing municipal infrastructure and assets over their serviceable lifespan.

Policy 4.27 Commission a long-range land use demand study to inform infrastructure decisions, development reviews and long-range budgeting efforts.

Policy 4.28 Assess municipal resources and strategize the appropriate approaches to most efficiently delivering the level of service expected by the community.



The District recognises that information is another piece of key infrastructure for the community. Land, building, demographic and business data are important information sources which can support community functions, economic development and the work of other agencies.

Policy 4.29 Continue to pursue corporate records management strategies to develop efficient and resilient information storage and retrieval systems.

Policy 4.30 Continue to review District methods of internal and external communication to provide transparency while maintaining an appropriately efficient allocation of resources and staff time.

Policy 4.31 Provide educational materials and opportunities for engaging citizens and expanding awareness, knowledge and participation in civic functions.

Economic Development

Ucluelet prides itself as being a working town. The economy has traditionally been based on the forest, fishing and mining industries up until the nineteen nineties.

Today Ucluelet and Tofino serve a trading population of roughly 4,000 in addition to an increasingly large number of tourists attracted by the area's pristine scenic beauty.

The District works with Tourism Ucluelet and the Chamber of Commerce to further promote the unique attributes of the town, while differentiating the visitor experience between the west coast communities of Tofino and Ucluelet.

Ucluelet continues to improve its image and appeal to visitors. This is achieved through promoting the community as a working harbour and drawing attention to the Wild Pacific Trail, the area's heritage and cultural values and access to the Broken Group Islands.

A new fiber-optic data network serving Ucluelet supports businesses and individuals who increasingly live locally but interact with a far-flung network of clients, customers and suppliers.

Strategic improvements to the public realm in the Village Square area is a priority for enhancing the safety, comfort and experience of both locals and visitors. These pathways and gathering places act as the backbone to the community and also support the further development of the Ucluelet economy.

The District of Ucluelet commissioned an Economic Development Strategy Update in 2017. The study identified strategic directions which are reflected in the following economic objectives.

It remains important that Ucluelet maintains a diversified economy, so that it does not concentrate solely on tourism, while retaining its traditional small-town character.

“As of the 2011 National Household Survey, the concentration of tourism-based jobs in the Ucluelet area was about 2.5 times the provincial average. These are a combination of jobs in accommodation services, food and beverage services, recreation, transportation, retail, and others.

This underlies the importance of tourism to the Ucluelet economy and is impressive considering that every community in the province has at least a small tourism industry.

But the real outlier in the Ucluelet economy is the fishing sector. Including fishing, aquaculture and fish processing, the concentration of employment in Ucluelet is 64 times the provincial average. Fishing jobs are naturally more concentrated because they are mostly limited to coastal communities, but this is still a remarkable result.

About 18% of all jobs with a fixed place of work in Ucluelet were in fishing, and this does not include all the various suppliers to the industry.”¹

Objective 4R Sustain a local economic development structure and tools.

Objective 4S Invest in Ucluelet’s human potential.

Objective 4T Enhance physical infrastructure for economic development.

Objective 4U Support and build on the twin pillars of the Ucluelet economy – harbor-related industries and tourism.

Objective 4V Pursue targeted economic development opportunities.



The updated Economic Development Strategy identifies the following strategic polices which the District is pursuing:

Policy 4.32 As part of an overall strategic review of the long-term demand for municipal resources, assess the level of staffing and/or financial commitment to economic development.

Policy 4.33 Continue to support a business and employment retention and expansion (UBERE) program.

Policy 4.34 Communicate Ucluelet’s attributes and opportunities for economic development.

Policy 4.35 Maintain a collaborative relationship on economic development projects with Yuuluᑭiᑭᑭᑭᑭᑭ and ‘tukwaaᑭᑭᑭᑭᑭ First Nations.

Policy 4.36 Continue to support the development of a range of housing options, including dedicated staff housing if the need arises.

Policy 4.37 Continue working to improve the municipal water system.

Policy 4.38 Continue to work with the Department of Fisheries and Oceans (DFO) and industry to maximise the effectiveness of the harbor for commercial fishing operations.

Policy 4.39 Support the expansion and diversification of tourism amenities and attractions.

Policy 4.40 Support ongoing community input into Economic Development.

Policy 4.41 Continue to support new and expanded post-secondary education and/or advanced research institutions.

Policy 4.42 Continue to support health service improvements in Ucluelet and the region.

Policy 4.43 Continue to support programs and events that enhance Ucluelet’s unique sense of place and high quality of life.

Policy 4.44 Explore alternative uses of the Coast Guard lands.

Policy 4.45 Ensure sufficient supply of industrial land is designated and, when appropriate, serviced for future use.

Policy 4.46 Support continued improvement to regional transportation infrastructure.

Policy 4.47 Support the continued operation and expansion of marine support services.

Policy 4.48 Support the commercial fishing, aquaculture, and processing sectors in the development of new and higher-value seafood products.

Policy 4.49 Target technology and energy-related entrepreneurs.

Policy 4.50 Support the expansion of forestry and wood products manufacturing.

Policy 4.51 Explore marketing synergies among tourism providers in the west coast region.

Policy 4.52 Support closer ties between local educational institutions and the business community.


Policy 4.53 Develop a business resource package, including referral service, to support entrepreneurs and small businesses.

Policy 4.54 Explore the potential to partner with other agencies to beautify the Highway 4 junction, including undergrounding or relocating power lines, coordinating (and minimizing) signage, and installing new landscaped medians befitting the coastal forest environment. Consider providing maintenance to median landscaping, should its installation be accepted by the Ministry of Transportation and Infrastructure.

Policy 4.55 A major draw and economic opportunity lies in the trails by which visitors experience the beauty of the Ucluth Peninsula. Approach funding for extension and upgrade to the Wild Pacific Trail and Safe Harbour Trail equally as an investment

in economic development as well as a recreational amenity for residents.

Policy 4.56 Capitalize on the growing recognition of Ucluelet as a prime destination for active recreational pursuits including surfing, kayaking, sport fishing, hiking and mountain biking.



Part Five: Schedules & Maps

SCHEDULE A: LONG-RANGE LAND USE PLAN

SCHEDULE B: TRANSPORTATION NETWORK

SCHEDULE C: PARKS & TRAILS NETWORK

SCHEDULE D: WATER & SEWER INFRASTRUCTURE

SCHEDULE E: DEVELOPMENT PERMIT AREAS – ENVIRONMENTAL PROTECTION

SCHEDULE F: DEVELOPMENT PERMIT AREAS – FORM & CHARACTER

SCHEDULE G: DEVELOPMENT PERMIT AREAS – STEEP SLOPES

MAP 1: REGIONAL CONTEXT

MAP 2: REGIONAL INFRASTRUCTURE

MAP 3: ARCHAEOLOGICAL POTENTIAL


MAP 4: COASTAL STORM – FLOOD CONSTRUCTION LEVELS

MAP 5: TSUNAMI FLOOD VULNERABILITY

MAP 6: TSUNAMI FLOOD PLANNING

MAP 7: CURRENT LAND USE

MAP 8: ENVIRONMENTAL BASE INFORMATION




DISTRICT OF UCLUELET

Official Community Plan

SCHEDULE 'A'
Long-Range Land Use Plan

SF - Single Family Residential
MF - Multi-Family Residential
MH - Manufactured Home Park
VS - Village Square Commercial
NC - Neighbourhood Commercial
SC - Service Commercial
TC - Tourist Commercial
IN - Industrial
PI - Institutional
P - Parks & Open Space
WL - Marine Tenure
Areas for Future Comprehensive Planning
District Boundary

Date: February 1, 2021

This map has been prepared for the use of the District of Ucluelet and may not be used, reproduced or relied upon by a third party unless an agreement by the District of Ucluelet. The information depicted is for general reference only. Accuracy cannot be guaranteed.

Map prepared by 




Official Community Plan


SCHEDULE 'B'
Transportation Network

- Existing Roads**
 - Arterial
 - Collector
- Future Roads**
 - Arterial
 - Collector
- Multi-Use Trails**
 - Existing
 - Future
- Bike Lanes**
 - Shared Lane (Car/Bike)
 - Dedicated Bike Lane
 - Future Shared Lane (Car/Bike)
 - Future Dedicated Bike Lane
- Crosswalks**
 - Existing Crosswalk
 - Proposed Crosswalk
- Parking**
 - Existing Parking
 - Proposed Parking

Date: December 18, 2020
This map has been prepared for the use of the District of Ucluelet and may not be used, reproduced or relied upon by a third party without the consent of the District of Ucluelet. The information depicted is for general reference only. Accuracy cannot be guaranteed.

Map prepared by cgis





Official Community Plan


**SCHEDULE 'C'
Parks & Trails Network**

- Sidewalk - 2 Sides
- - - Future Sidewalk - 2 Sides
- Sidewalk - 1 Side
- - - Future Sidewalk - 1 Side
- - - Wild Pacific Trail
- Future Wild Pacific Trail
- - - Safe Harbour Trail
- Future Safe Harbour Trail
- Harbour Walk
- - - Future Harbour Walk
- Pedestrian Connectors
- Key Active Transportation Generators
- Park / Open Space
- - - Future Park / Open Space
- View Point
- Future View Point
- Ⓟ Future Park Facility

Date: February 2, 2021

This map has been prepared for the use of the District of Ucluelet and may not be used, reproduced or relied upon by a third party without an agreement by the District of Ucluelet. The information depicted is for general reference only. Accuracy cannot be guaranteed.

Map prepared by **cgis**




Official Community Plan
SCHEDULE 'D'
Water & Sewer Infrastructure

- Water System**
- Watermain
 - Future Watermain
- Sanitary System**
- Sewer Gravity Main
 - Sewer Forcemain
 - Future Gravity Sewer
 - Pump Station
- Processing Plant System**
- Processing Plant Force Main

Date: December 17, 2020
This map has been prepared for the use of the District of Ucluelet and may not be used, reproduced or relied upon by a third party unless an agreement is made with the District of Ucluelet. The information depicted is for general reference only. Accuracy cannot be guaranteed.





DISTRICT OF UCLUELET

Official Community Plan

**SCHEDULE 'E'
Environmental Development Permits Areas**


- Terrestrial Development Permit Area**
 - Wetlands
 - Mature Forests
 - Sensitive Ecosystems
- 30m Marine Shoreline Development Permit Area**
 - Includes 30m on Intertidal area
- 30m Riparian Development Permit Area**

Marine Shoreline DPA is designated as 30m from either side of the natural boundary of the sea. Stream DPA is designated as 30m offset from stream feature. Refer to OCP text for development permit guidelines.

Date: February 17, 2021

The information reported is for general reference only and is based on available sources. The District of Ucluelet assumes no liability for the accuracy of base mapping information; ground truthing on individual properties should be undertaken by qualified professionals prior to development planning.


Prepared by **cgis**




DISTRICT OF UCLUELET

Official Community Plan

SCHEDULE 'F'
Development Permit Areas for Form and Character



■ DPA I - Village Square
■ DPA II - Peninsula Road
■ DPA III - Industrial
■ DPA IV - Multi-Family, Mixed Use, Commercial

NOTE: All lands within the boundaries of Ucluelet are also designated as a Development Permit Area for the regulation of form and character when being developed for any Multi-Family Residential, Mixed-Use and/or Commercial uses (DPA IV).

Date: February 1, 2021

This map has been prepared for the use of the District of Ucluelet and may not be used, reproduced or relied upon by a third party without the consent of the District of Ucluelet. The information depicted is for general reference only, accuracy cannot be guaranteed.

Map prepared by 




DISTRICT OF UCLUELET

Official Community Plan

SCHEDULE 'G'
Development Permit Areas
for Hazardous Conditions



 Steep Slopes (>30 degrees)


NOTE: For information on lands which may be subject to flooding please refer to Maps 4, 5 and 6.


Date: February 2, 2021

This map has been prepared for the use of the District of Ucluelet and may not be used, reproduced or relied upon by a third party except as agreed by the District of Ucluelet. The information depicted is for general reference only, accuracy cannot be guaranteed.

Map prepared by 







DISTRICT OF
UCLUELET

Official Community Plan

**Map 3
Archaeological &
Cultural Potential**

■ Areas of High Archaeological
and Cultural Potential

Areas of highest archaeological and cultural potential include the native forest, lands 150m inward from the natural boundary of the sea, and stands of trees which may contain old growth. Part of the District's heritage includes archaeological sites—the physical evidence of how and where people lived in the past. For 95% of the time people have lived in this area, no written records were made. Archaeological sites, or traditions and cultural practices connected to the rich history extending back more thousands of years. The South Peninsula is within 1000 years of the international coastline remains recorded archaeological sites are the potential to contain more. The Province protects these sites, whether known or concealed, through the Heritage Conservation Act. This protection applies to both private and Crown land and means that you must have a provincial heritage permits investigate, alter or develop within an archaeological site.

Archaeological sites/objects are not identified in this plan due to their sensitivity. However, areas shown here have significant potential to contain unknown archaeological sites that are protected under the Heritage Conservation Act. For more information contact the BC Archaeology Branch.

Date: February 2, 2021

The information depicted is for general reference only and is based on available sources. The District of Ucluelet assumes no liability for the accuracy of base mapping information. Ground truthing on individual properties should be undertaken by qualified professionals prior to development planning.

Map prepared by **cgis**

Notes to Users:

- This map was prepared to accompany the District of Ucluelet Coastal Flood Mapping Report (Ebbwater Consulting Inc. and Cascadia Coast Research Ltd., 2020) and is intended for the purposes set out in that report only. See the report for further details on the methodology, results, and limitations.
- Flood water levels were developed using a 0.5% AEP flood and 1.0 m freeboard. Flood Levels (FSLs) to represent future flood levels. This is based on guidelines from Ausenco Sandwell (2011). Each value is subject to change and may need to be reassessed in the future.
- A 0.6 m freeboard allowance is included in flood construction levels (FCLs) and is consistent with Ausenco Sandwell (2011).
- The Flood Construction Levels (FCLs) have been divided into zones based on similar flood level values. FCL values are given relative to CGVD (2013).
- The colored zone polygons show flood hazard extent areas as defined by the indicated FCL.
- FCLs were developed for the municipal District of Ucluelet (DDU) and Francis Island.
- The FCLs do not represent a specific planning level as defined by Ausenco Sandwell (2011). This map should not be interpreted to mean that planning will be limited to the FCLs indicated for each zone on this map.
- Applicable FCLs presented in this map should be done in accordance with relevant policy and regulations by a suitably qualified professional.
- The extreme variability of the western (outer) coastline means that care should be taken in interpreting these FCLs for specific sites. Flooding with steep forebays are subject to more wave runup and could experience higher flood levels.

Limitations:

- The accuracy of the presented FCLs is limited by available data and modeling techniques. The FCLs are based on 1D cross-shore transects and have been simplified by merging areas of similar characteristics. Please refer to the report for a detailed discussion of limitations.
- The accuracy of the flood hazard extent is limited by the accuracy of the surveys and mapping data. The flood hazard extents were established on the ground by legal survey.
- This map was prepared by Ebbwater Consulting Inc. using generally accepted practice and guidelines for the province of British Columbia. However, flooding may still occur outside the defined flood hazard boundaries, and Ebbwater Consulting Inc. and Cascadia Coast Research Ltd. do not assume any liability by reason of this map.
- The flood levels and levels shown on this map are to provide an assessment of current and future flooding to help inform land use policy. Under the provisions of the Local Government Act, 2004, these flood extents only take effect when adopted, approved or implemented via another planning tool (such as a zoning bylaw or plan). They therefore do not currently have any legal or planning standing.
- Base map and parcel layers were provided by different data owners and are subject to differences.

Data Sources:

- Flood Construction Reference Plane (FCRP) values were provided by Cascadia Coast Research Ltd.
- Water levels were interpolated from a limited number of transects and were subject to bathymetry.
- Digital Elevation Model (DEM) was created based on LIDAR data surveyed by the District of Ucluelet.
- Mapping Data and Land Parcels were received from the DDU.
- Base map was based on CARTO's Postmap, created using geospatial infrastructure data - openstreetmap.org (© OpenStreetMap contributors; cartography license CC BY-SA).

References:

- Ebbwater Consulting Inc. and Cascadia Coast Research Ltd. (2020). District of Ucluelet Coastal Flood Mapping (Final Report).
- Ausenco Sandwell (2011). Climate Change Adaptation Guidelines for Sea Level Rise Coastal Flood Hazard Land Use - Guidelines for Management of Coastal Flood Hazard Land Use. Prepared for the British Columbia Ministry of Environment.





DISTRICT OF UCLUELET



Coastal Flood Mapping

Coastal Storm Flood Planning Support Map 3/5
Flood Construction Level - Zones for Rare Event (Future)
 0.5% AEP, 1 m FSL, with 0.6 m freeboard

Flood Construction Level (CGVD 2013, m)

| |
|-------------|
| 4.0 - 6.0 |
| 6.0 - 8.0 |
| 8.0 - 10.0 |
| 10.0 - 12.0 |
| 12.0 + |

— Flood Hazard Boundary

Official Community Plan
 Map 4
 Coastal Storm Flood Planning Support Map 3/5
 Planning Support Map 3/5

DATE PREPARED BY
UCLUELET

Date Created:
June 26, 2020

Map Scale:
1:10,000

Coordinate System:
NAD83, UTM 10N

Vertical Datum:
CGVD 2013

Stamp provided in original version



Notes to Users

- This map was prepared to accompany the District of Ucluelet Coastal Flooding Planning report (EBBwater Consulting Inc. and Cascadia Coast Research Ltd., 2020) and is intended for the purposes set out in that report only. See the report for further details on the methodology, results and limitations.
- Flood and tsunami inundation depths were determined based on a simulation of tsunami waves generated by a modeled rupture (Coley and Moore, 2019; Coley et al., 2019).
- Water levels were conservatively assumed a tide equal to higher high water (HHW) (HHW) equal to 2 m at Ucluelet, and 1 m of residual surge level rise (RSLR), to provide results for a potential worst-case.
- Based on guidelines for the management of coastal flood hazard based on the Australian Disaster Resilience Guidelines (2011), 1 m of one level rise approximately corresponds to the year 2100. However, these projections are subject to changes in climate projections and may require reassessment in the future.
- Flood depth, duration and thresholds are based on ADR Guidelines for Disaster Resilience (2017).

Limitations

- The accuracy of the presented tsunami flood hazard vulnerability zones is limited by available data and the modeling approach used. Users refer to the report for detailed discussion on limitations.
- This map displays results for one possible tsunami wave (based on a specific source type and source). Flood characteristics and associated responses could vary based on different tsunamis.
- The accuracy of the tsunami flood hazard vulnerability zones is limited by the accuracy of the base mapping data and data. The data provided limits were not established on the ground level.
- No field verification was provided for mapping of tsunamis. This map was produced by EBBwater Consulting Inc. and Cascadia Coast Research Ltd. using guidance documents and approaches identified from a literature review of other similar studies. EBBwater Consulting Inc. and Cascadia Coast Research Ltd. do not assume any liability for the failure to capture flood hazard areas on this map.
- The tsunami flood hazard vulnerability zones shown on this map are intended to provide an assessment of current and future flooding to inform decisions on future land use policy. Under the provisions of the Local Government Act (2004), these flood hazard zones take effect when adopted by Order or implemented through another planning tool (such as a development permit area). They therefore do not currently have any legal planning standing.
- Flood hazard zones are presented for all areas landward of the federal shoreline layer (as provided by the District of Ucluelet (2013)), including a small buffer to ensure all exposed areas are captured.
- Base map error layers were provided by different data owners and may be subject to differences.

Data Sources

- Tsunami wave depths and velocities were provided by Cascadia Coast Research Ltd.
- Mapping data, including Shoreline Layer, and Land Parcels were received from the District of Ucluelet.
- Base map data was based on CARTO's Position, created using derivative OpenStreetMap data - openstreetmap.org (© OpenStreetMap contributors, cartography license CC BY-SA).

References

- EBBwater Consulting Inc. and Cascadia Coast Research Ltd. (2020). District of Ucluelet Coastal Flood Mapping (Final Report).
- Australian Disaster Resilience Guidelines (2011). Climate Change Adaptation Guidelines for Urban Dikes and Coastal Flood Hazard Land Use. Guidelines for the Management of Coastal Flood Hazard Land Use. Prepared for the Australian Government Department of Environment.
- ADR Guidelines for Disaster Resilience. Australian Disaster Resilience Guidelines. Department of Environment and Heritage. <https://www.environment.gov.au/australian-disaster-resilience-guidelines>
- Coley et al. (2019). Nat. Haz. (2019) 94:445-460.



Tsunami Flood Hazard Vulnerability Zones - Definition:

- H1 - generally safe for people, vehicles and buildings
- H2 - unsafe for small vehicles
- H3 - unsafe for vehicles, children and the elderly
- H4 - unsafe for people and vehicles
- H5 - unsafe for people and vehicles. Buildings require special engineering design and construction
- H6 - unsafe for vehicles and people. All building types considered vulnerable to failure



DISTRICT OF UCLUELET



Coastal Flood Mapping

Tsunami Flood Planning Support Map 6/6

Tsunami Flood Hazard Vulnerability Zones - Splay Faulting Rupture (Future) G2018-S4 model, 1 m RSLR

Land Parcels

Tsunami Flood Hazard Vulnerability Zones

- H1
- H2
- H3
- H4
- H5
- H6

Official Community Plan

Map 6/6
Tsunami Flood Planning Support Map 6/6

DISTRICT OF UCLUELET

Date Created: June 26, 2020

Map Scale: 1:12,500

Coordinate System: NAD83, UTM 10N

Vertical Datum: CGVD 2013

Stamp provided in original version



Notes to Users:

- This map was designed to accompany the District of Ucluelet Coastal Flood Mapping report (Ebbwater Consulting Inc. and Cascadia Coast Research Ltd, 2020) and is intended for the purposes set out in that report only. It does not constitute support for further details on the methodology and limitations.
- The tsunami surge elevation was developed based on the highest of the simulated tsunami (runup) elevations (excluding rupture from Gao et al., (2018)) for a 1 m relative sea level rise (RSLR). The extent of the tsunami planing level of 18 m (without safety factor) are shown on the map.
- Water level was conservatively assume a 2 m subsidence, a tide equal to the high water surge tide (HWST), equal to 2 m at Ucluelet, and 1 m of relative sea level rise (RSLR), in which results for a potential future flood event.
- Based on the best practices for the management of coastal flood hazard (Auerbach and Sandwell 2011), 1 m of sea level rise is conservatively assumed to correspond to the year 2050. However, this period is subject to changes in climate projections and may likely require reassessment in the future.

Limitations:


- The accuracy of the presented tsunami flood planning level is limited by available data and the modeling approaches used. Users are referred to the report for detailed discussion.
- This map shows results for one possible tsunami wave (based on one rupture type and source). Flood characteristics for associated responses could vary based on different waves.
- The accuracy of the tsunami flood planning level extent is limited by the accuracy of the base mapping data and DEM. The flood hazard limits were not established on the ground by the survey.
- No formal guidelines exist for the province for mapping of tsunami flood planning level extent shown on this map are to inform decisions on future land use policy. Under the provisions of the Local Government Act (2009), these maps only take effect when adopted by bylaw or resolution via another planning tool (such as a development permit area). They therefore do not currently have legal or planning standing.
- Flood planning level extent are presented for all areas landward of the coastal shoreline layer (as provided by the District of Ucluelet (DOU)), including a small buffer to ensure all coastal areas are captured.
- Base map and parcel layers were provided by different data owners and are subject to differences.

Data Sources:

- Tsunami forecast data were provided by Cascadia Coast Research Ltd.
- Reshape file, Shoreline layer, and Land Parcels were received from the DOU.
- Base layer was created on CARTO's Position, created using derivative OpenStreetMap data - openstreetmap.org (© OpenStreetMap contributors; cartography license CC BY-SA).

References:

- Ebbwater Consulting Inc. and Cascadia Coast Research Ltd. (2020) District of Ucluelet Coastal Flood Mapping Final Report.
- Auerbach, R., and Sandwell, S.M. (2011). Climate Change Adaptation Guidelines for Dikes and Coastal Flood Hazard Land Use - Guiding the Management of Coastal Flood Hazard Land Use. Prepared for the British Columbia Ministry of Environment.
- Gao et al., Nat. Haz. (2018) 94:445-469.





DISTRICT OF UCLUELET



Coastal Flood Mapping
Tsunami

Tsunami Flood Planning Support
Map 2 / 6
Tsunami Flood Planning Level – Splay
Faulting Rupture (No Safety Factor)
G2018-S-A model, 1 m RSLR

Land Parcels

Tsunami Flood Planning Level:

- Areas below 18 m CGVD 2013
- Areas at or above 18 m CGVD 2013

Official Community Plan

Map 6
Developed by:
Tsunami Flood
Planning Support 6-6
DISTRICT OF UCLUELET

| | |
|---|--------------------------------------|
| Stamp provided in original version | Issue Created: June 26, 2020 |
| | Map Scale: 1:10,000 |
| | Coordinate System: NAD83, UTM 10N |
| | Vertical Datum: CGVD 2013 |






Official Community Plan

MAP 5
Environmental
Base Information

- Eel grass
- Wetland
- Parcel Boundaries
- Contours (5m)
- Stream


- Tree Canopy - Height (m)**
- 10 - 20
 - 20 - 30
 - 30 - 40
 - 40 - 50
 - Over 50

This map shows environmental features based on best available information, and is not a substitute for the investigation by qualified professionals. For information on environmental Development Permit Areas refer to Schedule E.

Date: February 17, 2021

The information reported is for general reference only and is based on available sources. The District of Ucluelet assumes no liability for the accuracy of base mapping information; ground truthing on individual properties should be undertaken by qualified professionals prior to development planning.

Prepared by



| UCLUELET WATERCOURSES | | | | |
|--------------------------|---------------------------|---------------------------|----------------------------|-----------------------|
| 1 - NOT IDENTIFIED | 11 1.75m - FISH STREAM | 21 - NOT IDENTIFIED | 31 0.2m - NON-FISH STREAM | 31b - NON-FISH STREAM |
| 2 0.5m - FISH STREAM | 12 1.25m - FISH STREAM | 22 - NOT IDENTIFIED | 32 1.35m - FISH STREAM | |
| 3 1.0m - FISH STREAM | 13 1.0m - FISH STREAM | 23 - NOT IDENTIFIED | 33 0.85m - NON-FISH STREAM | |
| 4 1.0m - FISH STREAM | 14 1.0m - FISH STREAM | 24 - NOT IDENTIFIED | 34 0.5m - NON-FISH STREAM | |
| 5 1.0m - FISH STREAM | 15 - FISH STREAM | 25 - NOT IDENTIFIED | 35 0.5m - NON-FISH STREAM | |
| 6 - NON-FISH STREAM | 16 0.2m - NON-FISH STREAM | 26 - NOT IDENTIFIED | 36 0.25m - FISH STREAM | |
| 7 - FISH STREAM | 17 - FISH STREAM | 27 - NOT IDENTIFIED | 37 1.65m - FISH STREAM | |
| 8 - NON-FISH STREAM | 18 - FISH STREAM | 28 - NOT IDENTIFIED | 38 - NOT IDENTIFIED | |
| 9 0.2m - NON-FISH STREAM | 19 - NOT IDENTIFIED | 29 2.0m - NON-FISH STREAM | 37b 1.4m | |
| 10 1.0m - FISH STREAM | 20 - NOT IDENTIFIED | 30 1.33m - FISH STREAM | 38b - NOT IDENTIFIED | |

NOTE:
 - INFORMATION LISTED IN THIS CHART IS BASED ON PREVIOUSLY COMPLETED ENVIRONMENTAL ASSESSMENTS.
 - STREAM SIZE AND DESIGNATION AS A FISH STREAM OR NON-FISH STREAM IS SUBJECT TO FURTHER REVIEW.
 * IDENTIFIED AS HAVING POTENTIAL FOR ECOLOGICAL RESTORATION.

Part Six: Implementation

Implementation

As noted in Part 1, this OCP takes a 30-year view, looking ahead to how the community of Ucluelet will evolve to the year 2050 and beyond.

An Official Community Plan is a statement of objectives and policies adopted by a local government to guide decisions on land use planning, land use management and municipal operations within the area covered by the plan.

The OCP sets out a road map for the community, to let everyone know where we're headed in the long term. The timing of individual actions and steps to implement any area of the OCP depend on future budget discussions, decisions and priorities of the community's elected Council.

Written in 2020, this plan is a complete policy document to guide the community at this point in time, but also acknowledges specific areas where further work is necessary to adjust or more clearly define the community direction and priorities.

The following work, some of which is already underway (or budgeted and scheduled), will allow the District to update this plan in the near future to provide a true "2020" vision:

- further conversation with indigenous communities;
- priority housing actions including a housing needs assessment;
- incorporating the results of a long-term land use demand study;
- review and refinement of environmental development permit areas;
- consideration of a floodplain bylaw to clarify expectations for flood construction levels;

- completion of the sewer master plan;
- completion of an integrated stormwater management plan;
- implementing asset management program;
- development of a community monitoring and reporting process

It is anticipated that the further work noted above could result in specific amendments to this OCP (e.g., adoption of new and updated mapping). The OCP is a living document and such amendments should be seen as a healthy function for an engaged community. It is generally recommended that a community review and update its OCP every five to ten years.

Monitoring

Implementation and monitoring are critical elements to realizing the goals of an Official Community Plan over the duration of the plan.

A regular monitoring process will also benefit future updates to the OCP.

Objective 6A Ensure the OCP is implemented in a timely manner consistent with the goals, objectives and policies identified herein.

Objective 6B Monitor the plan and identify any shortcomings or amendments required to address community-endorsed changes or needs.

Policy 6.1 Develop a process for monitoring and reporting progress on the OCP which dovetails with the excellent work of the Clayoquot Biosphere Trust in producing their regular Vital Signs report.

Climate Action Monitoring

The District's Annual Reporting will include a section on Climate and Energy, which will include progress updates on actions and indicators in the 2019 Climate Action Plan.

The District will track and report on the 2030 greenhouse gas emissions reduction target of 40% by 2030 based on 2007 levels, and also report on additional indicators identified in the Climate Action Plan.

Relationship to Other Plans

The OCP builds on and references a number of other plans. More detailed background, discussion and analysis can be found in these plans. The primary recommendations from these inform the policy statements adopted in this OCP.

- Transportation Plan (2011)
- Economic Development Strategy (2012)
- Harbour Plan (2012)
- Parks and Recreation Master Plan (updated 2013)
- Traffic Control Review (2013)
- Age-Friendly Action Plan (2016)
- Economic Development Strategy Update (2017)
- Clean Energy for the Safe Harbour – District of Ucluelet 100% Renewable Energy Plan (2019)
- Community Climate Change Adaptation Plan (2020)

In turn, the direction set by the OCP influences a number of bylaws enacted by Council. Adoption of a new or updated OCP is a good catalyst for reviewing and if necessary updating regulatory bylaws of the municipality. This OCP may influence minor, or in some cases significant, amendments or replacement to bylaws such as:

- Annual Budget and 5-year Financial Plan
- Council Procedures Bylaw
- Zoning Bylaw
- Development Application Procedures Bylaw
- Development Cost Charges Bylaw
- Subdivision and Development Servicing Standards Bylaw

A number of these bylaws are long in the tooth, and their review and update is supported by the policies in this OCP. The

process, timing and prioritization of this work will be the subject of strategic planning by Council and annual budget decisions.

Regional Context

The Alberni Clayoquot Regional District has not adopted a Regional Growth Strategy. A Regional Context Statement is therefore not required as part of the municipal OCP. Nevertheless, the municipality is fortunate to have a history of strong working relationships with nearby jurisdictions and will benefit from even greater cooperation in the future. Developing a local Regional Context Statement would provide an opportunity for continued dialogue and a clear statement of expectations among neighbours.

The west coast has experienced rapid visitor growth and change in recent years. Acknowledging that the entire west coast sub-region overlaps the traditional territories of Nuu-Chah-Nulth peoples and nations, a co-developed regional strategy for sustainable development will include consideration of:

- environmental resilience and diversity
- social and cultural resilience for both indigenous and non-indigenous members of the community
- carrying capacity
- equity and opportunities for the economic development aspirations of both indigenous and non-indigenous communities

This may mean throttling back on the amount, and/or adjusting the types, of development within the municipal boundaries of Ucluelet and Tofino. At the same time the benefits of keeping towns compact can include reduced impact on the environment,

efficient service delivery, and achieving the “critical mass” that can increase community energy, interactions and character. Developing a strategy to meet the needs of the environment and the aspirations of all communities will be a balancing act.

Objective 6C Consider municipal matters in the context of the whole west coast subregion and be a good neighbour to the communities of Tofino, First Nations, the Pacific Rim National Park Reserve and ACRD Electoral Area “C”.

Policy 6.2 In consultation with neighbouring jurisdictions, develop and adopt a Regional Context Statement for Ucluelet to further define the long-term role of the community within the west coast subregion.

Policy 6.3 In partnership with all neighbouring jurisdictions, develop a regional strategy for sustainable development of the west coast to meet the needs of the community and protect the ecology of this special place.

Policy 6.4 Call on the ACRD to implement the policies of the adopted South Long Beach (Area C) Official Community Plan Bylaw No. P1166, 2007, to maintain the environmental values and rural character expressed in the plan.

Policy 6.5 Explore with the ACRD options for expanded services for the west coast including the role of regional planning and regional parks to meet the needs of local communities and visitors.

Development Permit (DP) Area Designations and Guidelines

Authority

Section 488(1) of the *Local Government Act* allows local governments to designate Development Permit Areas (DPAs) for one or more of the following purposes:

- a) protection of the natural environment, its ecosystems and biological diversity;
- b) protection of development from hazardous conditions;
- c) protection of farming;
- d) revitalization of an area in which a commercial use is permitted;
- e) establishment of objectives for the form and character of intensive residential development;
- f) establishment of objectives for the form and character of commercial, industrial or multi-family residential development;
- g) in relation to an area in a resort region, establishment of objectives for the form and character of development in the resort region;
- h) establishment of objectives to promote energy conservation;
- i) establishment of objectives to promote water conservation;
- j) establishment of objectives to promote the reduction of greenhouse gas emissions.

The **form and character** DPAs, the locations of which are identified on Schedule F, are:

- Village Square (DPA I)
- Peninsula Road (DPA II)
- Industrial (DPA III)

In addition, all lands within the boundaries of Ucluelet are designated as a Development Permit Area for the regulation of form and character when being developed for:

- Multi-Family, Commercial & Mixed-Use (DPA IV)

The **environmental** DPAs, the locations of which are identified on Schedule E, are:

- Terrestrial (Mature Forest) (DPA V)
- Streams and Riparian Areas (DPA VI)
- Marine Shorelines (DPA VII)

The **hazardous conditions** DPAs, the approximate locations of which are identified on Schedule G, are:

- Steep Slopes (DPA VIII)

DPA General Guidelines

The following General Guidelines apply to DPAs:

Guideline 1 Where land is subject to more than one DPA designation, only a single development permit is required and only one permit fee will be charged. However, the application is subject to the requirements of all applicable DPAs.

Guideline 2 On existing lots that meet or are less than minimum lot area standards, the location of which limits the opportunity to fully meet development permit requirements, the development permit guidelines should be addressed to the fullest extent within the constraints of the site and lot.

Guideline 3 The District may consider issuing a development permit to supplement a bylaw or to set standards in accordance with Section 490 of the *LGA*.

Form and Character Development Permit Areas

Objective: to guide the development of a pedestrian-oriented, compact and vibrant town which maintains its coastal village character and does the following: protect important public views, create buildings at a scale which is comfortable and inviting to pedestrians, reflect and adapt to the climate and coastal weather, and acknowledge the heritage of Ucluelet.

Designation: the following Development Permit Areas (DPAs) are designated under section 488 of the *Local Government Act* to

control the form and character of the built environment within Ucluelet, to guide commercial, industrial and multi-family residential development, and development in the resort region.

The following Development Permit Areas are identified on Schedule F, Form and Character Development Permit Areas map:

- Village Square (DPA I)
- Peninsula Road (DPA II)
- Industrial (DPA III)

In addition, all lands within the boundaries of Ucluelet are designated as a Development Permit Area for the regulation of form and character when being developed for:

- Multi-Family / Commercial / Mixed-Use (DPA IV)

Development Permit Area Guidelines specify the District's objectives and regulations for each area. All developments within a designated Development Permit Area require a Development Permit to be issued by the District.

Development Permit Area Exemptions

The following are exempt from requiring a form and character Development Permit:

1. construction of a single-family dwelling unit on a property where single-family dwelling is a principal permitted use under the property's designation in the zoning bylaw.
2. development of Institutional buildings and uses - nevertheless these uses are encouraged to meet the intent of these guidelines;

3. public works undertaken or authorized by the District of Ucluelet, or provincial or federal agencies;
4. interior construction or renovations which do not affect the exterior form and character of a building;
5. renovations which do not impact the overall appearance of the exterior of a building. This would include repainting or refinishing, roof repair, replacement of windows and doors, replacement of exterior materials that comply with these guidelines, and replacement or addition of awnings. To clarify, building alterations such as the restoration or reconfiguration of a building's whole façade, or additions to the front of a building would require a Development Permit.
6. an addition to a principal building, provided that:
 - a. The value of the proposed construction is less than \$75,000; and
 - b. The proposed construction is located within a rear yard and conforms to the minimum setback requirements.
7. construction of an accessory building or structure provided that:
 - a. The value of the proposed construction is less than \$75,000; and
 - b. The proposed construction is located within a rear yard and conforms to the minimum setback requirements.
8. replacement or alteration of existing signs or canopies or the construction of new signs and canopies provided they are in full compliance with the Sign Bylaw or an existing Development Permit;
9. new landscaping and/or landscape maintenance which complies with these design guidelines; and,

10. construction, building improvements or site improvements associated with an approved temporary use permit.

General Guidelines applying to all Form and Character Development Permit Areas

All development applications need to meet the underlying objectives for the building design, landscape design, streetscape and signage (as applicable).

- F1. Building design, layout, finish and colour should be of a high quality that reflects traditional (e.g., fishing village) or contemporary West Coast architectural styles;
- F2. Larger development should be broken up into smaller components. The image of any new larger building should be as a grouping of smaller pieces. Break up building massing by articulated building faces, stepping back whole or partial upper floors, and landscaping to soften the building appearance and present a human-scale presence at the pedestrian level;
- F3. Building frontage design (any building elevation facing a public street) and associated public realm enhancement must create an attractive pedestrian environment. Considerations include:
 - Easily identifiable building entrances;
 - Narrow commercial storefronts; and
 - Concentrating signage at pedestrian eye level.



F4. Parking shall be located at the rear of lots, if possible, and screened from street view with either a structure or landscaping, or where feasible, below grade;

F5. Parking areas with more than 10 spaces should be broken into smaller groups, divided by landscaped areas and trees;

F6. Awnings, deep roof overhangs or colonnades should be incorporated into buildings to provide weather protection along sidewalks and at building entrances. These devices must be an integral part of the overall design;

F7. On corner sites, buildings must be designed with consideration for their visual prominence, potential function as landmarks and their ability to contain and define streets. Additionally, developments occurring at corner lots must consider their prominence within the streetscape hierarchy and include architectural detailing or massing which reflects this. All developments located at a corner must occupy that corner on both sides;

F8. The extensive use of blank walls, regardless of the material used, must be avoided. The visual impact of blank walls should be softened by using one or more of the following:

- Architectural details and/or articulated façade;
- Graphic or artistic illustration;
- Placement of doors and/or windows; and



- Public seating and/or planters integrated into the façade.

F9. Where adjoining properties have uses of different intensity (e.g. single family next to multi-family residential) or different types (e.g. residential next to commercial) an appropriate architectural, building and landscaping transition must be provided;

F10. Buildings should provide protection from rain (e.g. awnings, overhangs, canopies);

F11. The following exterior materials are encouraged:

- Wooden posts and beams with visible fastenings;
- Wood siding, planks, board-and-batten, shakes or shingles;
- Corrugated or standing-seam sheet metal;
- Weathering steel (e.g., Core-ten), aluminum, galvanized, zinc, copper or other non-reflective architectural metal elements,
- Finished concrete;
- Cementitious composite siding (e.g., Hardi-plank) when detailed to avoid large areas of flat panels; and,
- Limited use of brick or local stone.

F12. As part of the building vernacular, not only of Ucluelet but the BC coast in general, sloped roofs are indicative of the climate and weather of the region. Sloped roofs with an angle no less than 30 degrees (7:12 pitch) are strongly encouraged. Exceptions may be considered for flat or curved roofs for significant sites and landmark buildings displaying exceptional architectural design;



F13. Roof materials must be in keeping with the character of Ucluelet. This includes the use of cedar shake and shingle, asphalt roof tile, standing-seam or corrugated sheet metal.



F14. As a major contributor to the feel and character of the street, wood – particularly Red Cedar, is the preferred material for exterior cladding. The use of cedar shake or shingle applications is especially favoured. Cedar lap siding and vertical board-and-batten are also preferred.



F15. The use of vinyl siding, stucco, pebble dash or artificial stone is not supported.

F16. As signage contributes to the character and feel of the area, it should reflect the artistic, cultural and historical traditions of Ucluelet. Signage must complement the architecture of the development and be sized appropriately;



F17. Exterior illumination of signage (e.g., gooseneck fixtures) is encouraged;

F18. Carved or painted wooden signs and individual letters are encouraged;

F19. Interior-lit plastic sign panels are not supported;

F20. All exterior mechanical units or equipment, including roof top units, must be enclosed in a manner that is attractive and integrated with the overall design;

F21. Landscape plans submitted for a development permit shall illustrate type, size, and location of proposed planting, and shall detail all hard and soft landscaping elements to convey a comprehensive design for the site;

F22. Landscape planting schemes must provide definition and clarity within the public realm. Plant material should be used to:

- a. Define the edges of outdoor space such as a café seating area;
- b. Signify a particular spot such as an entrance or gateway;
- c. Highlight pedestrian corridors;
- d. Delineate private and semi-private space from public space;
- e. Beautify a streetscape; and,
- f. Soften the transition of adjacent land uses.



F23. Planting should be designed so that drivers' sight lines are maintained at intersections, maneuvering aisles and parking lots;

- F24. Native trees and plants should be used where appropriate;
- F25. All landscaping shall be provided in accordance with British Columbia Society of Landscape Architects /British Columbia Nursery Trade Association landscape standards;
- F26. When laying out new parking areas, integrate vegetated bioswales to collect and filter stormwater;
- F27. Hardscape materials must be of a "non-skid" type and of durable quality;
- F28. Building and site design shall take into account CPTED (Crime Prevention Through Environmental Design) principles;

- F29. Site design should show functional, screened areas for waste and recycling in appropriate wildlife-smart containers.
- F30. All developments shall respect archaeological resources and comply with all relevant statutes for the protection thereof;
- F31. When locating buildings allow space for the Wild Pacific Trail, Safe Harbour Trail and Harbour Walk within vegetated corridors along the coastline, as an integrated part of the design for properties located on the waterfront, as shown on Schedule 'C' Parks and Trails Network.
- F32. In order to preserve Ucluelet's dark skies, minimize impacts on adjacent land uses and avoid unnecessary impacts on nocturnal wildlife, outdoor lighting should be shielded so that all light is directed towards the ground.



Development Permit Area I (Village Square)

The Village Square Development Permit Area (DPA I) is established for the following purposes:

revitalizing an area in which commercial, multi-family and mixed uses are permitted; and,

establishing objectives for the form and character of development in the resort region.

The Village Square DP Area I corresponds to the area designated as Village Square in the Official Community Plan and generally surrounds Main Street, Cedar Road, Bay Street and the section of Peninsula Road in this vicinity, as shown on Schedule F; Development Permit Areas for Form and Character. The Village Square is the heart of the community, the site of the District municipal hall, Aquarium and Village Green. The square is Ucluelet’s main gathering and shopping destination. It is a compact area comprised of those lands within an approximate five-minute walk of Main Street and Peninsula Road. The Village Square has the community’s highest densities and built forms, yet is designed to respect public views and the community character.

The objectives which justify this designation include assisting in the revitalization of the Village Square and enhancing and creating form and character that befits the community’s core area. Ucluelet is designated a “resort municipality” under Provincial legislation, and seeks to distinguish itself from nearby Tofino and other resort regions through its distinctive location, historical development and local attributes, much of which is characterized by its core Village Square. The DPA guidelines are intended to strengthen a high quality and distinct character that celebrates the community’s history, culture, and natural landscape. A key strategy of the OCP is to create a vibrant and mixed-use Village Square by concentrating new retail,

service and office development in the area, complemented by specific residential uses.

Guidelines

In addition to the General Requirements for Form and Character DP Areas, the following apply within DP Area I:

- F.I.1. Maintaining views of the harbour from Peninsula Road and Main Street is critical. The height of new buildings in DPA I must be carefully considered, and the building mass designed to avoid blocking views of the water from the public streets.
- F.I.2. Assessed on a site-by-site basis, general views to the harbour are to be maintained along the shoreline and include those depicted in Figure DPA 1.1 and from the north side of Peninsula Road. This may be done through considerations in building massing and height in key locations;



Figure DPA 1.1 Important Views - Inlet



F.I.3. Developments shall strive to create openness, connections, or views to the waterfront areas through open spaces or pathways. New development shall avoid impeding public access to the foreshore beyond private property

boundaries;

F.I.4. New developments should enhance and connect to the network of adjacent public open spaces, walkways and trails which connect and cross through the area;

F.I.5. Properties fronting Peninsula Road and Main Street must be designed to create an eclectic, inviting and pedestrian-friendly streetscape by carefully considering scale, massing and character;

F.I.6. New buildings should be sited close (e.g. 0 to 1.5m) to the property line fronting the street, with parking located to the side or rear. Covered porches, canopies or awnings are encouraged.

F.I.7. Some variation in the location of the building frontage relative to neighbouring buildings is encouraged, which will preserve the sense of informality and allow for the creation of useful outdoor areas facing the street.

F.I.8. Zero setbacks from side property lines is supported to create a continuous pedestrian streetscape. Gaps between buildings are to be minimized; therefore, avoid

placing buildings in the middle of open cleared sites. Shared driveways accessing parking and service areas at the rear of buildings is encouraged.

F.I.9. The block bound by Peninsula Road to the south, Cedar Road to the north, Main Street to the east and Bay Street to the west should be considered for its long-range redevelopment potential. This centrally located area is well positioned to become Ucluelet's core block, having strong connective qualities to other central areas. Situated between street-oriented development, a series of alleys should lead to an internal system of courtyard and mews type developments with a mix of uses clustered around groups of existing trees and central green. Pursue opportunities for connection and access in this area as the design of the Cedar Road parking lot / pedestrian hub is developed:



F.I.10. Improve the character of the streetscape adjacent to the existing Co-op Store by:

- Retain and enhance landscaping;
- Explore improved use of the plaza space for pedestrian and vehicle movements, and visual interest;
- Reduce the width of the existing driveway access;
- Screen adjacent parking area to the north; and
- Rethink the function and character of the lane on the east side of the property.

Development Permit Area II (Peninsula Road)

The Peninsula Road Development Permit Area (DPA II), as shown on Schedule C, is established for the purposes of:

- A. revitalizing an area in which commercial, multi-family and mixed uses are permitted; and,
- B. establishing objectives for the form and character of development in the resort region.

The objectives that justify this designation include:

- assisting in the revitalization of Peninsula Road as the gateway and main approach into Ucluelet;
- improving the form and character of the area and public realm as experienced on street and public pathways;
- maintaining and improving the views and experience of the Inner Harbour from public places, as a key landmark and focal point to the image of Ucluelet;

Special conditions that warrant these DPA guidelines include the emergence of tourism and its related services alongside the district's established but changing industrial edge. Efforts to beautify Ucluelet's main streets and associated public realm need not lose sight of the town's past industrial flavour, but should become more inviting and accessible.

The entrance to town on Peninsula Road and the nearby Inner Boat Basin is an area of concentrated tourist commercial development. This means the types of activities that occur here are attractive to tourists seeking a west-coast fishing village experience. This includes developments in the form of hotel/motel or vacation rentals, tourist facilities such as information centres, galleries and specialty retail stores, but also marine-related light industrial uses that are attractive to tourists such as commercial fishermen vending straight off the dock and boat building/repairs.

Successful marinas and related retail and commercial developments are natural draws for people. Ucluelet is in a strong position to capture the vitality of the waterfront by building welcoming places that evoke the character of coastal life.

Pedestrian connectivity along Peninsula Road and around the Inner Boat Basin to the rest of central Ucluelet and the Village Square is extremely important. Having easy walking access that is both obvious (way-finding) and attractive entices residents and visitors to stroll. This type of activity engages people to meet and is good for community spirit; but it is also good for the local economy as it brings people in contact with those businesses that rely on pedestrian traffic.

As a key focal point for the District's image, the form and character described above needs to translate to the area's architecture and associated landscape and public realm. Attractive quality design which evokes the natural beauty and history of Ucluelet must be sought to achieve cohesion and continuity throughout the Inner Boat Basin. Concentrating uses and offering attractive walking routes along the main roads and along the water's edge, is also greatly encouraged.

Development Permit Area guidelines exist to promote and manage these community-led aspirations to achieve developments of high quality and character.

Guidelines

In addition to the General Requirements for Form and Character DP Areas, the following apply within DP Area II:

- F.II.1. Views to the harbour from public streets, pathways and along the shoreline, generally shown on Figure DPA II.1, must be retained by adjusting building massing and height in key locations including the north side of Peninsula Road;





Figure DPA II.1 Important Views - Small Craft Harbour

F.II.2. A continuous pedestrian pathway should follow the shoreline, wherever possible, across the entire Inner Boat Basin. This pathway should continue through and connect to the Safe Harbour Trail and the Village Square.

F.II.3. Gaps between buildings are to be minimized; therefore, avoid placing buildings in the middle of open cleared sites. Shared driveways accessing parking and service areas at the rear of buildings is encouraged.

F.II.4. Buildings, structures and roads should be located to minimize alterations to treed areas and other environmentally sensitive areas;

F.II.5. Parking should be located at the rear of lots if possible and screened from street view with either a structure or landscaping, or where feasible, below grade;

F.II.6. Continuous accessible pedestrian sidewalks, planted boulevards and bicycle lanes should be provided along the length of Peninsula Road, on both sides, from Forbes Road to Marine Drive as shown on Schedules 'B' and 'C';

F.II.7. Street trees should be used along the entire length of Peninsula Road, on both sides, thereby creating a sense of enclosure and cohesion to the street;

Development Permit Area III (Industrial)

The Industrial Development Permit Area (DPA II), as shown on Schedule F, is established for the purposes of:

- A. revitalizing an area in which commercial and industrial uses are permitted; and,
- B. establishing objectives for the form and character of development in the resort region.

The objectives that justify this designation include:

- ensuring that light industrial uses do not detract from the form and character of the area or experience of the public realm in the community;
- ensure compatibility between commercial and light industrial land uses and activities in this area and adjacent parks, trails, residential and tourist commercial uses;
- maintaining and improving the views and experience of the working Harbour, and improve visibility so that people can experience and appreciate the activities of various marine industries safely from public places, as a key part of the image of Ucluelet;

Guidelines

In addition to the General Requirements for Form and Character DP Areas, the following apply within DP Area III:

- F.III.1. Monolithic structures and long expanses of blank walls facing the roadway should be avoided;
- F.III.2. Landscaped screening strips should be provided:
 - Along the property edge next to roadways;
 - Between parking areas, roadways and buildings;
 - Between different parking areas; and,
 - Between buildings and parking areas.
- F.III.3. Wildlife-proof garbage and recycling containers must be provided for all new developments;
- F.III.4. Support service structures such as loading bays, storage areas and waste bins should be located to minimize visibility from view of public roads and pathways and/or screened with walls, planting, solid wooden fencing or a combination;
- F.III.5. New industrial development should be accessed, wherever possible, from secondary roads;
- F.III.6. Transitions between light industrial areas and adjacent residential or tourist commercial properties should ensure privacy and avoid the impacts of noise and glare.
- F.III.7. New Marine Industrial development should incorporate sections of the Harbour Walk and Safe Harbour Trail. It is recognized that continuous pedestrian access along the waterfront will not be possible in every location, to ensure the safe operation of marine industries and access to vessels and machinery; where trails must divert away from the shoreline provide opportunities for viewing and include signage to explain marine activities, their history and economic importance.

Development Permit Area IV (Multi-Family, Commercial, and Mixed-Use)

The Multi-Family, Commercial, and Mixed-Use Development Permit Area (DPA IV) is established for the following purposes:

- A. revitalizing an area in which commercial, multi-family and mixed uses are permitted; and,
- B. establishing objectives for the form and character of development in the resort region.

The natural beauty and rich ecological qualities of this place are of utmost value to Ucluelet, its residents, and future generations. It is these qualities – beautiful, natural, and wild – which create the character residents cherish and people from afar come to experience. The District’s objective is to make every effort to preserve and enhance this experience. The *primary* character-giving qualities of the area are:

- The immediacy of the ocean and the marine environment;
- The presence of significant stands of forest, including old-growth;
- The sights, sounds and smells of a working harbour; and,
- The human-scale, walkable, funky and welcoming village atmosphere.

These qualities result in a real sense of a town inhabiting a coastal rainforest “on the edge”.

Two general multi-family residential typologies are anticipated:

Medium Scale – Ground oriented units usually having multiple floors and are attached by way of shared walls (e.g. duplex, triplex, terrace housing, townhouses);



Higher Scale – Units are a part of a larger multi-storied shared building (e.g. apartments), but may also include townhouses and coach houses.



Mixed-use developments, particularly including ground-floor commercial with housing behind and/or above, are also expected particularly along major roads and in the centre of town.

Objectives include ensuring that new multi-family areas are compatible and complementary in form and character to adjacent traditional single-family areas. It is important to establish suitable regulations to govern this transition. As these housing types expand in Ucluelet, sensitivity around issues such as scale, height, and style must be addressed. Generally, higher scale building forms are encouraged along major roads such as Peninsula Road, with medium scale building forms providing a transition to single-family areas.

Guidelines:

In addition to the General Requirements for Form and Character DP Areas, the following apply within DP Area IV:

- F.IV.1. All buildings, structures and additions thereto must be designed and coordinated in a comprehensive manner considering efficient site circulation, the relationship between buildings, visual impact and design compatibility with its context;
- F.IV.2. Sloped roofs, rather than flat roofs, are preferred;
- F.IV.3. Where internal roadways are required, they should provide efficient circulation, encourage appropriate speed through physical design, and the pedestrian realm should be clearly defined by using alternative materials, landscaping and physical design;
- F.IV.4. Buildings or groups of buildings placed adjacent to a public street must face that street (or streets), with each unit having its own individual and distinct front entry from the street. Excessive use of blank walls must be avoided;
- F.IV.5. Higher scale building forms may be located along Matterson Drive and Peninsula Road. Heights up to 12m (39 feet) may be permitted;



- F.IV.6. Medium scale building forms are preferred in other areas zoned for multi-family uses, to provide sensitive transitions to single family areas;
- F.IV.7. Where buildings are in very close proximity to the street or other public realm feature such as a pathway or courtyard, the finished floor level of that building should be raised by two feet as a minimum, to aid in privacy;
- F.IV.8. Garages and garage doors must not dominate the street-front façade of multi-family buildings. All attempts must be made to accommodate integrated parking at the side or rear of units. If garage doors *must* be placed at the front of a building, they should be well integrated and subtle in appearance;
- F.IV.9. Where visitor parking or common parking areas are required, small groupings of parking stalls interspersed with tree planting should be employed rather than 1 uninterrupted lot wherever possible. Native plants are preferred;
- F.IV.10. Parking areas that are visible from the street and/or adjacent to residential buildings should be screened by substantial landscaping.
- F.IV.11. A reasonable amount of common area must be included in all multi-family developments in the form of native landscaping, courtyards or the like;
- F.IV.12. Preserving as much of the natural shoreline condition as possible, as well as the forest and its underlying shrub layer is critical to maintaining the character of the

community. All development must recognise these values and strive to minimize the adverse effects on the natural environment development can often bring. The form and character of buildings should reflect the natural beauty of the area. This can be achieved through:



F.IV.13. The sensitive siting of buildings;

F.IV.14. Producing architectural designs that are naturally inspired; and,

F.IV.15. Using materials and building methods that are inherent to the area and its natural and man-made history.

F.IV.16. New development with areas of high ground in the



District should be designed to accommodate areas for evacuation in extraordinary cases of emergency. Access, parking areas and parks or other open space at the highest points should be designed with thought to how they could double as muster points, if needed;

F.IV.17. Clear-cutting forested sites is prohibited. Developments must present plans showing tree retention and measures to ensure protection of existing significant trees and shrubs, clearly delineated limits of disturbance during construction, along with new plantings. The plans shall show pre- and post-development conditions to

prevent over-cutting. Protection of adequate root zone buffers around retained trees shall be identified by a qualified professional and shown on the plans;

F.IV.18. Mature Western Red Cedar and Sitka Spruce must be identified by a qualified arborist and, where they are determined to be healthy, preserved;

F.IV.19. The siting of new buildings, extensions to existing buildings as well as campsites and roads etc., must work sensitively around established existing vegetation and must be located to minimize alterations to the foreshore and other environmentally sensitive areas. As part of the efforts to maintain and enhance the landscape character of the area, all efforts must be made to retain landscape and ecological integrity;



F.IV.20. Minimal blacktop and hardscape paving should be used for driveways and patio areas, particularly in front yards. Gravel or grass driveways and wood decks are preferred;



F.IV.21. Architectural form and character must be site-sensitive to both the physical environment, as well as to the qualities of natural beauty in the area. Buildings should work with the natural environment on all levels;

F.IV.22. All developments must provide robust visual buffers of parking, loading and service areas by way of retained and enhanced native vegetation along all boundaries. In the case of those boundaries fronting the road, reasonable efforts must be made to retain significant trees and shrubs between driveways;



F.IV.23. Wildlife-proof garbage and recycling containers must be provided for all new developments;

F.IV.24. All waste bins must located at the rear of buildings or screened from view of public roads and pathways with solid wooden fencing.

Environmental Development Permit Areas

Objective: to guide development and use land wisely to ensure that the most sensitive environmental features of a site are protected and ecological functions are not needlessly disturbed by development activities.

Designation: the following Development Permit Areas (DPAs), identified on Schedule E, Environmental Development Permit Areas map, are designated under section 488(1)(a) of the *Local Government Act* protection of the natural environment, its ecosystems and biological diversity):

- Terrestrial (Mature Forest) (DPA V)
- Streams and Riparian Areas (DPA VI)
- Marine Shorelines (DPA VII)

Development Permit Area Guidelines specify the District's objectives and regulations for each area.

General Guidelines Applicable to all Environmental DPAs:

- E1. For all land lying within an Environmental DP area, an assessment of the site, its natural features and the development shall be undertaken and a report prepared by a Qualified Environmental Professional (QEP) shall be submitted with the DP application;
- E2. The QEP report must contain any records listed in the BC Conservation Data Centre and must include data obtained from a search of the Ministry of Environment's BC Species and Ecosystems Explorer for the categories

"plants and animals" and "Ecological Communities" that includes all potential red listed, blue listed, and SARA listed species along with their Conservation Framework priority.

- E3. In cases of reporting after the fact due to managing emergency situations, the applicant shall provide an environmental report certified by a Qualified Environmental Professional (QEP), describing follow-up works to restore environmentally sensitive areas which were present prior to the emergency.
- E4. For all non-emergency circumstances, the applicant shall provide an environmental report certified by a Qualified Environmental Professional (QEP). The report must include:
 - a. A site plan certified by a B.C. Land Surveyor that locates:
 - i. the proposed development relative to DPA boundaries shown on Schedule E and property lines;
 - ii. the environmental sensitive areas as defined under the general definitions and any other significant or rare species or species assemblages found in the DPA as identified by the QEP;
 - iii. the applicable buffer or setback recommended by the QEP to separate the proposed development from the environmentally sensitive feature.
 - b. For activity or construction within the stream channel, documentation of Provincial and Federal approval, with supporting technical reports.

- E5. If the QEP report identifies environmentally sensitive areas (ESAs) not shown on Schedule E, then the applicant and the District shall treat those values as if they are shown on Schedule E for the purposes of applying requirements of the more specific environmental DPAs.
- E6. If the QEP report confirms that an environmental value relating to a DPA shown on Schedule E is not present or does not affect the subject property, then the applicant and the District shall treat the property as though it is not in the applicable DPA. This includes the case where a QEP determines that there is a physical barrier between the environmental feature and the subject property that creates a functional separation between the two.
- E7. Clustering of density is encouraged as a means for preserving environmentally sensitive areas.
- E8. For all projects that involve development within an ESA, the District shall require the applicant to post security at 125% of the cost of protection and/or restoration works.
- E9. The District may, as part of the development permit, vary the setback requirements from an ESA where it can be demonstrated in a less than desirable existing situation that a “net positive improvement” for fish or wildlife habitat will result, or, in a more desirable existing situation that “no net loss” will result, subject to municipal, Provincial and or Federal agency review and comment. Any reduction of setback distances within an ESA shall occur in accordance with the findings and recommendations of the technical/environmental report.

Development Permit Area Exemptions

The following are exempt from requiring an environmental Development Permit. Despite the exemption provisions, owners must also satisfy themselves that they meet the requirements of any applicable federal or provincial regulations:

1. Development that is shown to be outside of all designated DPAs on a plan prepared by a registered BC Land Surveyor.
2. Interior or structural exterior alterations, renovations or repair to a permanent building or structure on an existing foundation to an extent that does not alter, extend or increase the building’s footprint or height.
3. Planting or replanting of native trees, shrubs or ground cover for slope stabilization, habitat improvement, soil stabilization and/or erosion control.
4. Routine maintenance of existing landscaping, lawn, paths or developed areas.
5. Actively manage priority invasive plants and noxious weeds listed on the Coastal Invasive Species Committee website www.coastalisc.com/priority-invasive-plants.
6. The removal of trees determined by a Certified Arborist or Registered Professional Forester, or another professional certified to do tree-risk assessments, as presenting an imminent safety risk.
7. Stream enhancement and fish and wildlife habitat restoration works carried out under provincial or federal approvals or notifications, and on provision of evidence of such approvals to the District.
8. Emergency procedures to prevent, control or reduce immediate threats to life or property including:

- a. emergency actions for flood protection and erosion protection;
 - b. removal of hazard trees characterized by a Certified Arborist;
 - c. clearing of an obstruction from bridge, culvert or drainage flow;
 - d. bridge and safety fence repairs in accordance with the *Water Act*;
 - e. pruning trees where a minimum of 60% of the original crown of any tree is retained to maintain tree health and vigour as prescribed by a Certified Arborist.
9. Public works and services constructed by or on behalf of the municipality, or by provincial or federal agencies, following best management practices.
10. Forestry activities on private lands that are managed under the *Private Managed Forest Land Act*.
11. Activities permitted by the provincial government on provincial Crown lands.
12. Paths for pedestrian use up to 1.5 metres in width provided all of the following are satisfied:
- a. Constructed exclusively of previous natural materials with no concrete, asphalt, or pavers;
 - b. Do not entail structural stairs;
 - c. Entail no removal of streamside or shoreline vegetation;
 - d. Do not impair stream bank or shoreline stability;
 - e. Do not impact sensitive habitat;
 - f. Avoid wildlife corridors and nesting sites; and
 - g. Are specifically designed to discourage motorized vehicle use.

13. Development in sites which have been previously assessed and where a Section 219 Restrictive Covenant has already been registered on the title of the property identifying areas and measures necessary to protect environmental values.

DPA V – Terrestrial Ecosystems (Mature Forest)

Category

In accordance with Section 488(1)(a) of the *LGA*, the District establishes objectives for the protection of the natural environment, ecosystems and biological diversity. These areas are designated as DPA V, generally as shown on Schedule E.

Justification

This Development Permit Area includes mature forests and wildlife habitat that could be subject to degradation due to development or harmful uses. Ucluelet is home to rich plant and animal habitat due to the peninsula’s interface between the terrestrial and marine environments. The ecosystems here are a complex and fragile array of diverse flora and fauna which depend on the health and resources of the ocean and temperate rainforest. Forest health and age is a critical component of the natural life and biodiversity of the area. There are also high aesthetic values in mature forest areas.

Guidelines

- E.V.1. Development should be planned to avoid intrusion into DPA V areas of the site and to minimize the impact of any activity on these areas.
- E.V.2. Development permit applications that encroach on areas designated as DPA V should include a report prepared by a qualified environmental professional outlining the following information:

- a. detailed site plan (1:250 or larger) identifying the location of property lines, proposed development and natural features including any Sitka Spruce, krummholz tree forms, nesting trees or wildlife corridors;
- b. an impact statement describing effects of proposed development on the natural features and ecosystems on the site;
- c. measures necessary to avoid wildlife conflict and any adjustments to the development plan where necessary to avoid established wildlife corridors;
- d. guidelines and procedures for mitigating habitat degradation including limits of proposed leave areas;
- e. recommendations for timing, construction standards, and where further assessment is necessary (e.g., seasonal nesting bird surveys),
- f. habitat compensation alternatives, where compensation is approved.

DPA VI - Stream and Riparian Areas Protection

Category

In conformance with the objectives of the provincial *Fish Protection Act*, the District wishes to ensure sufficient water for fish, to protect and restore fish habitat, and to improve riparian protection and enhancement. Therefore, pursuant to Section 488(1)(a) of the *LGA*, the District designates all riparian areas as DPA VI: Riparian Areas Protection.

DPA VI areas include the lands within 30 metres of streams and watercourses and include watercourses, lakes, streams, ponds and wetlands identified as fish-supportive habitat or connected to watercourses:

a) for a stream, a 30-metre strip on both sides of the watercourse measured from the high-water mark; and,

b) for a ravine less than 60 metres wide, a strip on both sides of the stream measured from the high-water mark to a point that is 30 metres beyond the top of the ravine bank.

For purposes of clarity, the above descriptions should be relied upon rather than the riparian areas shown on Schedule E. The latter is intended as a visual aid to help locate these areas. Within the Plan area, “stream” includes all named and unnamed watercourses, ponds, and wetlands.

Justification

The natural environment is a significant feature of the Plan area. It includes wet aquatic ecosystems that consist of and surround watercourses: streams, ponds, wetlands and in some cases, ditches. Some of these ecosystems may only be wet during the winter months, drying up in the summer. The geography and vegetation that surrounds, protects and interacts with the aquatic environment is called the riparian area.

Together, the water and the riparian area form aquatic habitat which are critical for the survival of fish, fish supportive processes and are important to maintain biodiversity and essential for many species. Unnecessarily disturbing these sensitive and important aquatic environments may harm their vitality and the ecological services they provide and can have downstream consequences on fish habitat.

Aquatic ecosystems are also critical for the survival of wildlife and form necessary travel corridors between habitats. Water is an important part of maintaining biodiversity and is essential for many species. Many rare species are associated with aquatic environments. Aquatic ecosystems are natural water purifiers and pollution filtration systems. Healthy aquatic ecosystems have a capacity to retain stormwater runoff, maintain water quality by reducing levels of sediment, nutrients and contaminants in outflow water, to slow water flow and to prevent erosion.

A development permit is required for any development within DPA VI to ensure that the ecological values of sensitive riparian and wetland habitats have been considered prior to development, and that measures will be taken to limit or avoid damage to these ecosystems. The objectives of having these Development Permit requirements include:

- Planning and guiding new development in a manner that preserves and protects fish and fish supportive processes, fish habitat and sensitive aquatic ecosystems;
- Protecting, restoring and enhancing fish and fish supportive processes, fish habitat and sensitive aquatic ecosystems in a relatively natural state while supporting adjacent land uses;
- Meeting the objectives of the *Fish Protection Act*, and
- Protecting water quality and quantity.

Guidelines

E.VI.1. Development or alteration should be planned to avoid intrusion into DPA VI areas of the site and to minimize the impact of any activity on these areas.

E.VI.2. Development permit applications that would encroach on areas designated as DPA VI should include a report prepared by a qualified environmental professional outlining the following information:

- a. detailed site plan (1:250 or larger) identifying the natural boundary and a line 30 metres from the natural boundary;
- b. an impact statement describing effects of proposed development on the natural conditions;
- c. measures deemed necessary to protect the integrity of streamside protection and enhancement areas from the effects of development;
- d. guidelines and procedures for mitigating habitat degradation including limits of proposed leave areas; and,
- e. habitat compensation alternatives, where compensation is approved.

E.VI.3. Development permit applications should include a vegetation management plan indicating the extent of proposed buffer areas and the proposed management of vegetation in these areas.

E.VI.4. Based on the biophysical assessment of the site within an area designated DPA VI, works or protective measures such as the planting or retention of trees or vegetation may be required to preserve, protect, restore or enhance stream, watercourses, fish habitat or riparian areas.

E.VI.5. In the absence of a report from a qualified environmental professional, a minimum buffer of 30 metres should be preserved between the high water mark of the watercourse and any building or structure.

- E.VI.6. The total amount of impervious cover on property adjacent to a watercourse should minimize impact on the receiving aquatic environment. Consideration should be given to reducing impervious cover through reduction in building footprint and paved areas, exceeding the minimum riparian setback where feasible, and use of on-site infiltration.
- E.VI.7. The construction of a small accessory building such as a pump house, gazebo, garden shed or play house may be permitted if all the following apply:
 - a. The building is located within an existing landscaped area;
 - b. No native trees are removed; and
 - c. The area of the structure is not more than 10 m².

DPA VII – Marine Shoreline

Category

In accordance with Section 488(1)(a) of the *LGA*, the District establishes objectives for the protection of the natural environment, its ecosystems and biological diversity. These areas are designated as DPA VII, generally as shown on Schedule E.

Justification

This Development Permit Area includes shoreline waters and natural fish and wildlife habitat that could be subject to degradation due to development or harmful uses. Shoreline areas and beaches may contain unstable slopes and soils subject to erosion, land slip and rock falls. In addition, the tidal

waters are habitat to a wide range of fish, wildlife, and plant species: eelgrass, in particular, is highly sensitive to negative impacts from intensive uses or development. There are also high aesthetic values along shoreline areas.

Guidelines

- E.VII.1. This DPA applies to all lands within 30 metres, measured horizontally in both landward and seaward directions, from the natural boundary of the ocean.
- E.VII.2. Unless otherwise exempt, prior to undertaking any development on the lands within DPA VII, the owner of the lands must obtain a Development Permit, the application for which must include an assessment report that has been prepared by a Qualified Environmental Professional, with demonstrated experience regarding the subject matter. The assessment report will identify how the proposed development will affect aquatic resources, and recommend measures to reduce or mitigate any negative impacts, such as the:
 - i. Appropriate siting of buildings, structures, roads, driveways, parking areas, trails, paths, and utilities;
 - ii. Retention or restoration of native vegetation and soils;
 - iii. Removal of invasive species;
 - iv. Designation of buffer areas to protect environmentally sensitive features or habitat;
 - v. Specification of any activities that may occur within the buffer areas; and
 - vi. Must state that the proposal is suitable for the area intended for development.
- E.VII.3. Land shall be retained in its natural state where possible, preserving indigenous vegetation and trees. If an adequate suitable building envelope exists on a parcel

outside of the DPA, the proposed development should be directed to that site or area. Encroachment into the DPA shall only be permitted where the applicant can demonstrate that the encroachment is necessary to protect environmentally sensitive features, due to hazardous conditions or topographical considerations, or to relate the development to surrounding buildings and structures.

- E.VII.4. The removal of trees and vegetation within DPA VII is discouraged and must be limited to only those areas that must be cleared to support the development. Any clearing required to accommodate roads, buildings, structures, and utilities, with the exception of necessary hydraulic, percolation, or geotechnical testing, shall not occur until after the issuance of a Development Permit to minimize the potential for soil erosion, runoff and spread of invasive species.
- E.VII.5. Shoreline stabilization devices are not supported on parcels that are not subject to active erosion nor are they supported on parcels that erode more rapidly as a result of vegetation removal that is not recommended or supervised by a Qualified Coastal Professional.
- E.VII.6. Shoreline stabilization devices are supported where a Qualified Coastal Professional, with experience to advise on such matters, has determined that a softer approach to shoreline stabilization such as vegetation enhancement, upland drainage control, biotechnical measures, beach enhancement, tree anchoring or gravel placement are not appropriate given site-specific conditions.
- E.VII.7. Shoreline stabilization devices are only permitted for the protection of existing structures when threatened by erosion due to natural forces as recommended by a

Qualified Coastal Professional and must be located entirely within the property boundary. New development and structures should be sited to avoid the need for shoreline stabilization devices over the expected lifespan of the structure.

- E.VII.8. The assessment for siting a shoreline stabilization device prepared by a Qualified Coastal Professional must include:
 - a. Assesses the risk of erosion on the subject property and the suitability of the subject property for a shoreline stabilization device;
 - b. Analyses of the potential impacts on coastal geomorphologic processes as a result of installing or not installing the device;
 - c. Analyses of the potential impacts on adjacent properties as a result of installing and not installing the device;
 - d. Recommendation measures to ensure that the subject property is protected while mitigating potential negative impacts on marine riparian areas, coastal geomorphologic processes or neighbouring properties.
- E.VII.9. Shoreline stabilization measures, pilings, floats, wharves and other structures which disrupt light penetration to the water column or obstruct public access to the foreshore are discouraged.
- E.VII.10. Impervious surfaces, including materials to construct docks and wharves, shall be kept to a minimum.
- E.VII.11. Parking areas should be equipped with oil/water separators and be landscaped to absorb runoff, and proof of a maintenance program for these will be provided.

- E.VII.12. New piers, docks and ramps shall be allowed only for water-dependent uses or for public access, and only permitted when the applicant has demonstrated that a specific need exists to support the intended water-dependent use.
- E.VII.13. Docks and wharves shall not extend over marshes or other productive foreshore areas, including critical areas such as eelgrass and kelp beds, shellfish beds, and fish habitats. Wharves shall not, in any case, extend over the water beyond the mean low-water mark, except as necessary to access floats or for public viewing access. Construction which minimizes disturbance of shoreline sediments and enables light penetration is encouraged.
- E.VII.14. Piers on pilings and floating docks are preferred over solid-core piers or ramps.
- E.VII.15. Boat launch ramps are discouraged and will only be considered for shared or public use, and only where they can be located on stable, non-erosional banks where a minimum amount of substrate disturbance or stabilization is necessary.
- E.VII.16. Structures in contact with the water shall be constructed of stable materials, including finishes and preservatives that will not degrade water quality.
- E.VII.17. All docks shall be constructed so that they do not rest on the bottom of the foreshore at low water levels.
- E.VII.18. Any plastic foams or other non-biodegradable materials used in construction of floats and docks shall be encased to prevent escape into the natural environment.
- E.VII.19. Piers should use the minimum number of pilings necessary, with preference to large spans over more pilings.

- E.VII.20. Piers should be constructed with a minimum clearance of 0.5 m above the elevation of the natural boundary of the sea.
- E.VII.21. Preference is given to the placement of mooring buoys and floats instead of docks.
- E.VII.22. New shoreline residential development of two or more dwellings shall provide joint use or community dock facilities rather than individual docks for each residence.
- E.VII.23. No more than one facility for mooring boats shall be located on or fronting any single parcel.
- E.VII.24. The consideration of the issuance of a Development Permit by the District in no way exempts the property owner from obtaining all necessary permits and approvals from provincial and federal agencies.

DPA VIII– Natural Hazard Areas Protection (Steep Slopes)

Category

In accordance with Section 488(1)(b) of the *LGA*, areas of steep slopes with an incline of 30 degrees or more are designated as DPA VIII, as shown on Schedule G.

Justification

Ucluelet experiences significant rainfall and storm events; soils on steeper slopes carry a higher hazard of failure from the effects of runoff and erosion, once disturbed or exposed by development.

Steep slopes tend to constitute high-risk areas for erosion and slippage if the tree cover is substantially altered. Potentially hazardous conditions on steep slopes may be avoided if adequate tree cover is retained and surface water runoff is minimized.

In order to protect development from these hazardous conditions, development permits are required for areas designated as DPA VIII.

Exemptions

The following development is exempted from the requirement to obtain a development permit for Hazardous Conditions:

In a steep slope area:

1. Development, where a geotechnical report has been received in conjunction with an application for building permit or subdivision approval.
2. Erecting fencing;

For trees:

3. Cutting down dead trees provided that the stump and roots remain undisturbed;
4. Planting new trees;
5. Removal of trees where the tree trunk diameter is less than 5cm (measured 1m from the base); and,
6. Where the tree trunk diameter is greater than 5cm (measured 1m from the base) pruning and limbing of trees provided a Certified Arborist provides a written opinion stating that the activity will not kill the tree.

Domestic yard maintenance, gardening and planting, including:

7. Planting new vegetation and maintaining existing vegetation through mowing, pruning, and similar activities;

8. Removing any dead vegetation provided the root structure is not disturbed; and

9. Removing any vegetation with stem diameter less than 5cm (measured 1m from the base), and not resulting in areas of exposed soil on a steep slope.

Guidelines

- E.VIII.1. The development or alteration of land, buildings and structures should be planned to avoid intrusion into DPA VIII areas and to minimize the impact of any activity on these areas.
- E.VIII.2. Prior to any development or alteration of land within DPA VIII areas, a development permit application must be issued that includes an assessment or report by a qualified, licensed professional engineer or other qualified professional addressing the following:
 - a. Contain a description of the methodology and assumptions used to undertake the assessment. The methodology should be described in sufficient detail to facilitate a professional peer review.
 - b. Identify any hazards which may affect the safe development of the land including, but not limited to:
 - i. flooding;
 - ii. slopes with an incline of 30 degrees or more;
 - iii. subsidence; and
 - iv. ground water flows.
 - c. Identify the location of all proposed buildings or development sites by specifying setback distances from a natural boundary, property boundary or feature or

hazard area. Areas depicted on maps must be delineated with sufficient accuracy and detail to allow the preparation of a legal reference plan for attachment to a restrictive covenant.

- d. Where applicable, flood construction levels should be provided by prescribing an elevation above the natural boundary of the sea or watercourse or natural ground elevation at the building site, or by specifying a geodetic elevation, or by a combination of both.
- e. An application should identify the location of all proposed buildings and structures on the development site and specify the setback distances from the natural boundary, property boundary, land features, and hazard areas.
- f. The applicant should consider the suitability of the land to accommodate the use intended.
- g. Plans should establish a safe setback line from any watercourses and shorelines to protect the land, buildings and inhabitants from the risk of injury or damage that may, in the opinion of an engineer or qualified professional, be caused by the hazards of flooding, erosion, subsidence earthquake, mud flows or any combination thereof.

E.VIII.3. The professional’s recommendations and the conclusion of the report should:

- a. acknowledge that the Approving Officer may rely upon the report when reviewing subdivision applications and/or that the District may review the report prior to making land development decisions;
- b. certify that the land is safe for the use intended, with probability of a geotechnical failure, flooding or any other substantial hazard resulting in property

damage of less than two per cent (2%) in 50 years or as specified by the most recent edition of the “APEGBC Guidelines for Legislated Landslide Assessments for Residential Developments in BC”;

- c. identify any deficiency in the location or design of the buildings, the proposed water, sewer, drainage, access and road works or the construction standards intended for the development;
- d. prescribe the geotechnical works and any changes in the standards of the design of the development which are required to develop land, buildings, structures and infrastructure safely for the use intended and to maintain the safety of the land, buildings, structures and infrastructure as a condition of the approval of the development; and
- e. where mitigation works and actions are proposed, describe the effects that the proposed works and actions may have on other properties, including public infrastructure or lands.

E.VIII.4. Where mitigation works and actions designed to reduce hazards or impacts are contemplated, the applicant’s professional engineer should confirm that the works and actions will be acceptable to local government, and that they would meet regulatory requirements, prior to completing the report and a detailed design.

E.VIII.5. where mitigation works and actions are proposed, the qualified professional should identify whether ongoing maintenance or periodic replacement measures are necessary, and specify what ongoing measures are necessary for the property to remain safe for its intended use.

E.VIII.6. Plans should include the retention of significant stands of trees, as well as native vegetation, within DPA VIII areas, as recommended by a QEP.

A note on Flood Hazards:

This OCP bylaw does not designate Development Permit areas for protection from coastal flooding; the District has commissioned detailed flood risk mapping and exercises its ability to require professional assessment and certification of construction under section 56 of the *Community Charter*. Map 4 shows minimum Flood Construction Levels for detailed reaches of the shoreline of the Ucluth Peninsula.

Lands in the vicinity of the coastal shoreline can be susceptible to flood hazard and, in certain areas, to erosion or sloughing. Lands that are or may be flooded represent a hazardous condition for people and permanent structures.

One of the effects of climate change is a rise in sea level. While experts using the best available science are still grappling with a range of possible impacts, current expectations are that the sea level on the west coast of Vancouver Island will rise somewhere in the vicinity of one metre by the year 2100. Any development along the coastline must take this into consideration in an attempt to anticipate and minimize any negative impacts that rising sea levels may have on the built environment and the safety of residents.

The west coast of Vancouver Island, identified as Zone C by the provincial Ministry of Public Safety and Solicitor General, is also a high-risk seismic zone, known to be vulnerable to flooding in the event of a tsunami. The District wishes to protect the community against the loss of lives and to minimize property damage, injury

and trauma associated with flooding events. Maps 5 and 6 show Tsunami Flood Vulnerability and Tsunami Flood Planning areas.

It is District policy that it is in the public interest for new subdivisions and developments to be planned to avoid areas of potential flood risk. Many of these areas are also of great habitat value and natural beauty, and have been incorporated into the potential future parks and open spaces shown on Schedules A and C.

Enforcement

No person shall do any act or suffer or permit any act or thing to be done in contravention of the Development Permit Area Designations and Guidelines adopted in Part 6 of this bylaw.

Every person who violates any of the provision of this bylaw, or who suffers or permits any act or thing to be done in contravention of this bylaw, is liable on summary conviction to a fine of not more than ten thousand dollars (\$10,000.00) and costs, including the costs of the committal and conveyances to the place of imprisonment, for each offence, and in default of payment therefore, to imprisonment of a term not exceeding six (6) months in jail, and each day that such violation is permitted to continue shall be a separate offence.

The Bylaw Enforcement Officer is authorized to inspect all work regulated by Development Permit Area designation under this bylaw, and compel and require compliance with the provisions of this bylaw. No person shall prevent or obstruct, or attempt to prevent or obstruct, the Bylaw Enforcement Officer, or any other employee of the District authorized to enforce the provisions of this bylaw.

A person who fails to comply with an order or notice issued by a Bylaw Enforcement Officer who allows a violation of this bylaw to continue, despite that order or notice, commits an offence.

A Bylaw Enforcement Officer may order the cessation of work that is proceeding in contravention of this bylaw by posting a Stop Work notice on the site of the work.

The Owner of property on which a Stop Work notice has been posted, and every other person, shall cease all construction or

development work immediately and shall not do any work on the property, except for such work as is necessary to remedy the reasons for the Stop Work notice with the agreement of the Bylaw Enforcement Officer, until all applicable provisions of the Development Permit Area Guidelines of this bylaw are substantially complied with and the Stop Work notice is rescinded in writing by a Bylaw Enforcement Officer.

Ticketing

Tickets for offences against the Development Permit Area Designations and Guidelines of this OCP bylaw may also be issued in accordance with the Municipal Ticket Information Bylaw in force at the time of the offence.

Part Seven: Appendices

Boilerplate (required content, legislation)

The purpose of the Official Community Plan (OCP) is to provide a long-term vision for the District of Ucluelet. It sets out broad objectives and policies that will guide planning and land use decisions within the District, while respecting the community's existing character.

The OCP charts a growth management course that supports Ucluelet's quality of life, enhances economic prosperity and advances environmental sustainability.

The Province of British Columbia's *Local Government Act* provides the authority and direction for the preparation of the Official Community Plan. Once adopted as a bylaw, an Official Community Plan has a legal status that requires that all subsequent bylaws enacted and works undertaken be consistent with the plan.

This Official Community Plan replaces the previous Official Community Plan, adopted in 2011.

Section 473 of the *Local Government Act* requires that an OCP include statements and map designations for the area covered by the plan for the following:

- the approximate location, amount, type and density of residential development required to meet anticipated housing needs over a period of at least 5 years;
- the approximate location, amount and type of present and proposed commercial, industrial, institutional, agricultural, recreational and public utility land uses;
- the approximate location and area of sand and gravel deposits that are suitable for future sand and gravel extraction;

- restrictions on the use of land that is subject to hazardous conditions or that is environmentally sensitive to development;
- the approximate location and phasing of any major road, sewer and water systems;
- the approximate location and type of present and proposed public facilities, including schools, parks and waste treatment and disposal site;
- housing policies of the local government respecting affordable housing, rental housing and special needs housing;
- targets for the reduction of greenhouse gas emissions in the area covered by the plan, and policies and actions of the local government proposed with respect to achieving those targets;

Section 474 of the *Local Government Act* allows that an OCP may also include statements on the following:

- policies of the local government relating to social needs, social well-being and social development;
- a regional context statement, consistent with the rest of the plan, of how matters referred to in a regional growth strategy, and other matters dealt with in the plan, apply in a regional context;
- policies of the local government respecting the maintenance and enhancement of farming on land in a farming area or in an area designated for agricultural use in the plan;
- policies of the local government relating to the preservation, protection, restoration and enhancement of

the natural environment, its ecosystems and biological diversity.

An OCP may also include general statements on matters outside the jurisdiction of a local government, dealing with issues of advocacy or general interest.

Planning Process

The Village of Ucluelet was incorporated in 1952 and became a District Municipality in 1997. The community adopted its first Official Community Plan (OCP) bylaw in 1971. The history of OCP's in Ucluelet is as follows:

- OCP Bylaw No. 235 (1971)
- OCP Bylaw No. 407 (1981)
- OCP Bylaw No. 498 (1988)
- OCP Bylaw No. 772 (1998)
- OCP Bylaw No. 900 (2004)
- OCP Bylaw No. 1140 (2011)


A review of the Ucluelet OCP bylaw was initiated by Council in 2016.

From 2016 through 2018 the District, along with students and faculty from Vancouver Island University's (VIU) Master of Community Planning program, collected community opinions on the OCP and the broad range of issues of interest to the community. A series of public engagement activities and events were held during this time, including "planning on the streets" events, pop-up planning workshops, stakeholder workshops with community groups and classes from the local schools. A three-day public consultation blitz in the spring of 2018, culminating in a large public open house, connected with 256 local residents.

Council initially received the draft OCP bylaw in September of 2018, at which point the bylaw received first reading. The 2018 municipal election, focus on pressing affordable housing issues and a robust community debate on new non-medical cannabis retail regulations – and then the onset of a global pandemic – all

Population Projections (low, medium and high growth projections):


Figure 2: Estimated and Projected Population, West Coast Region, 2015 – 2050



Source: Environics, 2020, BC Stats, and custom projections


Annual visitors

Figure 7: Average Annual Daily Traffic on Tofino-Ucluelet Hwy South of Ucluelet Junction, 2009 – 2019



Source: Ministry of Transportation and Infrastructure, 2020

Figure 14: Visitors, Pacific Rim National Park Reserve (Long Beach), 2003 – 2018



Source: Parks Canada, 2019

Definitions

“Bylaw Enforcement Officer”: means the Chief Administrative Officer of the District of Ucluelet and her or his designate.

“Development” includes:

- a) Removal, alteration, disruption, or destruction of vegetation;
- b) Disturbance of soils;
- c) Construction or erection of buildings and structures;
- d) Creation of non-structural impervious or semi-impervious surfaces;
- e) Flood protection works;
- f) Construction of roads, trails, docks, wharves, and bridges;
- g) Provision and maintenance of sewer and water services;
- h) Development of drainage systems;
- i) Development of utility corridors; and
- j) Subdivision as defined in the *Local Government Act*.

“Qualified Environmental Professional” (QEP): means an applied scientist or technologist, acting alone or together with another qualified environmental professional, if:

- 1) the individual is registered and in good standing in British Columbia with an appropriate professional organization constituted under an Act, acting under the association’s code of ethics and subject to disciplinary action by that association;
- 2) the individual is acting within that individual’s area of expertise; and,
- 3) the individual is acceptable to the District of Ucluelet.

With respect to item 2), above:

a) for Riparian Development Permit Areas: the individual’s area of expertise is recognized in the BC Riparian Areas Regulation assessment methods as one that is acceptable for the purpose of providing all or part of an assessment report in respect of that development proposal;

b) for Marine Shoreline Development Permit Areas, coastal and shoreline erosion aspects: a coastal geomorphologist, or a marine or metocean engineer with experience in coastal zone engineering; other professionals with experience in coastal processes and soft shore restorations may be considered on a case-by-case basis.

c) for Hazardous Conditions Development Permit Areas: a professional engineer with experience in geotechnical and slope stability engineering, or in flood protection design as the project may warrant.

Per the *Riparian Areas Protection Regulation* BC Reg 178/2019, s 21, a QEP may be:

- (i) an agrologist;
- (ii) an applied technologist or technician;
- (iii) a professional biologist;
- (iv) a professional engineer;
- (v) a professional forester;
- (vi) a professional geoscientist;
- (vi.1) a registered biology technologist;
- (vii) a registered forest technologist,

Stream: means the same as defined under the *Riparian Areas Protection Regulation*.

United Nations Declaration on the Rights of Indigenous Peoples

(Resolution adopted by the General Assembly on 13 September 2007)ⁱ

The General Assembly,

Guided by the purposes and principles of the Charter of the United Nations, and good faith in the fulfilment of the obligations assumed by States in accordance with the Charter,

Affirming that indigenous peoples are equal to all other peoples, while recognizing the right of all peoples to be different, to consider themselves different, and to be respected as such,

Affirming also that all peoples contribute to the diversity and richness of civilizations and cultures, which constitute the common heritage of humankind,

Affirming further that all doctrines, policies and practices based on or advocating superiority of peoples or individuals on the basis of national origin or racial, religious, ethnic or cultural differences are racist, scientifically false, legally invalid, morally condemnable and socially unjust,

Reaffirming that indigenous peoples, in the exercise of their rights, should be free from discrimination of any kind,

Concerned that indigenous peoples have suffered from historic injustices as a result of, inter alia, their colonization and dispossession of their lands, territories and resources, thus preventing them from exercising, in particular, their right to development in accordance with their own needs and interests,

Recognizing the urgent need to respect and promote the inherent rights of indigenous peoples which derive from their political, economic and social structures and from their cultures, spiritual traditions, histories and philosophies, especially their rights to their lands, territories and resources,

Recognizing also the urgent need to respect and promote the rights of indigenous peoples affirmed in treaties, agreements and other constructive arrangements with States,

Welcoming the fact that indigenous peoples are organizing themselves for political, economic, social and cultural enhancement and in order to bring to an end all forms of discrimination and oppression wherever they occur,

Convinced that control by indigenous peoples over developments affecting them and their lands, territories and resources will enable them to maintain and strengthen their institutions, cultures and traditions, and to promote their development in accordance with their aspirations and needs,

Recognizing that respect for indigenous knowledge, cultures and traditional practices contributes to sustainable and equitable development and proper management of the environment,

Emphasizing the contribution of the demilitarization of the lands and territories of indigenous peoples to peace, economic and social progress and development, understanding and friendly relations among nations and peoples of the world,

Recognizing in particular the right of indigenous families and communities to retain shared responsibility for the upbringing, training, education and well-being of their children, consistent with the rights of the child,

Considering that the rights affirmed in treaties, agreements and other constructive arrangements between States and indigenous peoples are, in some situations, matters of international concern, interest, responsibility and character,

Considering also that treaties, agreements and other constructive arrangements, and the relationship they represent, are the basis for a strengthened partnership between indigenous peoples and States,

Acknowledging that the Charter of the United Nations, the International Covenant on Economic, Social and Cultural Rightsⁱⁱ and the International Covenant on Civil and Political Rights, as well as the Vienna Declaration and Programme of Action,ⁱⁱⁱ affirm the fundamental importance of the right to self-determination of all peoples, by virtue of which they freely determine their political status and freely pursue their economic, social and cultural development,

Bearing in mind that nothing in this Declaration may be used to deny any peoples their right to self-determination, exercised in conformity with international law,

Convinced that the recognition of the rights of indigenous peoples in this Declaration will enhance harmonious and cooperative relations between the State and indigenous peoples, based on principles of justice, democracy, respect for human rights, non-discrimination and good faith,

Encouraging States to comply with and effectively implement all their obligations as they apply to indigenous peoples under international instruments, in particular those related to human rights, in consultation and cooperation with the peoples concerned,

Emphasizing that the United Nations has an important and continuing role to play in promoting and protecting the rights of indigenous peoples,

Believing that this Declaration is a further important step forward for the recognition, promotion and protection of the rights and freedoms of indigenous peoples and in the development of relevant activities of the United Nations system in this field,

Recognizing and reaffirming that indigenous individuals are entitled without discrimination to all human rights recognized in international law, and that indigenous peoples possess collective rights which are indispensable for their existence, well-being and integral development as peoples,

Recognizing that the situation of indigenous peoples varies from region to region and from country to country and that the significance of national and regional particularities and various historical and cultural backgrounds should be taken into consideration,

Solemnly proclaims the following United Nations Declaration on the Rights of Indigenous Peoples as a standard of achievement to be pursued in a spirit of partnership and mutual respect:

Article 1

Indigenous peoples have the right to the full enjoyment, as a collective or as individuals, of all human rights and fundamental freedoms as recognized in the Charter of the United Nations, the Universal Declaration of Human Rights^{iv} and international human rights law.

Article 2

Indigenous peoples and individuals are free and equal to all other peoples and individuals and have the right to be free from any kind of discrimination, in the exercise of their rights, in particular that based on their indigenous origin or identity.

Article 3

Indigenous peoples have the right to self-determination. By virtue of that right they freely determine their political status and freely pursue their economic, social and cultural development.

Article 4

Indigenous peoples, in exercising their right to self-determination, have the right to autonomy or self-government in matters relating to their internal and local affairs, as well as ways and means for financing their autonomous functions.

Article 5

Indigenous peoples have the right to maintain and strengthen their distinct political, legal, economic, social and cultural institutions, while retaining their right to participate fully, if they so choose, in the political, economic, social and cultural life of the State.

Article 6

Every indigenous individual has the right to a nationality.

Article 7

1. Indigenous individuals have the rights to life, physical and mental integrity, liberty and security of person.

2. Indigenous peoples have the collective right to live in freedom, peace and security as distinct peoples and shall not be subjected to any act of genocide or any other act of violence, including forcibly removing children of the group to another group.

Article 8

1. Indigenous peoples and individuals have the right not to be subjected to forced assimilation or destruction of their culture.

2. States shall provide effective mechanisms for prevention of, and redress for:

(a) Any action which has the aim or effect of depriving them of their integrity as distinct peoples, or of their cultural values or ethnic identities;

(b) Any action which has the aim or effect of dispossessing them of their lands, territories or resources;

(c) Any form of forced population transfer which has the aim or effect of violating or undermining any of their rights;

(d) Any form of forced assimilation or integration;

(e) Any form of propaganda designed to promote or incite racial or ethnic discrimination directed against them.

Article 9

Indigenous peoples and individuals have the right to belong to an indigenous community or nation, in accordance with the traditions and customs of the community or nation concerned. No discrimination of any kind may arise from the exercise of such a right.

Article 10

Indigenous peoples shall not be forcibly removed from their lands or territories. No relocation shall take place without the free, prior and informed consent of the indigenous peoples concerned and after agreement on just and fair compensation and, where possible, with the option of return.

Article 11

1. Indigenous peoples have the right to practise and revitalize their cultural traditions and customs. This includes the right to maintain, protect and develop the past, present and future manifestations of their cultures, such as archaeological and historical sites, artefacts, designs, ceremonies, technologies and visual and performing arts and literature.

2. States shall provide redress through effective mechanisms, which may include restitution, developed in conjunction with indigenous peoples, with respect to their cultural, intellectual, religious and spiritual property taken without their free, prior and informed consent or in violation of their laws, traditions and customs.

Article 12

1. Indigenous peoples have the right to manifest, practise, develop and teach their spiritual and religious traditions, customs and ceremonies; the right to maintain, protect, and have access in privacy to their religious and cultural sites; the right to the use and control of their ceremonial objects; and the right to the repatriation of their human remains.

2. States shall seek to enable the access and/or repatriation of ceremonial objects and human remains in their possession

through fair, transparent and effective mechanisms developed in conjunction with indigenous peoples concerned.

Article 13

1. Indigenous peoples have the right to revitalize, use, develop and transmit to future generations their histories, languages, oral traditions, philosophies, writing systems and literatures, and to designate and retain their own names for communities, places and persons.
2. States shall take effective measures to ensure that this right is protected and also to ensure that indigenous peoples can understand and be understood in political, legal and administrative proceedings, where necessary through the provision of interpretation or by other appropriate means.

Article 14

1. Indigenous peoples have the right to establish and control their educational systems and institutions providing education in their own languages, in a manner appropriate to their cultural methods of teaching and learning.
2. Indigenous individuals, particularly children, have the right to all levels and forms of education of the State without discrimination.
3. States shall, in conjunction with indigenous peoples, take effective measures, in order for indigenous individuals, particularly children, including those living outside their communities, to have access, when possible, to an education in their own culture and provided in their own language.

Article 15

1. Indigenous peoples have the right to the dignity and diversity of their cultures, traditions, histories and aspirations which shall be appropriately reflected in education and public information.
2. States shall take effective measures, in consultation and cooperation with the indigenous peoples concerned, to combat prejudice and eliminate discrimination and to promote tolerance, understanding and good relations among indigenous peoples and all other segments of society.

Article 16

1. Indigenous peoples have the right to establish their own media in their own languages and to have access to all forms of non-indigenous media without discrimination.
2. States shall take effective measures to ensure that State-owned media duly reflect indigenous cultural diversity. States, without prejudice to ensuring full freedom of expression, should encourage privately owned media to adequately reflect indigenous cultural diversity.

Article 17

1. Indigenous individuals and peoples have the right to enjoy fully all rights established under applicable international and domestic labour law.
2. States shall in consultation and cooperation with indigenous peoples take specific measures to protect indigenous children from economic exploitation and from performing any work that is likely to be hazardous or to interfere with the child's education, or to be harmful to the child's health or physical, mental, spiritual, moral or social development, taking into account their special

vulnerability and the importance of education for their empowerment.

3. Indigenous individuals have the right not to be subjected to any discriminatory conditions of labour and, inter alia, employment or salary.

Article 18

Indigenous peoples have the right to participate in decision-making in matters which would affect their rights, through representatives chosen by themselves in accordance with their own procedures, as well as to maintain and develop their own indigenous decision-making institutions.

Article 19

States shall consult and cooperate in good faith with the indigenous peoples concerned through their own representative institutions in order to obtain their free, prior and informed consent before adopting and implementing legislative or administrative measures that may affect them.

Article 20

1. Indigenous peoples have the right to maintain and develop their political, economic and social systems or institutions, to be secure in the enjoyment of their own means of subsistence and development, and to engage freely in all their traditional and other economic activities.

2. Indigenous peoples deprived of their means of subsistence and development are entitled to just and fair redress.

Article 21

1. Indigenous peoples have the right, without discrimination, to the improvement of their economic and social conditions, including, inter alia, in the areas of education, employment, vocational training and retraining, housing, sanitation, health and social security.

2. States shall take effective measures and, where appropriate, special measures to ensure continuing improvement of their economic and social conditions. Particular attention shall be paid to the rights and special needs of indigenous elders, women, youth, children and persons with disabilities.

Article 22

1. Particular attention shall be paid to the rights and special needs of indigenous elders, women, youth, children and persons with disabilities in the implementation of this Declaration.

2. States shall take measures, in conjunction with indigenous peoples, to ensure that indigenous women and children enjoy the full protection and guarantees against all forms of violence and discrimination.

Article 23

Indigenous peoples have the right to determine and develop priorities and strategies for exercising their right to development. In particular, indigenous peoples have the right to be actively involved in developing and determining health, housing and other economic and social programmes affecting them and, as far as possible, to administer such programmes through their own institutions.

Article 24

1. Indigenous peoples have the right to their traditional medicines and to maintain their health practices, including the conservation of their vital medicinal plants, animals and minerals. Indigenous individuals also have the right to access, without any discrimination, to all social and health services.
2. Indigenous individuals have an equal right to the enjoyment of the highest attainable standard of physical and mental health. States shall take the necessary steps with a view to achieving progressively the full realization of this right.

Article 25

Indigenous peoples have the right to maintain and strengthen their distinctive spiritual relationship with their traditionally owned or otherwise occupied and used lands, territories, waters and coastal seas and other resources and to uphold their responsibilities to future generations in this regard.

Article 26

1. Indigenous peoples have the right to the lands, territories and resources which they have traditionally owned, occupied or otherwise used or acquired.
2. Indigenous peoples have the right to own, use, develop and control the lands, territories and resources that they possess by reason of traditional ownership or other traditional occupation or use, as well as those which they have otherwise acquired.
3. States shall give legal recognition and protection to these lands, territories and resources. Such recognition shall be conducted with due respect to the customs, traditions and land tenure systems of the indigenous peoples concerned.

Article 27

States shall establish and implement, in conjunction with indigenous peoples concerned, a fair, independent, impartial, open and transparent process, giving due recognition to indigenous peoples' laws, traditions, customs and land tenure systems, to recognize and adjudicate the rights of indigenous peoples pertaining to their lands, territories and resources, including those which were traditionally owned or otherwise occupied or used. Indigenous peoples shall have the right to participate in this process.

Article 28

1. Indigenous peoples have the right to redress, by means that can include restitution or, when this is not possible, just, fair and equitable compensation, for the lands, territories and resources which they have traditionally owned or otherwise occupied or used, and which have been confiscated, taken, occupied, used or damaged without their free, prior and informed consent.
2. Unless otherwise freely agreed upon by the peoples concerned, compensation shall take the form of lands, territories and resources equal in quality, size and legal status or of monetary compensation or other appropriate redress.

Article 29

1. Indigenous peoples have the right to the conservation and protection of the environment and the productive capacity of their lands or territories and resources. States shall establish and implement assistance programmes for indigenous peoples for such conservation and protection, without discrimination.

2. States shall take effective measures to ensure that no storage or disposal of hazardous materials shall take place in the lands or territories of indigenous peoples without their free, prior and informed consent.

3. States shall also take effective measures to ensure, as needed, that programmes for monitoring, maintaining and restoring the health of indigenous peoples, as developed and implemented by the peoples affected by such materials, are duly implemented.

Article 30

1. Military activities shall not take place in the lands or territories of indigenous peoples, unless justified by a relevant public interest or otherwise freely agreed with or requested by the indigenous peoples concerned.

2. States shall undertake effective consultations with the indigenous peoples concerned, through appropriate procedures and in particular through their representative institutions, prior to using their lands or territories for military activities.

Article 31

1. Indigenous peoples have the right to maintain, control, protect and develop their cultural heritage, traditional knowledge and traditional cultural expressions, as well as the manifestations of their sciences, technologies and cultures, including human and genetic resources, seeds, medicines, knowledge of the properties of fauna and flora, oral traditions, literatures, designs, sports and traditional games and visual and performing arts. They also have the right to maintain, control, protect and develop their intellectual property over such cultural heritage, traditional knowledge, and traditional cultural expressions.

2. In conjunction with indigenous peoples, States shall take effective measures to recognize and protect the exercise of these rights.

Article 32

1. Indigenous peoples have the right to determine and develop priorities and strategies for the development or use of their lands or territories and other resources.

2. States shall consult and cooperate in good faith with the indigenous peoples concerned through their own representative institutions in order to obtain their free and informed consent prior to the approval of any project affecting their lands or territories and other resources, particularly in connection with the development, utilization or exploitation of mineral, water or other resources.

3. States shall provide effective mechanisms for just and fair redress for any such activities, and appropriate measures shall be taken to mitigate adverse environmental, economic, social, cultural or spiritual impact.

Article 33

1. Indigenous peoples have the right to determine their own identity or membership in accordance with their customs and traditions. This does not impair the right of indigenous individuals to obtain citizenship of the States in which they live.

2. Indigenous peoples have the right to determine the structures and to select the membership of their institutions in accordance with their own procedures.

Article 34

Indigenous peoples have the right to promote, develop and maintain their institutional structures and their distinctive customs, spirituality, traditions, procedures, practices and, in the cases where they exist, juridical systems or customs, in accordance with international human rights standards.

Article 35

Indigenous peoples have the right to determine the responsibilities of individuals to their communities.

Article 36

1. Indigenous peoples, in particular those divided by international borders, have the right to maintain and develop contacts, relations and cooperation, including activities for spiritual, cultural, political, economic and social purposes, with their own members as well as other peoples across borders.
2. States, in consultation and cooperation with indigenous peoples, shall take effective measures to facilitate the exercise and ensure the implementation of this right.

Article 37

1. Indigenous peoples have the right to the recognition, observance and enforcement of treaties, agreements and other constructive arrangements concluded with States or their successors and to have States honour and respect such treaties, agreements and other constructive arrangements.
2. Nothing in this Declaration may be interpreted as diminishing or eliminating the rights of indigenous peoples contained in treaties, agreements and other constructive arrangements.

Article 38

States in consultation and cooperation with indigenous peoples, shall take the appropriate measures, including legislative measures, to achieve the ends of this Declaration.

Article 39

Indigenous peoples have the right to have access to financial and technical assistance from States and through international cooperation, for the enjoyment of the rights contained in this Declaration.

Article 40

Indigenous peoples have the right to access to and prompt decision through just and fair procedures for the resolution of conflicts and disputes with States or other parties, as well as to effective remedies for all infringements of their individual and collective rights. Such a decision shall give due consideration to the customs, traditions, rules and legal systems of the indigenous peoples concerned and international human rights.

Article 41

The organs and specialized agencies of the United Nations system and other intergovernmental organizations shall contribute to the full realization of the provisions of this Declaration through the mobilization, inter alia, of financial cooperation and technical assistance. Ways and means of ensuring participation of indigenous peoples on issues affecting them shall be established.

Article 42

The United Nations, its bodies, including the Permanent Forum on Indigenous Issues, and specialized agencies, including at the country level, and States shall promote respect for and full application of the provisions of this Declaration and follow up the effectiveness of this Declaration.

Article 43

The rights recognized herein constitute the minimum standards for the survival, dignity and well-being of the indigenous peoples of the world.

Article 44

All the rights and freedoms recognized herein are equally guaranteed to male and female indigenous individuals.

Article 45

Nothing in this Declaration may be construed as diminishing or extinguishing the rights indigenous peoples have now or may acquire in the future.

ⁱ See Official Records of the General Assembly, Sixty-first Session, Supplement No. 53 (A/61/53), part one, chap. II, sect. A.

ⁱⁱ See resolution 2200 A (XXI), annex.

Article 46

1. Nothing in this Declaration may be interpreted as implying for any State, people, group or person any right to engage in any activity or to perform any act contrary to the Charter of the United Nations or construed as authorizing or encouraging any action which would dismember or impair, totally or in part, the territorial integrity or political unity of sovereign and independent States.

2. In the exercise of the rights enunciated in the present Declaration, human rights and fundamental freedoms of all shall be respected. The exercise of the rights set forth in this Declaration shall be subject only to such limitations as are determined by law and in accordance with international human rights obligations. Any such limitations shall be non-discriminatory and strictly necessary solely for the purpose of securing due recognition and respect for the rights and freedoms of others and for meeting the just and most compelling requirements of a democratic society.

3. The provisions set forth in this Declaration shall be interpreted in accordance with the principles of justice, democracy, respect for human rights, equality, non-discrimination, good governance and good faith.

ⁱⁱⁱ A/CONF.157/24 (Part I), chap. III.

^{iv} Resolution 217 A (III).

